

**CONSTRUCTION MANAGER
AT RISK SERVICES FOR
THE NEW FULTON
COUNTY ANIMAL
SHELTER FACILITY**

**#21RFP22421K-DB
11/18/2021**

**GUARANTEED
MAXIMUM
PRICE
PROPOSAL**



TABLE OF CONTENTS

- A** DRAWINGS AND SPEC LOGS
- B** GMP COST
- C** CLARIFICATIONS AND ASSUMPTIONS
- D** ALLOWANCES (INCLUDED IN EXHIBIT C)
- E** PAYMENT AND PERFORMANCE BONDS
NOT INCLUDED - TO BE INCLUDED WITH FINAL GMP AMENDMENT
- F** CERTIFICATE OF INSURANCE
NOT INCLUDED - TO BE INCLUDED WITH FINAL GMP AMENDMENT
- G** PURCHASING FORMS
NOT INCLUDED - TO BE INCLUDED WITH FINAL GMP AMENDMENT
- H** OFFICE OF CONTRACT COMPLIANCE
NOT INCLUDED - TO BE INCLUDED WITH FINAL GMP AMENDMENT
- I** CONTRACT SCHEDULE



EXHIBIT A

DRAWING AND SPEC LOGS

Drawing Log

Project: (21-123) Fulton County Animal Services
Owner: Fulton County Government
Architect: PGAL

| Type | Sheet | Title | Stamp Date |
|---------------|-------|--|------------|
| General | G0.00 | Cover Sheet - Volume 1 | 10/8/2021 |
| General | G0.01 | Sheet Index, General Project Information | 10/8/2021 |
| General | G1.00 | Code Analysis | 10/8/2021 |
| General | G1.10 | Life Safety Plan - Overall | 10/8/2021 |
| General | G1.11 | Life Safety Plan - Sector A | 10/8/2021 |
| General | G1.12 | Life Safety Plan - Sector B | 10/8/2021 |
| General | G1.13 | Life Safety Plan - Sector C | 10/8/2021 |
| General | G1.14 | Life Safety Plan - Sector D | 10/8/2021 |
| General | G1.20 | Accessibility Information | 10/8/2021 |
| General | G1.21 | Accessibility Information | 10/8/2021 |
| Civil | C0.00 | Cover | 10/8/2021 |
| Civil | C0.01 | General Notes | 10/8/2021 |
| Civil | C0.02 | Survey | 10/8/2021 |
| Civil | C2.00 | Demolition Plan | 10/8/2021 |
| Civil | C2.01 | Detailed Demolition Plan | 10/8/2021 |
| Civil | C2.02 | Detailed Demolition Plan | 10/8/2021 |
| Civil | C3.00 | Master Site Plan | 10/8/2021 |
| Civil | C3.01 | Detailed Site Plan | 10/8/2021 |
| Civil | C3.02 | Detailed Site Plan | 10/8/2021 |
| Civil | C3.40 | Fire Access Plan | 10/8/2021 |
| Civil | C3.41 | Truck Access Plan | 10/8/2021 |
| Civil | C4.00 | Grading Plan | 10/8/2021 |
| Civil | C4.01 | Detailed Grading Plan | 10/8/2021 |
| Civil | C4.02 | Detailed Grading Plan | 10/8/2021 |
| Civil | C4.40 | Stormwater Management Plan | 10/8/2021 |
| Civil | C4.41 | Stormwater Management Plan | 10/8/2021 |
| Civil | C5.00 | Utility Plan | 10/8/2021 |
| Civil | C5.01 | Detailed Utility Plan | 10/8/2021 |
| Civil | C5.02 | Detailed Utility Plan | 10/8/2021 |
| Civil | C6.00 | Erosion Notes | 10/8/2021 |
| Civil | C6.01 | Erosion Notes | 10/8/2021 |
| Civil | C6.02 | Erosion Notes | 10/8/2021 |
| Civil | C6.10 | Phase I Erosion Control Plan | 10/8/2021 |
| Civil | C6.11 | Phase I Erosion Control Plan | 10/8/2021 |
| Civil | C6.12 | Phase I Erosion Control Plan | 10/8/2021 |
| Civil | C6.20 | Phase II Erosion Control Plan | 10/8/2021 |
| Civil | C6.21 | Phase II Erosion Control Plan | 10/8/2021 |
| Civil | C6.22 | Phase II Erosion Control Plan | 10/8/2021 |
| Civil | C6.30 | Phase III Erosion Control Plan | 10/8/2021 |
| Civil | C6.31 | Phase III Erosion Control Plan | 10/8/2021 |
| Civil | C6.32 | Phase III Erosion Control Plan | 10/8/2021 |
| Civil | C6.40 | Erosion Control Details | 10/8/2021 |
| Civil | C6.41 | Erosion Control Details | 10/8/2021 |
| Civil | C6.42 | Erosion Control Details | 10/8/2021 |
| Civil | C6.43 | Erosion Control Details | 10/8/2021 |
| Civil | C7.00 | Sanitary Sewer Profiles | 10/8/2021 |
| Civil | C7.50 | Storm Profiles | 10/8/2021 |
| Civil | C7.51 | Storm Profiles | 10/8/2021 |
| Civil | C7.52 | Storm Profiles | 10/8/2021 |
| Civil | C8.00 | Sight Distance Profiles | 10/8/2021 |
| Civil | C8.01 | Sight Distance Profiles | 10/8/2021 |
| Civil | C9.00 | Construction Details | 10/8/2021 |
| Civil | C9.01 | Construction Details | 10/8/2021 |
| Civil | C9.02 | Construction Details | 10/8/2021 |
| Architectural | A0.10 | Partition Types | 10/8/2021 |
| Architectural | A0.30 | Door Schedule | 10/8/2021 |
| Architectural | A0.31 | Door And Frame Types | 10/8/2021 |
| Architectural | A0.32 | Door Details - Exterior | 10/8/2021 |
| Architectural | A0.33 | Door Details - Interior | 10/8/2021 |
| Architectural | A0.34 | Door Details - Interior | 10/8/2021 |

| Type | Sheet | Title | Stamp Date |
|---------------|--------|--|------------|
| Architectural | A0.40 | Window & Storefront Types/Schedule | 10/8/2021 |
| Architectural | A0.41 | Curtain Wall & Storefront Elevations | 10/8/2021 |
| Architectural | A0.42 | Window Details | 10/8/2021 |
| Architectural | A0.43 | Interior Window Details | 10/8/2021 |
| Architectural | A1.00 | Architectural Site Plan (Overall) | 10/8/2021 |
| Architectural | A1.10 | Architectural Site Plan (Enlarged) | 10/8/2021 |
| Architectural | A1.15 | Site Plan - Public Parking Lot | 10/8/2021 |
| Architectural | A1.15B | Site Plan - Public Parking Lot | 10/8/2021 |
| Architectural | A1.16 | Site Plan - Employee Parking Lot | 10/8/2021 |
| Architectural | A1.17 | Site Plan - Dog Yards | 10/8/2021 |
| Architectural | A1.18 | Enlarged Barn Plan | 10/8/2021 |
| Architectural | A1.19 | Site Plan - Details | 10/8/2021 |
| Architectural | A1.20 | Architectural Site Sections/Details | 10/8/2021 |
| Architectural | A2.00 | Slab Plan | 10/8/2021 |
| Architectural | A2.01 | Slab Plan - Sector A | 10/8/2021 |
| Architectural | A2.02 | Slab Plan - Sector B | 10/8/2021 |
| Architectural | A2.03 | Slab Plan - Sector C | 10/8/2021 |
| Architectural | A2.04 | Slab Plan - Sector D | 10/8/2021 |
| Architectural | A2.10 | Overall Floor Plan | 10/8/2021 |
| Architectural | A2.11 | Floor Plan - Sector A | 10/8/2021 |
| Architectural | A2.11D | Dimension Floor Plan - Sector A | 10/8/2021 |
| Architectural | A2.12 | Floor Plan - Sector B | 10/8/2021 |
| Architectural | A2.12D | Dimension Floor Plan - Sector B | 10/8/2021 |
| Architectural | A2.13 | Floor Plan - Sector C | 10/8/2021 |
| Architectural | A2.13D | Dimension Floor Plan - Sector C | 10/8/2021 |
| Architectural | A2.14 | Floor Plan - Sector D | 10/8/2021 |
| Architectural | A2.14D | Dimension Floor Plan - Sector D | 10/8/2021 |
| Architectural | A2.20 | Overall Roof Plan | 10/8/2021 |
| Architectural | A2.21 | Roof Plan - Section A | 10/8/2021 |
| Architectural | A2.22 | Roof Plan - Section B | 10/8/2021 |
| Architectural | A2.23 | Roof Plan - Section C | 10/8/2021 |
| Architectural | A2.24 | Roof Plan - Section D | 10/8/2021 |
| Architectural | A2.60 | Drain Details | 10/8/2021 |
| Architectural | A3.10 | Overall Reflected Ceiling Plan | 10/8/2021 |
| Architectural | A3.11 | Reflected Ceiling Plan - Sector A | 10/8/2021 |
| Architectural | A3.12 | Reflected Ceiling Plan - Sector B | 10/8/2021 |
| Architectural | A3.13 | Reflected Ceiling Plan - Sector C | 10/8/2021 |
| Architectural | A3.14 | Reflected Ceiling Plan - Sector D | 10/8/2021 |
| Architectural | A3.20 | Details - Ceilings | 10/8/2021 |
| Architectural | A4.10 | Enlarged Restroom Plans And Elevations | 10/8/2021 |
| Architectural | A4.11 | Enlarged Restroom Plans And Elevations | 10/8/2021 |
| Architectural | A5.10 | Exterior Plan Details - Sector A | 10/8/2021 |
| Architectural | A5.10B | Exterior Plan Details - Sector A | 10/8/2021 |
| Architectural | A5.11 | Exterior Plan Details - Sector B | 10/8/2021 |
| Architectural | A5.12 | Exterior Plan Details - Sector C | 10/8/2021 |
| Architectural | A5.13 | Exterior Plan Details - Sector D | 10/8/2021 |
| Architectural | A6.10 | Overall Exterior Elevations | 10/8/2021 |
| Architectural | A6.12 | Enlarged Facade Elevations | 10/8/2021 |
| Architectural | A6.13 | Enlarged Facade Elevations | 10/8/2021 |
| Architectural | A6.20 | Enlarged Exterior Elevations | 10/8/2021 |
| Architectural | A7.10 | Overall Building Sections | 10/8/2021 |
| Architectural | A7.11 | Enlarged Building Sections | 10/8/2021 |
| Architectural | A7.12 | Enlarged Building Sections | 10/8/2021 |
| Architectural | A7.13 | Enlarged Building Sections | 10/8/2021 |
| Architectural | A7.20 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.21 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.22 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.23 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.24 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.25 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.26 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.27 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.28 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.29 | Exterior Wall Sections | 10/8/2021 |
| Architectural | A7.30 | Exterior Wall Sections | 10/8/2021 |

| Type | Sheet | Title | Stamp Date |
|---------------|--------|--|------------|
| Architectural | A7.50 | Exterior Wall Details | 10/8/2021 |
| Architectural | A7.51 | Exterior Wall Details | 10/8/2021 |
| Architectural | A7.52 | Exterior Wall Details | 10/8/2021 |
| Architectural | A7.53 | Exterior Wall Details | 10/8/2021 |
| Architectural | A7.54 | Exterior Wall Details | 10/8/2021 |
| Architectural | A7.75 | Exterior Wall Details | 10/8/2021 |
| Architectural | A7.56 | Exterior Wall Details | 10/8/2021 |
| Architectural | A7.57 | Exterior Wall Details | 10/8/2021 |
| Architectural | A7.58 | Exterior Wall Details | 10/8/2021 |
| Architectural | A8.10 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.11 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.12 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.13 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.14 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.15 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.16 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.17 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.18 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.19 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.20 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.21 | Elevations - Interior | 10/8/2021 |
| Architectural | A8.50 | Interior Details - Millwork | 10/8/2021 |
| Architectural | A8.51 | Interior Details - Millwork | 10/8/2021 |
| Architectural | A8.52 | Interior Details - Millwork | 10/8/2021 |
| Architectural | A8.53 | Interior Details | 10/8/2021 |
| Architectural | A9.01 | Equipment Details | 10/8/2021 |
| Architectural | A9.02 | Animal Housing Details | 10/8/2021 |
| Architectural | A9.03 | Animal Housing Details | 10/8/2021 |
| Architectural | A9.04 | Animal Housing Details | 10/8/2021 |
| Architectural | A9.05 | Animal Housing Details | 10/8/2021 |
| Architectural | A9.06 | Caging Schedule And Elevations | 10/8/2021 |
| Architectural | A9.10 | Finish Schedule And Room Finish Schedule | 10/8/2021 |
| Architectural | A9.11 | Finish Plan - Sector A | 10/8/2021 |
| Architectural | A9.12 | Finish Plan - Sector B | 10/8/2021 |
| Architectural | A9.13 | Finish Plan - Sector C | 10/8/2021 |
| Architectural | A9.14 | Finish Plan - Sector D | 10/8/2021 |
| Architectural | A10.01 | Equipment Plan - Sector A | 10/8/2021 |
| Architectural | A10.02 | Equipment Plan - Sector B | 10/8/2021 |
| Architectural | A10.03 | Equipment Plan - Sector C | 10/8/2021 |
| Architectural | A10.04 | Equipment Plan - Sector D | 10/8/2021 |
| Architectural | A10.11 | Equipment Schedule | 10/8/2021 |
| Structural | S0.01 | General Notes | 10/8/2021 |
| Structural | S0.02 | General Notes | 10/8/2021 |
| Structural | S0.03 | Wind Load Diagram | 10/8/2021 |
| Structural | S0.04 | Gid Geometry Plan | 10/8/2021 |
| Structural | S0.05 | Isometric Views - Overall | 10/8/2021 |
| Structural | S0.06 | Isometric Views - Partial Lobby | 10/8/2021 |
| Structural | S2.10 | Overall Foundation Plan | 10/8/2021 |
| Structural | S2.11 | Foundation Plan - Sector A | 10/8/2021 |
| Structural | S2.12 | Foundation Plan - Sector B | 10/8/2021 |
| Structural | S2.13 | Foundation Plan - Sector C | 10/8/2021 |
| Structural | S2.14 | Foundation Plan - Sector D | 10/8/2021 |
| Structural | S2.20 | Overall Roof Plan | 10/8/2021 |
| Structural | S2.21 | Roof Framing Plan - Sector A | 10/8/2021 |
| Structural | S2.22 | Roof Framing Plan - Sector B | 10/8/2021 |
| Structural | S2.23 | Roof Framing Plan - Sector C | 10/8/2021 |
| Structural | S2.24 | Roof Framing Plan - Sector D | 10/8/2021 |
| Structural | S2.30 | Pre-Manufactured Barn Foundation | 10/8/2021 |
| Structural | S3.01 | Typical Foundation Details | 10/8/2021 |
| Structural | S3.02 | Typical Foundation Details | 10/8/2021 |
| Structural | S3.03 | Typical Foundation Details | 10/8/2021 |
| Structural | S3.04 | Typical Foundation Details | 10/8/2021 |
| Structural | S3.05 | Foundation Details | 10/8/2021 |
| Structural | S3.06 | Foundation Details | 10/8/2021 |
| Structural | S4.01 | Masonry Details | 10/8/2021 |

| Type | Sheet | Title | Stamp Date |
|------------|-------|---|------------|
| Structural | S4.02 | Masonry Details | 10/8/2021 |
| Structural | S5.01 | Typical Steel Details | 10/8/2021 |
| Structural | S5.02 | Typical Steel Details | 10/8/2021 |
| Structural | S5.03 | Typical Steel Details | 10/8/2021 |
| Structural | S5.04 | Typical Steel Details | 10/8/2021 |
| Structural | S5.05 | Framing Details | 10/8/2021 |
| Structural | S5.06 | Framing Details | 10/8/2021 |
| Structural | S5.07 | Framing Details | 10/8/2021 |
| Structural | S5.08 | Framing Details | 10/8/2021 |
| Structural | S5.09 | Framing Details | 10/8/2021 |
| Structural | S6.01 | Building Sections | 10/8/2021 |
| Structural | S6.02 | Building Sections | 10/8/2021 |
| Structural | S6.03 | Building Sections | 10/8/2021 |
| Structural | S7.01 | Enlarged Plans And Sections - Canopy At Employee Patio | 10/8/2021 |
| Structural | S7.02 | Enlarged Plans And Sections - Canopy At Intake Lobby | 10/8/2021 |
| Structural | S7.03 | Enlarged Plans And Sections - Canopy At Catio | 10/8/2021 |
| Structural | S7.04 | Enlarged Plans And Sections - Canopy West Of Quart. Dog Kennels | 10/8/2021 |
| Structural | S7.05 | Enlarged Plans And Sections - Canopy East Of Quart. Dog Kennels | 10/8/2021 |
| Structural | S7.06 | Enlarged Plans And Sections - Canopy At Dog Yards 3 | 10/8/2021 |
| Structural | S7.07 | Enlarged Plans And Sections - Canopy At Dog Yards 4 | 10/8/2021 |
| Structural | S7.08 | Enlarged Plans And Sections - Canopy At Dog Yards 5 | 10/8/2021 |
| Structural | S7.09 | Enlarged Plans And Sections - Canopy At Dog Yards 6 | 10/8/2021 |
| Structural | S8.01 | Wall Elevations | 10/8/2021 |
| Structural | S8.02 | Wall Elevations | 10/8/2021 |
| Structural | S8.03 | Wall Elevations | 10/8/2021 |
| Structural | S8.04 | Wall Elevations | 10/8/2021 |
| Structural | S8.05 | Wall Elevations | 10/8/2021 |
| Structural | S8.06 | Wall Elevations | 10/8/2021 |
| Structural | S8.07 | Wall Elevations | 10/8/2021 |
| Structural | S8.08 | Wall Elevations | 10/8/2021 |
| Structural | S8.09 | Wall Elevations | 10/8/2021 |
| Mechanical | M1.01 | Mechanical Cover Sheet | 10/8/2021 |
| Mechanical | M1.02 | Mechanical General Notes | 10/8/2021 |
| Mechanical | M1.03 | Mechanical Schedules | 10/8/2021 |
| Mechanical | M1.04 | Mechanical Schedules | 10/8/2021 |
| Mechanical | M1.05 | Mechanical Schedules | 10/8/2021 |
| Mechanical | M1.06 | Mech. Vent. Calcs | 10/8/2021 |
| Mechanical | M1.07 | Mechanical Zoning Plan | 10/8/2021 |
| Mechanical | M2.10 | Mechanical Ductwork Overall Floor Plan | 10/8/2021 |
| Mechanical | M2.11 | Mechanical Ductwork Plan - Sector A | 10/8/2021 |
| Mechanical | M2.12 | Mechanical Ductwork Plan - Sector B | 10/8/2021 |
| Mechanical | M2.13 | Mechanical Ductwork Plan - Sector C | 10/8/2021 |
| Mechanical | M2.14 | Mechanical Ductwork Plan - Sector D | 10/8/2021 |
| Mechanical | M2.20 | Mechanical Ductwork Overall Roof Plan | 10/8/2021 |
| Mechanical | M2.21 | Mechanical Ductwork Roof Plan - Sector A | 10/8/2021 |
| Mechanical | M2.22 | Mechanical Ductwork Roof Plan - Sector B | 10/8/2021 |
| Mechanical | M2.23 | Mechanical Ductwork Roof Plan - Sector C | 10/8/2021 |
| Mechanical | M2.24 | Mechanical Ductwork Roof Plan - Sector D | 10/8/2021 |
| Mechanical | M3.10 | Mechanical Overall Piping Floor Plan | 10/8/2021 |
| Mechanical | M3.11 | Mechanical Piping Plan - Sector A | 10/8/2021 |
| Mechanical | M3.12 | Mechanical Piping Plan - Sector B | 10/8/2021 |
| Mechanical | M3.20 | Mechanical Piping Overall Roof Plan | 10/8/2021 |
| Mechanical | M4.01 | Mechanical Details | 10/8/2021 |
| Mechanical | M4.02 | Mechanical Details | 10/8/2021 |
| Mechanical | M4.03 | Mechanical Details | 10/8/2021 |
| Mechanical | M4.04 | Mechanical Piping Schematics | 10/8/2021 |
| Mechanical | M4.05 | Mechanical Sequence Of Operations | 10/8/2021 |
| Mechanical | M4.06 | Mechanical Sequence Of Operations | 10/8/2021 |
| Electrical | E0.00 | Electrical Cover Sheet | 10/8/2021 |
| Electrical | E1.01 | Overall Electrical Site Plan | 10/8/2021 |
| Electrical | E1.02 | Enlarged Electrical Site Plan - East | 10/8/2021 |
| Electrical | E1.03 | Enlarged Electrical Site Plan - West | 10/8/2021 |
| Electrical | E1.10 | Overall - Electrical Floor Plan | 10/8/2021 |
| Electrical | E2.10 | Sector A - Electrical Power Plan | 10/8/2021 |
| Electrical | E2.11 | Sector B - Electrical Power Plan | 10/8/2021 |

| Type | Sheet | Title | Stamp Date |
|------------|-------|--------------------------------------|------------|
| Electrical | E2.12 | Sector C - Electrical Power Plan | 10/8/2021 |
| Electrical | E2.13 | Sector D - Electrical Power Plan | 10/8/2021 |
| Electrical | E2.20 | West Side - Electrical Roof Plan | 10/8/2021 |
| Electrical | E2.21 | East Side - Electrical Roof Plan | 10/8/2021 |
| Electrical | E3.10 | Sector A - Electrical Lighting Plan | 10/8/2021 |
| Electrical | E3.11 | Sector B - Electrical Lighting Plan | 10/8/2021 |
| Electrical | E3.12 | Sector C - Electrical Lighting Plan | 10/8/2021 |
| Electrical | E3.13 | Sector D - Electrical Lighting Plan | 10/8/2021 |
| Electrical | E6.01 | Electrical One-Line Diagram | 10/8/2021 |
| Electrical | E6.02 | Technology Riser Diagram | 10/8/2021 |
| Electrical | E7.01 | Electrical Schedules | 10/8/2021 |
| Electrical | E7.10 | Electrical Panel Schedules | 10/8/2021 |
| Electrical | E7.11 | Electrical Panel Schedules | 10/8/2021 |
| Electrical | E7.12 | Electrical Panel Schedules | 10/8/2021 |
| Electrical | E7.13 | Electrical Panel Schedules | 10/8/2021 |
| Electrical | E7.14 | Electrical Panel Schedules | 10/8/2021 |
| Electrical | E8.01 | Electrical Lighting Schedules | 10/8/2021 |
| Electrical | E8.02 | Lighting Control Schedules & Details | 10/8/2021 |
| Electrical | E9.00 | Electrical Lighting Compliance | 10/8/2021 |
| Electrical | T0.00 | Technology General Notes | 10/8/2021 |
| Electrical | T1.01 | Technology Site Plan | 10/8/2021 |
| Electrical | T2.10 | Sector A - Technology Plan | 10/8/2021 |
| Electrical | T2.11 | Sector B - Technology Plan | 10/8/2021 |
| Electrical | T2.12 | Sector C - Technology Plan | 10/8/2021 |
| Electrical | T2.13 | Sector D - Technology Plan | 10/8/2021 |
| Electrical | T2.20 | Technology Enlarged Plans | 10/8/2021 |
| Electrical | T3.20 | AV Detail Sheet | 10/8/2021 |
| Electrical | T3.21 | AV Detail Sheet | 10/8/2021 |
| Electrical | T3.22 | AV Detail Sheet | 10/8/2021 |
| Electrical | T3.23 | AV Detail Sheet | 10/8/2021 |
| Electrical | T3.24 | AV Detail Sheet | 10/8/2021 |
| Electrical | T4.00 | Technology Schedules | 10/8/2021 |
| Electrical | T5.01 | Technology Riser Diagram | 10/8/2021 |
| Electrical | T5.02 | AV Detail Sheet | 10/8/2021 |
| Electrical | T5.03 | AV Detail Sheet | 10/8/2021 |
| Electrical | T5.04 | AV Detail Sheet | 10/8/2021 |
| Electrical | T6.01 | Technology Detail | 10/8/2021 |
| Electrical | T6.02 | Technology Detail | 10/8/2021 |
| Electrical | T6.03 | Technology Detail | 10/8/2021 |
| Electrical | T6.04 | AV Detail Sheet | 10/8/2021 |
| Plumbing | P1.01 | Plumbing Cover Sheet | 10/8/2021 |
| Plumbing | P1.02 | Plumbing General Notes | 10/8/2021 |
| Plumbing | P1.03 | Plumbing Equipment Schedules | 10/8/2021 |
| Plumbing | P1.04 | Plumbing Equipment Schedules | 10/8/2021 |
| Plumbing | P2.10 | Overall Underground Plumbing Plan | 10/8/2021 |
| Plumbing | P2.11 | Underground Plumbing Plan - Sector A | 10/8/2021 |
| Plumbing | P2.12 | Underground Plumbing Plan - Sector B | 10/8/2021 |
| Plumbing | P2.13 | Underground Plumbing Plan - Sector C | 10/8/2021 |
| Plumbing | P2.14 | Underground Plumbing Plan - Sector D | 10/8/2021 |
| Plumbing | P2.20 | Plumbing Overall Main Floor Plan | 10/8/2021 |
| Plumbing | P2.21 | Plumbing Main Floor Plan - Sector A | 10/8/2021 |
| Plumbing | P2.22 | Plumbing Main Floor Plan - Sector B | 10/8/2021 |
| Plumbing | P2.23 | Plumbing Main Floor Plan - Sector C | 10/8/2021 |
| Plumbing | P2.24 | Plumbing Main Floor Plan - Sector D | 10/8/2021 |
| Plumbing | P2.30 | Plumbing Overall Roof Plan | 10/8/2021 |
| Plumbing | P2.31 | Plumbing Roof Plan - Sector A | 10/8/2021 |
| Plumbing | P2.32 | Plumbing Roof Plan - Sector B | 10/8/2021 |
| Plumbing | P2.33 | Plumbing Roof Plan - Sector C | 10/8/2021 |
| Plumbing | P2.34 | Plumbing Roof Plan - Sector D | 10/8/2021 |
| Plumbing | P3.00 | Enlarged Medical Gas Plan - Sector B | 10/8/2021 |
| Plumbing | P3.01 | Enlarged Plumbing Plans | 10/8/2021 |
| Plumbing | P3.02 | Plumbing Details | 10/8/2021 |
| Plumbing | P4.00 | Plumbing Details | 10/8/2021 |
| Plumbing | P4.01 | Plumbing Details | 10/8/2021 |
| Plumbing | P4.02 | Plumbing Details | 10/8/2021 |

| Type | Sheet | Title | Stamp Date |
|-----------------|--------|--|------------|
| Plumbing | P5.00 | Overall Waste And Vent Isometric | 10/8/2021 |
| Plumbing | P5.01 | Overall Domestic Water Isometric | 10/8/2021 |
| Plumbing | P5.10 | Enlarged Plumbing Isometrics - Sector A1 | 10/8/2021 |
| Plumbing | P5.11 | Enlarged Plumbing Isometrics - Sector A2 | 10/8/2021 |
| Plumbing | P5.12 | Enlarged Plumbing Isometrics - Sector B1 | 10/8/2021 |
| Plumbing | P5.13 | Enlarged Plumbing Isometrics - Sector B2 | 10/8/2021 |
| Plumbing | P5.14 | Enlarged Plumbing Isometrics - Sector C1 | 10/8/2021 |
| Plumbing | P5.15 | Enlarged Plumbing Isometrics - Sector C2 | 10/8/2021 |
| Plumbing | P5.16 | Enlarged Plumbing Isometrics - Sector D1 | 10/8/2021 |
| Plumbing | P5.17 | Enlarged Plumbing Isometrics - Sector D2 | 10/8/2021 |
| Plumbing | P5.18 | Natural Gas Piping Isometric | 10/8/2021 |
| Fire Protection | FP1.0 | Fire Sprinkler General Info & Site Plan | 10/8/2021 |
| Fire Protection | FP1.1 | Fire Sprinkler Hanger Details | 10/8/2021 |
| Fire Protection | FP2.0 | Fire Sprinkler Piping Plan Overall | 10/8/2021 |
| Fire Protection | FP2.1 | Fire Sprinkler Piping Plan Sector A | 10/8/2021 |
| Fire Protection | FP2.2 | Fire Sprinkler Piping Plan Sector B | 10/8/2021 |
| Fire Protection | FP2.3 | Fire Sprinkler Piping Plan Sector C | 10/8/2021 |
| Fire Protection | FP2.4 | Fire Sprinkler Piping Plan Sector D | 10/8/2021 |
| Fire Alarm | FA1.10 | Overall Floor Plan | 10/8/2021 |
| Fire Alarm | FA1.11 | Fire Alarm Plan - Sector A | 10/8/2021 |
| Fire Alarm | FA1.12 | Fire Alarm Plan - Sector B | 10/8/2021 |
| Fire Alarm | FA1.13 | Fire Alarm Plan - Sector C | 10/8/2021 |
| Fire Alarm | FA1.14 | Fire Alarm Plan - Sector D | 10/8/2021 |
| Landscape | L1.0 | Landscape Plan - West | 10/8/2021 |
| Landscape | L2.0 | Landscape Plan - East | 10/8/2021 |
| Landscape | L3.0 | Landscape Plan Enlargement | 10/8/2021 |
| Landscape | L4.0 | Landscape Notes And Schedule | 10/8/2021 |
| Landscape | L5.0 | Landscape Details | 10/8/2021 |

11/18/2021

Specifications Log: 21-123 - Fulton County Animal Services

Project Owner: Fulton County Government
Architect: PGAL
Project Number: 21-123

| Spec # | Spec Title | Issue Date | Latest Revision | Revision Number |
|-----------|---|------------|-----------------|-----------------|
| 000000 | Covers | 10/08/2021 | | |
| 000103 | Design Team | 10/08/2021 | | |
| 000105 | Table Of Contents | 10/08/2021 | | |
| 000107.01 | Certification And Seal Sheet - Architectural | 10/08/2021 | | |
| 000107.02 | Certification And Seal Sheet - Structural | 10/08/2021 | | |
| 000107.04 | Certification And Seal Sheet - Plumbing | 10/08/2021 | | |
| 000107.05 | Certification And Seal Sheet - Mechanical | 10/08/2021 | | |
| 000107.06 | Certification And Seal Sheet - Electrical | 10/08/2021 | | |
| 000107.07 | Certification And Seal Sheet - Civil | 10/08/2021 | | |
| 000107.08 | Certification And Seal Sheet - Landscape Architect | 10/08/2021 | | |
| 011000 | Summary (pgal) | 10/08/2021 | | |
| 012500 | Substitution Procedures (pgal) | 10/08/2021 | | |
| 012600 | Contract Modification Procedures (pgal) | 10/08/2021 | | |
| 012900 | Payment Procedures (pgal) | 10/08/2021 | | |
| 013100 | Project Management And Coordination (pgal) | 10/08/2021 | | |
| 013200 | Construction Progress Documentation (pgal) | 10/08/2021 | | |
| 013233 | Photographic Documentation (pgal) | 10/08/2021 | | |
| 013300 | Submittal Procedures (pgal) | 10/08/2021 | | |
| 014000 | Quality Requirements (pgal) | 10/08/2021 | | |
| 014200 | References (pgal) | 10/08/2021 | | |
| 014533 | Structural Testing And Special Inspections Services (sci) | 10/08/2021 | | |
| 015000 | Temporary Facilities And Controls (pgal) | 10/08/2021 | | |
| 016000 | Product Requirements (pgal) | 10/08/2021 | | |
| 017300 | Execution (pgal) | 10/08/2021 | | |
| 017700 | Closeout Procedures (pgal) | 10/08/2021 | | |
| 017823 | Operation And Maintenance Data (pgal) | 10/08/2021 | | |
| 017839 | Project Record Documents (pgal) | 10/08/2021 | | |
| 017900 | Demonstration And Training (pgal) | 10/08/2021 | | |
| 018113 | Sustainability Requirements (ice) | 10/08/2021 | | |
| 018114 | LEED Scorecard And Responsibility Matrix (ice) | 10/08/2021 | | |
| 018115 | Sustainability Materials Coversheet (SMC) (ice) | 10/08/2021 | | |
| 018118 | Indoor Air Quality Requirements (ice) | 10/08/2021 | | |
| 018119 | Construction And Demolition Waste Management Plan (ice) | 10/08/2021 | | |
| 018120 | LEED Material Performance Requirements (ice) | 10/08/2021 | | |
| 019113 | General Commissioning Requirements (eg) | 10/08/2021 | | |
| 027920 | Loose-Fill Rubber Mulch Surfacing (aa) | 10/08/2021 | | |
| 031000 | Concrete Forming And Accessories (sci) | 10/08/2021 | | |

11/18/2021

| Spec # | Spec Title | Issue Date | Latest Revision | Revision Number |
|-----------|--|------------|-----------------|-----------------|
| 032000 | Concrete Reinforcing (sci) | 10/08/2021 | | |
| 033000 | Cast-In-Place Concrete (sci) | 10/08/2021 | | |
| 033543 | Polished Concrete Finishing (pgal) | 10/08/2021 | | |
| 033660 | Sealed Concrete (aa) | 10/08/2021 | | |
| 042000 | Unit Masonry (pgal) | 10/08/2021 | | |
| 042200 | Concrete Unit Masonry (sci) | 10/08/2021 | | |
| 051200 | Structural Steel Framing (sci) | 10/08/2021 | | |
| 051213 | Architecturally Exposed Structural Steel Framing (sci) | 10/08/2021 | | |
| 052100 | Steel Joist Framing (sci) | 10/08/2021 | | |
| 053100 | Steel Decking (sci) | 10/08/2021 | | |
| 054000 | Cold-Formed Metal Framing (sci) | 10/08/2021 | | |
| 055000 | Metal Fabrications (pgal) | 10/08/2021 | | |
| 061000 | Rough Carpentry (aa) | 10/08/2021 | | |
| 061600 | Sheathing (pgal) | 10/08/2021 | | |
| 064116 | Plastic-Laminate-Faced Architectural Cabinets (aa) | 10/08/2021 | | |
| 066400 | Plastic Paneling (pgal) | 10/08/2021 | | |
| 068300 | Composite Siding (pgal) | 10/08/2021 | | |
| 068313 | Thermoplastic Resin Panels (pgal) | 10/08/2021 | | |
| 071113 | Bituminous Dampproofing | 10/08/2021 | | |
| 072100 | Thermal Insulation | 10/08/2021 | | |
| 072726 | Fluid-Applied Membrane Air Barriers | 10/08/2021 | | |
| 074213.13 | Formed Metal Wall Panels | 10/08/2021 | | |
| 074213.23 | Metal Composite Material Wall And Soffit Panels | 10/08/2021 | | |
| 075423 | Thermoplastic-Polyolefin (TPO) Roofing | 10/08/2021 | | |
| 076200 | Sheet Metal Flashing And Trim | 10/08/2021 | | |
| 077100 | Roof Specialties | 10/08/2021 | | |
| 077129 | Manufactured Roof Expansion Joints | 10/08/2021 | | |
| 077200 | Roof Accessories | 10/08/2021 | | |
| 078413 | Penetration Firestopping | 10/08/2021 | | |
| 078446 | Joint Resistant Joint Systems (aa) | 10/08/2021 | | |
| 079200 | Joint Sealants (aa) | 10/08/2021 | | |
| 079219 | Acoustical Joint Sealants (aa) | 10/08/2021 | | |
| 079513.13 | Interior Expansion Joint Cover Assemblies | 10/08/2021 | | |
| 079513.16 | Exterior Expansion Joint Cover Assemblies | 10/08/2021 | | |
| 081113 | Hollow Metal Doors And Frames (aa) | 10/08/2021 | | |
| 081613 | Fiberglass Reinforced Doors And Frames (pgal) | 10/08/2021 | | |
| 083113 | Access Doors And Frames (pgal) | 10/08/2021 | | |
| 083323 | Overhead Coiling Doors (pgal) | 10/08/2021 | | |
| 083330 | Overhead Coiling Grilles (aa) | 10/08/2021 | | |
| 083613 | Sectional Doors (aa) | 10/08/2021 | | |
| 084113 | Aluminum-Framed Entrances And Storefronts (pgal) | 10/08/2021 | | |
| 084243 | Traffic Doors (aa) | 10/08/2021 | | |

11/18/2021

| Spec # | Spec Title | Issue Date | Latest Revision | Revision Number |
|-----------|---|------------|-----------------|-----------------|
| 084413 | Glazed Aluminum Curtain Walls (pgal) | 10/08/2021 | | |
| 085313 | Sliding Windows (aa) | 10/08/2021 | | |
| 086250 | Tubular Daylighting Devices (aa) | 10/08/2021 | | |
| 087100 | Door Hardware (pgal) | 10/08/2021 | | |
| 088000 | Glazing (aa) | 10/08/2021 | | |
| 092216 | Interior Non-Structural Metal Framing (aa) | 10/08/2021 | | |
| 092900 | Gypsum Board (aa) | 10/08/2021 | | |
| 093000 | Tiling (aa) | 10/08/2021 | | |
| 095113 | Acoustical Panel Ceilings (aa) | 10/08/2021 | | |
| 096513 | Resilient Base And Accessories (aa) | 10/08/2021 | | |
| 096516 | Resilient Sheet Flooring (pgal) | 10/08/2021 | | |
| 096517 | Resilient Sheet Safety Flooring (aa) | 10/08/2021 | | |
| 096723 | Resinous Flooring (aa) | 10/08/2021 | | |
| 097200 | Wall Coverings (pgal) | 10/08/2021 | | |
| 098433 | Sound-Absorbing Wall Units (aa) | 10/08/2021 | | |
| 099113 | Exterior Painting (pgal) | 10/08/2021 | | |
| 099123 | Interior Painting (pgal) | 10/08/2021 | | |
| 099600 | High-Performance Coatings (aa) | 10/08/2021 | | |
| 101000 | Slatwall Display Wall (aa) | 10/08/2021 | | |
| 101100 | Visual Display Units (pgal) | 10/08/2021 | | |
| 101419 | Dimensional Letter Signage (pgal) | 10/08/2021 | | |
| 101423 | Panel Signage (pgal) | 10/08/2021 | | |
| 102113.17 | Phenolic-Core Toilet Partitions (pgal) | 10/08/2021 | | |
| 102219 | Demountable Partitions (pgal) | 10/08/2021 | | |
| 102226 | Operational Partitions (aa) | 10/08/2021 | | |
| 102600 | Wall And Door Protection (aa) | 10/08/2021 | | |
| 102800 | Toilet And Bath Accessories (pgal) | 10/08/2021 | | |
| 104413 | Fire Extinguisher Cabinets (aa) | 10/08/2021 | | |
| 104416 | Fire Extinguishers (aa) | 10/08/2021 | | |
| 105113 | Metal Lockers (aa) | 10/08/2021 | | |
| 107316.06 | Metal Entrance Canopies (pgal) | 10/08/2021 | | |
| 111200 | Parking Control Equipment (pgal) | 10/08/2021 | | |
| 111323 | Portable Dock Equipment (pgal) | 10/08/2021 | | |
| 112000 | Animal Care Equipment (aa) | 10/08/2021 | | |
| 113100 | Appliances (pgal) | 10/08/2021 | | |
| 114000 | Foodservice Equipment (aa) | 10/08/2021 | | |
| 115213 | Projection Screens (pgal) | 10/08/2021 | | |
| 122413 | Roller Window Shades (aa) | 10/08/2021 | | |
| 123616 | Metal Countertops (aa) | 10/08/2021 | | |
| 123623.13 | Plastic-Laminate-Clad Countertops (aa) | 10/08/2021 | | |
| 123661 | Solid-Surface-Material Countertops And Sills (aa) | 10/08/2021 | | |
| 123662 | Quartz Agglomerate Countertops And Sills (aa) | 10/08/2021 | | |

11/18/2021

| Spec # | Spec Title | Issue Date | Latest Revision | Revision Number |
|-----------|---|------------|-----------------|-----------------|
| 133423 | Prefabrication Barns (aa) | 10/08/2021 | | |
| 211000 | Fire Suppression (tec) | 10/08/2021 | | |
| 220010 | General Requirements (2020) | 10/08/2021 | | |
| 220513 | Common Motor Requirements For Plumbing Equipment (2020) | 10/08/2021 | | |
| 220516 | Expansion Fittings And Loops For Plumbing Piping (2020) | 10/08/2021 | | |
| 220517 | Sleeves And Sleeve Seals For Plumbing Piping (2020) | 10/08/2021 | | |
| 220518 | Escutcheons For Plumbing Piping (2020) | 10/08/2021 | | |
| 220519 | Meters And Gages For Plumbing Piping (2020) | 10/08/2021 | | |
| 220523.12 | Ball Valves For Plumbing Piping (2020) | 10/08/2021 | | |
| 220523.13 | Butterfly Valves For Plumbing Piping (2020) | 10/08/2021 | | |
| 220523.14 | Check Valves For Plumbing Piping (2020) | 10/08/2021 | | |
| 220529 | Hangers And Supports For Plumbing Piping And Equipment (2020) | 10/08/2021 | | |
| 220553 | Identification For Plumbing Piping And Equipment (2020) | 10/08/2021 | | |
| 220593 | Testing, Adjusting, And Balancing For Plumbing (2020) | 10/08/2021 | | |
| 220719 | Plumbing Piping Insulation (2020) | 10/08/2021 | | |
| 220800 | Plumbing Systems Commissioning (eg) | 10/08/2021 | | |
| 220963 | Medical Gas Alarms (2020) | 10/08/2021 | | |
| 221116 | Domestic Water Piping (2020) | 10/08/2021 | | |
| 221119 | Domestic Water Piping Specialties (2020) | 10/08/2021 | | |
| 221123.21 | Inline, Domestic-Water Pumps (2020) | 10/08/2021 | | |
| 221316 | Sanitary Waste And Vent Piping (2020) | 10/08/2021 | | |
| 221330 | Sand-Oil Interceptors (2020) | 10/08/2021 | | |
| 221413 | Facility Storm Drainage Piping (2020) | 10/08/2021 | | |
| 221623 | Facility Natural-Gas Piping (2020) | 10/08/2021 | | |
| 223400 | Fuel-Fired, Domestic-Water Heaters (2020) | 10/08/2021 | | |
| 224213 | Commercial Plumbing Fixtures (2020) | 10/08/2021 | | |
| 226313 | Gas And Vacuum Piping For Animal Healthcare Facilities (2020) | 10/08/2021 | | |
| 230010 | General Requirements (2020) | 10/08/2021 | | |
| 230513 | Common Motor Requirements For HVAC Equipment (2020) | 10/08/2021 | | |
| 230517 | Sleeves And Sleeve Seals For HVAC Piping (2020) | 10/08/2021 | | |
| 230529 | Hangers And Supports For HVAC Piping And Equipment (2020) | 10/08/2021 | | |
| 230713 | Duct Insulation (2020) | 10/08/2021 | | |
| 230719 | HVAC Piping Insulation (2020) | 10/08/2021 | | |
| 230800 | Mechanical Systems Commissioning (eg) | 10/08/2021 | | |
| 230923 | Direct Digital Control (DDC) System For HVAC (2020) | 10/08/2021 | | |
| 232113 | Hydronic Piping (2020) | 10/08/2021 | | |
| 232116 | Hydronic Piping Specialties (2020) | 10/08/2021 | | |
| 232123 | Hydronic Pumps (2020) | 10/08/2021 | | |
| 232300 | Video Surveillance (aed) | 10/08/2021 | | |
| 233113 | Metal Ducts (2020) | 10/08/2021 | | |
| 233413 | Grilles, Registers, And Diffusers (2020) | 10/08/2021 | | |
| 233423 | Fans (2020) | 10/08/2021 | | |

11/18/2021

| Spec # | Spec Title | Issue Date | Latest Revision | Revision Number |
|-----------|---|------------|-----------------|-----------------|
| 233600 | Air Terminal Units (2020) | 10/08/2021 | | |
| 235216 | Condensing Boilers (2020) | 10/08/2021 | | |
| 236423.05 | Air-Cooled, Heat Recovery Chillers (2020) | 10/08/2021 | | |
| 237223 | Outdoor, Air-Handling Units (2020) | 10/08/2021 | | |
| 237223.29 | Packaged, Outdoor, Fixed Plate Energy Recovery Units (2020) | 10/08/2021 | | |
| 237343.01 | Packages, Outdoor, HW-CW Coil, Dedicated Outdoor Air Units (2020) | 10/08/2021 | | |
| 238126 | Ductless Split-System Air-Conditioners (2020) | 10/08/2021 | | |
| 238239.17 | Propeller Unit Heaters (2020) | 10/08/2021 | | |
| 260500 | Common Work Results For Electrical (aed) | 10/08/2021 | | |
| 260519 | Low-Voltage Electrical Power Conductors And Cables (aed) | 10/08/2021 | | |
| 260526 | Grounding And Bonding For Electrical Systems (aed) | 10/08/2021 | | |
| 260529 | Hangers And Supports For Electrical Systems (aed) | 10/08/2021 | | |
| 260533 | Raceways And Boxes For Electrical Systems (aed) | 10/08/2021 | | |
| 260553 | Identification For Electrical Systems (aed) | 10/08/2021 | | |
| 260800 | Electrical Systems Commissioning (eg) | 10/08/2021 | | |
| 262213 | Low-Voltage Distribution Transformers (aed) | 10/08/2021 | | |
| 262413 | Switchboards (aed) | 10/08/2021 | | |
| 262416 | Panelboards (aed) | 10/08/2021 | | |
| 262726 | Wiring Devices (aed) | 10/08/2021 | | |
| 262813 | Fuses (aed) | 10/08/2021 | | |
| 262816 | Enclosed Switches And Circuit Breakers (aed) | 10/08/2021 | | |
| 263213.14 | Diesel Engine Generators (aed) | 10/08/2021 | | |
| 263600 | Transfer Switches (aed) | 10/08/2021 | | |
| 264113 | Lightning Protection For Structures (aed) | 10/08/2021 | | |
| 265119 | LED Interior Lighting (aed) | 10/08/2021 | | |
| 265219 | Emergency And Exit Lighting (aed) | 10/08/2021 | | |
| 265619 | LED Exterior Lighting (aed) | 10/08/2021 | | |
| 270526 | Grounding And Bonding For Communications Systems (aed) | 10/08/2021 | | |
| 270536 | Cable Trays For Communications Systems (aed) | 10/08/2021 | | |
| 271100 | Communications Equipment Room Fittings (aed) | 10/08/2021 | | |
| 271313 | Communications Copper Backbone Cabling (aed) | 10/08/2021 | | |
| 271333 | Communications Coaxial Backbone Cabling (aed) | 10/08/2021 | | |
| 271513 | Communications Copper Horizontal Cabling (aed) | 10/08/2021 | | |
| 271533 | Communications Coaxial Horizontal Cabling (aed) | 10/08/2021 | | |
| 274100 | Audio-Visual Systems (aed) | 10/08/2021 | | |
| 274122 | Cabling For Audio-Visual Systems (aed) | 10/08/2021 | | |
| 274181 | Audio-Visual Control System (aed) | 10/08/2021 | | |
| 281300 | Access Control (aed) | 10/08/2021 | | |
| 281305 | Video Intercom System (aed) | 10/08/2021 | | |
| 284621.11 | Addressable Fire-Alarm Systems (tec) | 10/08/2021 | | |
| 311000 | Site Clearing (lowe) | 10/08/2021 | | |
| 311200 | Aggregate Piers (sci) | 10/08/2021 | | |

| Spec # | Spec Title | Issue Date | Latest Revision | Revision Number |
|--------|------------------------------------|------------|-----------------|-----------------|
| 312000 | Earth Moving (lowe) | 10/08/2021 | | |
| 312210 | Building Earthwork (sci) | 10/08/2021 | | |
| 313116 | Termite Control (pgal) | 10/08/2021 | | |
| 321216 | Asphalt Paving (lowe) | 10/08/2021 | | |
| 321313 | Concrete Paving (lowe) | 10/08/2021 | | |
| 321400 | Unit Paving (pgal) | 10/08/2021 | | |
| 321813 | Synthetic Grass Surfacing (aa) | 10/08/2021 | | |
| 323110 | Ornamental Fencing (aa) | 10/08/2021 | | |
| 323113 | Chain Link Fences And Gates (aa) | 10/08/2021 | | |
| 323119 | Decorative Fences And Gates (pgal) | 10/08/2021 | | |
| 323120 | Paddock Fending (aa) | 10/08/2021 | | |
| 329223 | Sodding (gf) | 10/08/2021 | | |
| 329310 | Landscape Plantings (gf) | 10/08/2021 | | |
| 334200 | Stormwater Conveyance (lowe) | 10/08/2021 | | |



GEOTECHNICAL EXPLORATION REPORT

Fulton County Animal Services Building

Fulton Industrial Boulevard

Atlanta, Georgia

Lot Number: 17 0268 LL0317

Prepared for:

Department of Real Estate and Asset Management

Fulton County Government Center

141 Pryor Street, SW

Suite 6001

Atlanta, Georgia 30303

Prepared by:

Wood Environment & Infrastructure Solutions, Inc.

2677 Buford Hwy. NE

Atlanta, GA 30324

July 2, 2020

Project No. 6162-20-1408

Copyright © 2020 by Wood Environment & Infrastructure Solutions, Inc.

All rights reserved.



Wood Environment & Infrastructure Solutions, Inc.
2677 Buford Highway NE
Atlanta, Georgia 30324
T: 404-873-4761
www.woodplc.com

July 2, 2020

Mr. Bill Mason
Facilities Program Manager
Department of Real Estate and Asset Management
Fulton County Government Center
141 Pryor Street, SW
Suite 6001
Atlanta, Georgia 30303

Subject: **Report of Geotechnical Exploration
Fulton County Animal Services Building
Fulton Industrial Boulevard
Atlanta, Georgia
Wood Project: 6162201408**

Dear Mr. Mason:

Wood Environment and Infrastructure Solutions, Inc. (Wood) is pleased to submit this report of Geotechnical Exploration for above-referenced property in Atlanta, Fulton County, Georgia. This exploration was conducted in general accordance with Wood's Proposal dated March 13, 2020.

This report briefly discusses our understanding of the project, describes our exploratory procedures and results, and presents our conclusions and recommendations related to the project design and construction. We appreciate your selection of Wood for this project and look forward to assisting you further on this and other projects. If you have any questions, please contact us.

Sincerely,

Wood Environment & Infrastructure Solutions, Inc.

Kayla Andrews, E.I.T.
Geotechnical Specialist

Pieter DePree, PE
Sr. Assoc. Geotechnical Engineer



Exhibit A - Attachment C **Fulton County Animal Shelter**

Fulton County Animal Services Building
Atlanta, Georgia
Geotechnical Investigation Report

TABLE OF CONTENTS

| | Page |
|--|-------------|
| 1.0 INTRODUCTION..... | 1 |
| 1.1 Site Description | 1 |
| 1.2 Project Description | 1 |
| 1.3 Field Exploration | 1 |
| 2.0 SUBSURFACE CONDITIONS..... | 2 |
| 2.1 Area and Site Geology | 2 |
| 2.2 Site Stratigraphy | 2 |
| 2.2.1 Topsoil3 | |
| 2.2.2 Residual Soils..... | 3 |
| 2.2.3 Partially Weathered Rock and Refusal Materials | 3 |
| 2.2.4 Groundwater..... | 4 |
| 3.0 CONCLUSIONS AND RECOMMENDATIONS..... | 4 |
| 3.1 Site Preparation | 4 |
| 3.2 Excavation | 4 |
| 3.3 Ground and Surface Water Controls | 4 |
| 3.4 Fill Placement | 5 |
| 3.5 Low Consistency Soils | 5 |
| 3.6 Foundation Recommendations..... | 5 |
| 3.7 Retaining Walls..... | 6 |
| 3.8 Slabs..... | 7 |
| 3.9 Pavement Recommendations | 7 |
| 3.10 Seismic Design Parameters | 7 |
| 4.0 QUALIFICATIONS OF RECOMMENDATIONS..... | 8 |

FIGURES

- Figure 1 Site Location Plan
- Figure 2 Boring Location Plan

APPENDIX

- Field and Laboratory Procedures
- Key to Symbols and Descriptions
- Soil Test Boring Records
- Laboratory Test Records
- GBA Information about Geotechnical Reports



GEOTECHNICAL EXPLORATION REPORT

Proposed Project: Fulton County Animal Services Building
Fulton Industrial Boulevard
Atlanta, GA

1.0 INTRODUCTION

Wood has completed a geotechnical exploration for the proposed construction of the new Fulton County Animal Services Building (FCASB), located on Fulton Industrial Boulevard in Atlanta, Georgia. The objective of the exploration was to assess the subsurface conditions in the area of the proposed new development and to analyze these conditions as they relate to foundation design and construction. This report briefly discusses our understanding of the project, describes our exploratory procedures and presents our conclusions and recommendations.

1.1 SITE DESCRIPTION

We understand the following based on documents provided by Don Green of CBRE-Heery. The site is a triangular shaped, approximately 44.2-acre parcel located just east of Charlie Brown Airport along Fulton Industrial Boulevard, west of Bolton Road (see Figure 1). It is bounded to the northwest by Fulton Industrial Boulevard, to the east by a power line easement, and to the south by undeveloped tracts that are part of a runway protection zone for the airport and which contain a drainage feature.

The site is undeveloped and partially wooded with a thick growth of young trees. Aerial photos show no evidence of significant previous development or grading but indicate the site was cleared in 2014-15 and large amounts of mulch were left around the site surface. Much of this mulch remains on the site. Site grades vary from high points around elevation 826 feet in the northern corner sloping down to the south and southwest to a low point of about 782 feet in a drainage at the extreme south corner.

1.2 PROJECT DESCRIPTION

The building will be a large (roughly 500 by 200 feet out-to-out), single-story, metal frame structure facing Fulton Industrial Boulevard with parking areas to the northeast and southwest (see Figure 2). A barn will be located near the southwestern corner of the site. Landscape areas, including outdoor exercise yards, will be located in front of and behind the building. Detailed grading information is not yet available, but the finished floor elevation is anticipated to be about 806 feet elevation (NGVD) and surrounding drives, parking, and yard areas will likely be near this, such that excavation up to about 20 feet and fill up to about 15 feet is anticipated to level the site. Excavation for utility trenches is also likely. We are not aware of plans for basements, but site retaining walls to allow grade changes around the building to better match existing site topography are likely and may be up to 15 feet high. Building load details were not provided but we anticipate column loads of 200 kips or less and wall loads of 5 kips per linear foot based on experience with similar construction.

1.3 FIELD EXPLORATION

Fifteen soil test borings were drilled to depths between 22 and 30 feet. Standard penetration tests were performed using a CME-55 drill rig utilizing and automatic hammer. The boring locations

Exhibit A - Attachment C Fulton County Animal Shelter

Fulton County Animal Services Building
Atlanta, Georgia
Geotechnical Investigation Report

were located in the field by a geotechnical engineer using coordinates obtained from Google Earth and a handheld GPS unit with a positional error of about 15 feet. Boring elevations were interpolated based on the provided site topographic plan. Since these methods are imprecise, the boring elevations and the boring locations (shown on the Boring Location Plan, Figure 2) should be considered approximate.

The Soil Test Boring Records in the Appendix graphically show the penetration resistances and present the soil descriptions for selected SPT borings. The stratification lines and depth designations on the boring records represent the approximate boundaries between soil types. Transitions between soils may be gradual. Brief descriptions of the exploratory drilling and sampling techniques used are presented in the Field and Laboratory Procedures section of the Appendix.

2.0 SUBSURFACE CONDITIONS

The subsurface conditions discussed in the following paragraphs and those shown on the Soil Test Boring Records represent an interpretation of the boring and other data using normally accepted geotechnical engineering judgments considering local geology and experience.

2.1 AREA AND SITE GEOLOGY

The project site is in the Piedmont Physiographic Province, an area underlain by metamorphic rocks with localized igneous intrusions. The residual soils encountered in the Piedmont are the product of in-place chemical and physical weathering of the parent rock. Typically, weathering is most advanced at the surface and decreases with depth. This results in a residual soil profile consisting of slightly clayey soils near the surface underlain by sandy silts and silty sands that generally become harder or denser and coarser with depth to the top of the unweathered bedrock. In deeper residual soil strata, known as saprolites, the banded structural appearance of the parent rock is typically evident.

The boundary between soil and rock in the Piedmont is typically not sharply defined. A transitional zone termed "partially weathered rock" is normally found overlying bedrock. Partially weathered rock (PWR) is arbitrarily defined for engineering purposes as residual material with a standard penetration resistance exceeding 100 blows per foot (bpf). Weathering is facilitated by fractures, joints, and by the presence of less resistant rock types. Consequently, the surface elevation of PWR and unweathered rock can vary significantly over short horizontal distances. Lenses and boulders of hard rock and zones of PWR may be present within the soil mantle, above the general bedrock level.

2.2 SITE STRATIGRAPHY

Table 1, below and the following paragraphs describe subsurface conditions encountered in our exploration. The boring logs in the Appendix represent our interpretation of the subsurface conditions encountered based on the driller's field logs and the engineer's examination of the samples. The groundwater condition indicated on the boring logs represent observations at the time of drilling. The lines designating the interfaces between various strata represent approximate boundaries only, as transition between materials may be gradual. Soil conditions may vary between and away from boring locations. Soil samples will be discarded after 30 days from the date of this report.

Exhibit A - Attachment C Fulton County Animal Shelter

Fulton County Animal Services Building
Atlanta, Georgia
Geotechnical Investigation Report

Table 1: Summary of Boring Results

| Boring ID | Surface Elevation (ft) | Soils <6 bpf Elev. (ft) | Groundwater Elevation (ft) | PWR Elevation (ft) | Termination Elevation (ft) |
|-----------|------------------------|-------------------------|----------------------------|--------------------|----------------------------|
| B-1 | 805 | 793-799 | NE | NE | 775 |
| B-2 | 812 | 799-804 | NE | NE | 782 |
| B-3 | 812 | NE | 798 | NE | 782 |
| B-4 | 809 | 798-803 | NE | NE | 779 |
| B-5 | 806 | 795-803 | 790 | 789 | 776 |
| B-6 | 808 | 796-808 | 792 | 786 | 778 |
| B-7 | 803 | NE | NE | 786 | 773 |
| B-8 | 799 | 794-797 | NE | 791 | 769 |
| B-9 | 810 | NE | 795 | 783 | 780 |
| B-10 | 801 | 793-798 | 789 | NE | 771 |
| B-11 | 797 | 789-794 | NE | 770 | 767 |
| B-12 | 792 | NE | 779 | 775 | 770(AR) |
| B-13 | 801 | 790-798 | 789 | NE | 778(AR) |
| B-14 | 820 | NE | 804 | NE | 790 |
| B-15 | 826 | 810-814 | NE | NE | 796 |

AR-Auger Refusal

NE-Not encountered (for GW, none encountered shortly after completion)

2.2.1 Topsoil

Approximately 3-8 inches of organic topsoil was encountered in most borings. Site clearing in 2014-15 likely removed topsoil in some areas. None of the borings was located in areas of apparent mulch disposal. The now 5-year-old mulch is likely degraded significantly but will add to the topsoil quantity on site. For planning, we suggest an assumption of 1 foot of topsoil, mulch, and root/stump removal across the site.

2.2.2 Residual Soils

Residual soils were typical of the area, composed of sandy silt near the surface transitioning to silty sand with depth and were encountered in all the borings below the surface/topsoil. SPT N-values in these soils ranged from 3 to 46 blows per foot (bpf). Significant layers of soil with SPT N-values of 5 or below were encountered in two thirds of the borings and appear to range from about 3 to 12 feet thick. Some low consistency surficial soils were not included in this total.

2.2.3 Partially Weathered Rock and Refusal Materials

Borings 5-9 (within the building footprint) as well as 11 and 12 encountered PWR at elevations as high as 789 feet. Borings 12 and 13, located southeast of the building in a lower part of the site, encountered auger refusal at depths of 22 and 23 feet. Refusal in the residual profile is typically interpreted as the upper surface of sound, massive rock, though it may represent a seam or boulder of hard rock. The elevation of the surface of PWR and rock in the Piedmont can vary significantly over short horizontal distances, so PWR and rock may occur at shallower depths between or away from the borings. Boulders, seams, and masses of rock may occur in the soil mantle above the general rock elevation, though it is rare for weak, soft, or highly compressible soils to occur beneath such seams in the Piedmont geology.

2.2.4 Groundwater

All the borings were completed in a single day (using 2 drilling rigs) so that stabilized groundwater levels were not obtained. Drilling occurred following several days of wet weather. Groundwater was encountered most of the borings. The expectation for natural conditions is that groundwater will mimic the surface gradients but be slightly deeper beneath ridges and hills and shallower in valleys. This trend is apparent, though elevated levels in B-5 and B-6 may be due to increased infiltration due to poor drainage/increased infiltration resulting from the piles of mulch. Groundwater levels can fluctuate with changes in weather and local drainage.

3.0 CONCLUSIONS AND RECOMMENDATIONS

The following conclusions and recommendations are based on the previously discussed project information, our observations at the site, interpretation of the field data obtained during the exploration, and our experience with similar subsurface conditions.

3.1 SITE PREPARATION

All vegetation, including root systems, topsoil, and deleterious materials, notably the mulch present in most of the site, should be cleared and stripped from areas to be excavated or that will receive fill, foundations, or pavements. These materials should be disposed of as allowed by the local jurisdiction. Topsoil and mulch as well as mulched vegetation may be re-used in landscape areas, if consistent with establishment of erosion control grassing. We recommend against burial of any organic matter at the site.

After stripping, proofrolling should be performed with a fully-loaded, tandem-axle, dump truck or pneumatic tired vehicle of similar size and weight. The geotechnical engineer or his representative should observe proofrolling to observe site conditions. Proofrolling should be performed after a period of dry weather. Unstable materials detected should be stabilized as directed by the engineer based on conditions and planned development of the area. Such treatment may include stabilization in place, excavation and replacement, or densification. Where the low consistency soils are encountered at or near the surface, thorough densification using compaction equipment will likely be required, possibly with some scarification and moisture conditioning.

3.2 EXCAVATION

Substantial site grading is anticipated. Soils can generally be excavated using conventional equipment (excavators, pan scrapers, loaders). PWR and rock may be encountered at any depth but are increasingly likely in deeper excavations. PWR typically requires ripping with a single tooth ripper on a large trackhoe (CAT 325) or crawler tractor (CAT D-8) for mass excavation. The ripping may take advantage of existing seams and weaknesses in the mass. In confined excavation, such as the edges or trenches, ripping may be more difficult and pneumatic tools or blasting may be required. Hard rock typically requires loosening by blasting for removal. Due to the substantially higher costs associated with blast rock removal, we recommend ripping or other measures be used until demonstrated to be ineffective before blasting begins. Use of loose soil or blast mats over the rock should be considered to control fly rock. Drilling and blasting through overburden increasing the confinement and is likely to result in higher overall costs and vibrations.

3.3 GROUND AND SURFACE WATER CONTROLS

Groundwater may be encountered in deeper excavations but can typically be controlled with sumps. Groundwater may not be immediately apparent during excavation but will accumulate in

Exhibit A - Attachment C Fulton County Animal Shelter

Fulton County Animal Services Building
Atlanta, Georgia
Geotechnical Investigation Report

the excavation bottom over time or overnight. Seepage may soften/weaken subgrades. Therefore, we recommend groundwater be controlled by means of sumps or trenches to maintain groundwater levels at least 3 feet below the bottom of the excavation at intermediate points between sumps or trenches. Groundwater flows are likely to be limited to a few gallons per minute by the relatively low permeability and transmissivity of the soils.

Positive site drainage should be maintained at all times and excavations should be protected from surface water accumulation. Any ponded water should be pumped or drained expeditiously to avoid degradation of subgrade.

3.4 FILL PLACEMENT

Fill to raise grades, backfill trenches, or replace over-excavated areas should be low to moderate plasticity soil (PI less than 30), free of deleterious materials and rock fragments larger than 6 inches in any dimension. Rock fragments should be rare and sufficient soil should be present to completely separate and fill voids between them. Site soils should meet these requirements. Excavated PWR can generally be pulverized into acceptable fill by trafficking with heavy equipment. Hard rock (blast rock fragments) are typically too large for re-use in fill and would require special crushing operations that are typically not justified on projects of this size. Therefore, blast rock should be used on the surface in landscape areas, for outlet protection in stormwater ponds, etc. or wasted off site. We recommend against burial of blast rock boulders.

Fill should be placed in thin (8-inch-thick loose measure) lifts and compacted to at least 95 percent of the soil's maximum dry density as determined by the standard Proctor compaction test (ASTM D 698) at moisture contents as required to achieve compaction, but in no case more than 3 percent above or below optimum moisture as determined by the standard Proctor test. The upper 2 feet of fill beneath foundations, slabs, or pavements should be compacted to 98 percent. Where access or other limitations require use of light compaction equipment, such as in utility trench excavations, the lift thickness should be reduced to achieve the required degree of compaction throughout the layer. All fill should be placed in horizontal lifts which are adequately keyed into the prepared and scarified subgrade soils.

The grading contractor have equipment on site during earthwork for both drying and wetting fill. Wood does not anticipate difficulty in controlling moisture within the fill during dry weather, but moisture control may be difficult during winter or extended periods of rain.

3.5 LOW CONSISTENCY SOILS

Significant zones of low consistency soils were encountered in many of the borings and may occur randomly across the site. These soils are likely to compress under load. Grading may remove some of these soils and others may be buried deeply under planned fill. Placement of fill over such soils may result in significant settlement due to compression of these zones. Therefore, we recommend using settlement plates (see detail in Appendix) to monitor settlement of significant fill areas (area fills greater than 5 feet thick). The settlement may be several inches, enough to impact site grading quantities. Construction of settlement sensitive elements, such as buildings, gravity utilities, etc. should be delayed until the fill settlement is largely complete, which may be typically about 6-10 weeks after completion of the fill.

3.6 FOUNDATION RECOMMENDATIONS

We anticipate the proposed building can be founded on shallow, spread footings, though much of the building will require treatment of the low consistency soils. If the soils are removed by grading

Exhibit A - Attachment C Fulton County Animal Shelter

Fulton County Animal Services Building
Atlanta, Georgia
Geotechnical Investigation Report

and/or buried more than about 1.5 to 2 times the footing width under fill beneath the footing, the impact on footings will be minimal. But where footings bear within that distance above the low consistency soils, treatment will be required. Treatment may include general undercut and replacement (reuse of the low consistency soils with moisture conditioning and compaction should generally be feasible), undercut of footings and replacement with compacted #57 stone placed in 12 inch lifts and compacted by tamping with the backhoe bucket, or use of aggregate piers.

Aggregate piers are installed by specialty contractors using various methods and described as rammed aggregate piers, stone columns, Vibropiers, Geopiers or others. The concept is to replace some of the soil with compacted aggregate which improves the surrounding soil and allows support of shallow footings designed for bearing pressures of 5,000 to 6,000 psf. The specialty contractor normally does the design and provides a warranty on the settlement. The aggregate piers typically replace about 20-30 percent of the bearing area to a depth below the low-consistency zone or at least about twice the footing width, so likely 10-20 feet for this project.

Numerous other ground improvement methods are available (dynamic compaction, preloading, grouting, etc.) but aggregate piers are likely the most practical for this project.

Alternately, the footings could be designed based on a presumptive bearing pressure of 3,000 psf and the geotechnical engineer can evaluate each footing independently. If low consistency soils are detected that would produce unacceptable settlements, the engineer will recommend undercut and replacement. Undercut would extend 1 foot around the footing. Replacement would be with compacted ASTM 57 stone, placed in 12-inch loose lifts and compacted remotely by tamping with the backhoe bucket. This approach may be cumbersome for large numbers of footings but may be cost-effective compared to the more general aggregate pier treatment if only a few footings are expected to be treated.

3.7 RETAINING WALLS

No specific information was provided for on site or below grade walls planned for this site, but it is anticipated that the site will likely step down to the southwest and south, so may require site walls up to about 15 feet high as well as possible dock walls in the loading dock area. Lateral earth pressure parameters for a typical fill material (sandy silt/silty sand) compacted as outlined in the fill section of this report are summarized in Table 2, below. These assume the ground is level above and below the walls and that buildings, pavements, or other surcharge loads are at least 10 feet from the top of walls and that the walls have drainage systems to prevent back up of groundwater or surface water behind the walls:

Table 2. Lateral Earth Pressure Parameters

| Earth Pressure Condition | Earth Pressure Coefficient | Recommended Equivalent Fluid Unit Weight (pcf) |
|--------------------------|----------------------------|--|
| Active | $K_a = 0.39$ | 50 |
| At-Rest | $K_0 = 0.56$ | 73 |
| Passive | $K_p = 1.3$ | 150 |

A coefficient of friction of 0.4 may be considered between the wall foundation and the soils. Wall settlement may be impacted by the low consistency soils and treatment as per building foundations should be considered. Mechanically Stabilized Earth walls, typically constructed by placing a fill reinforced with geogrids and faced with concrete blocks, are cost-effective and commonly used in fill areas. If site soils are used, we recommend an angle of internal friction of 26 degrees and a unit

weight of 130 pcf for the backfill (compacted per the above) and foundation. MSE walls are flexible and may withstand settlements due to the low-consistency soils better than concrete cantilever walls. In excavations, soil nail walls may be considered. The design concept is similar to MSE, but the construction uses using top-down methods during excavation. Tensile reinforcing bars are installed into the excavation face to a distance of about 0.7 or 0.8 times the wall height, typically on a 4 to 5-foot centers. A facing of shotcrete is then applied over a drainage system. Design may consider the same parameters as for MSE walls. MSE and soil nail walls are typically design build options installed by specialty contractors.

3.8 SLABS

Floor slabs on grade should be typical of the area. A modulus of subgrade reaction of about 100 pounds per cubic inch (pci) should be available for slab support of generally light (pedestrian/office) loads on a properly prepared soil subgrade as discussed in the site preparation section above. The floor slab design should include a capillary break, comprised of free draining, compacted, granular material, at least 4 inches thick. In our experience, the granular material helps provide more even support and improved slab performance. A vapor retarder is recommended under floor slabs to limit moisture entry into the building. Slabs should be jointed along walls and around columns to reduce the risk of cracking due to differential settlement. Jointing and reinforcement should follow ACI.

Floor slabs should be structurally independent of any building footings or walls to reduce the possibility of floor slab cracking caused by differential movements between the slab and foundation. Narrower, turned down slab-on-grade foundations may be utilized at the approval of the structural engineer. The slabs should be appropriately reinforced to support the proposed loads.

3.9 PAVEMENT RECOMMENDATIONS

A California Bearing Ratio (CBR) value of 3 may be considered for well-prepared subgrade consisting of site soils. Pavements for parking and driveways restricted to automobile traffic typically consist of 2 inches of asphaltic concrete over a 6-inch graded aggregate base. Pavements for truck traffic, such as garbage trucks, should be designed based on anticipated traffic but are typically thicker. Rigid Portland Cement Concrete (PCC) pavements are recommended for dumpster pads, loading docks, and other areas where heavy trucks maneuver or point loads are applied. We recommend a minimum PCC section of 8 inches of PCC with a flexural strength of at least 600 psi (typically about 4,000 psi concrete) over 4 inches of graded aggregate base.

A well-drained, uniform subgrade is critical to pavement performance. Sealing of pavement and joints is recommended, but experience shows that stormwater can typically reach the subgrade. The subgrade should be sloped to drain and GAB should be provided with outlets at the low edges or into drop inlets to prevent accumulation of water in the subgrade which can lead to saturation and softening.

3.10 SEISMIC DESIGN PARAMETERS

The International Building Code (IBC) 2012 provides six Site Class Definitions that range from hard rock (A) to potentially unstable soil (F). Each site class is described by the average shear wave velocity, standard penetration resistance, or soil undrained shear strength in the top 100 feet of the site profile. The shear wave velocity is related to the site column shear modulus, whereas the standard penetration resistance and undrained shear strength can be empirically related to the shear wave velocity. Each site class is associated with amplification factors that represent the

Exhibit A - Attachment C Fulton County Animal Shelter

Fulton County Animal Services Building
Atlanta, Georgia
Geotechnical Investigation Report

effects that site stiffness (shear modulus) has on the presumed earthquake bedrock motion. Based on SPT results, we recommend design based on Site Class D. This can be reviewed once grading plans are more complete, and/or geophysical methods can be used to directly assess site shear wave velocities in the building, which may allow use of a higher site class.

4.0 QUALIFICATIONS OF RECOMMENDATIONS

This evaluation of foundation design and construction conditions has been based on our understanding of the site, the available project information, our assumptions and the data obtained during our field exploration as described herein. The recommendations in this report have been developed on the basis of the previously described project characteristics and subsurface conditions. As the design develops, we should be consulted to review and potentially revise these recommendations.

Regardless of the thoroughness of a subsurface exploration, there is the possibility that conditions will differ from those at the boring location, that conditions are not as anticipated by the designers, or that the construction process has altered the soil conditions. Therefore, experienced geotechnical engineers must observe earthwork and foundation construction to assess if the conditions anticipated in design actually exist.

Our professional services have been performed, our findings derived, and our recommendations prepared in accordance with generally accepted geotechnical engineering principles and practices. This warranty is in lieu of all other warranties either express or implied. This company is not responsible for the conclusions, opinions or recommendations of others based on these data.



APPENDIX

Figure 1 – Site Location Plan



Figure 2 – Boring Location Plan

Field and Laboratory Procedures

Key to Symbols and Descriptions

Soil Test Boring Records

GBA Information about Geotechnical Reports



Source: USGS, 2014 Northwest Atlanta, GA

NOT TO SCALE

**Fulton County Animal Services
Building
Industrial Boulevard
Atlanta, Georgia**



Wood Environment & Infrastructure Solutions, Inc.
2677 Buford Highway
Atlanta, Georgia 30324 (404) 873 4761

SITE LOCATION MAP

PROJECT: 6162201408

DATE: April 14, 2020

FIGURE 1



Source: PGAL Fulton County Animal Services Building: Approximate Geotechnical Boring Locations (3/19/2020)

● Approximate Boring Location

| | | | |
|---|---|------------------------------------|-----------------|
| <p>Fulton County Animal Services Building Industrial Boulevard Atlanta, Georgia</p> | <p>wood. Wood Environment & Infrastructure Solutions, Inc. 2677 Buford Highway Atlanta, Georgia 30324 (404) 873 4761</p> | <p>BORING LOCATION PLAN</p> | |
| <p>PROJECT: 6162201408</p> | | <p>DATE: April 14, 2020</p> | <p>FIGURE 2</p> |

FIELD EXPLORATORY PROCEDURES

Field Operations: The general field procedures employed by Wood are summarized in ASTM D 420, which is entitled "Investigating and Sampling Soils and Rocks for Engineering Purposes." This recommended practice lists recognized methods for determining soil and rock distribution and groundwater conditions. These methods include geophysical and in situ methods as well as borings.

Borings are drilled to obtain subsurface samples using one of several alternate techniques depending upon the subsurface conditions. These techniques are:

- a. Continuous 2-1/2 or 3-1/4 inch I.D. hollow stem augers;
- b. Wash borings using roller cone or drag bits (mud or water);
- c. Continuous flight augers (ASTM D 1425).

These drilling methods are not capable of penetrating through material designated as "refusal materials." Refusal, thus indicated, may result from hard cemented soil, soft weathered rock, coarse gravel or boulders, thin rock seams, or the upper surface of sound continuous rock. Core drilling procedures are required to determine the character and continuity of refusal materials.

The subsurface conditions encountered during drilling are reported on a field test boring record by the chief driller. The record contains information concerning the boring method, samples attempted and recovered, indications of the presence of various materials such as coarse gravel, cobbles, etc., and observations between samples. Therefore, these boring records contain both factual and interpretive information. The field boring records are on file in our office.

The soil and rock samples and the field boring records are reviewed by a geotechnical engineer. The engineer classifies the soils in general accordance with the procedures outlined in ASTM D 2488 and prepares the final boring records that are the basis for all evaluations and recommendations.

The final boring records represent our interpretation of the contents of the field records based on the results of the engineering examinations and tests of the field samples. These records depict subsurface conditions at the specific locations and at the particular time when drilled. Soil conditions at other locations may differ from conditions occurring at these boring locations. Also, the passage of time may result in a change in the subsurface soil and groundwater conditions at these boring locations. The lines designating the interface between soil or refusal materials on the records and on profiles

represent approximate boundaries. The transition between materials may be gradual. The final boring records are included with this report.

The detailed data collection methods used during this study are discussed on the following pages.

Soil Test Borings: Soil test borings were made at the site at approximate locations shown on the attached Boring Location Plan. Soil sampling and penetration testing were performed in general accordance with ASTM D 1586.

Each boring was made by mechanically twisting a hollow-stem steel auger into the soil. At regular intervals, the drilling tools were removed and soil samples obtained with a standard 1.4-inch I.D., 2-inch O.D., split tube sampler. The sampler was first seated 6 inches to penetrate loose cuttings, then driven an additional foot with blows of a 140-pound hammer falling 30 inches. The number of hammer blows required to drive the sampler the final foot was recorded and is designated the "penetration resistance." The penetration resistance, when properly evaluated, is an index to the soil strength and foundation supporting capability.

Representative portions of the soil samples, thus obtained, were placed in glass jars and transported to the laboratory. In the laboratory, the samples were examined to evaluate the driller's field classifications. Test boring records are attached which graphically show the soil descriptions and penetration resistances.

Water Level Readings: Water table readings are normally taken in conjunction with borings and are recorded on the "Test Boring Records." These readings indicate the approximate location of the hydrostatic water table at the time of our field investigation. Where impervious soils are encountered (clayey soils) the amount of water seepage into the boring is small, and it is generally not possible to establish the location of the hydrostatic water table through water level readings. The groundwater table may also depend on the amount of precipitation at the site during a particular period. Fluctuations in the water table should be expected with variations in precipitation, surface run-off, evaporation and other factors.

The time of boring water level reported on the boring records is determined by field crews as the drilling tools are advanced. The time of boring water level is detected by changes in the drilling rate, soil samples obtained, etc. The readings are taken by dropping a weighted line down the boring or using an electrical probe to detect the water level surface.

Rock Coring: Core drilling procedures were utilized to determine the character and continuity of materials below the soil drilling refusal level. The core drilling procedure is performed in general accordance with ASTM designation D-2113-70. Initially, casing is set through the overburden soils to keep the hole from collapsing. Refusal materials are then cored with a diamond-studded bit fastened to the end of a hollow double-tube core barrel. This device is rotated at high speeds and is capable of cutting the hardest rock. The cuttings are brought to the surface by circulating water. Rock core samples of the materials penetrated are protected and retained in a swivel-mounted inner tube. Upon completion of the drill run, the core barrel is brought to the surface and the samples are removed and placed in core boxes. The samples are then returned to our laboratory where the rock is identified and the “recovery” and “rock quality designation” (RQD) are determined.

Rock Hardness descriptions are listed below:

Rock Hardness Descriptions

| | |
|-----------------|--|
| Very Hard | Rock core rings and can be made to spark when struck with a hammer |
| Hard | Rock core rings when struck with a hammer |
| Moderately Hard | Thin edges of rock core cannot be broken with fingers |
| Soft | Thin edges of rock core can be broken with fingers |
| Very Soft | Rock core crumbles when handled |

The “recovery” is the ratio of the sample length to the length drilled, expressed as a percent. The “rock quality designation” (RQD) is the percent of recovered rock sample in segments four or more inches long compared to the total length of the run. This designation is generally applied only to samples of NX size or larger and to samples described as moderately hard or harder. The percent recovery and RQD are related to rock soundness and continuity. The NX size designates a bit which obtains core samples 2-1/8 inches in diameter.

| MAJOR DIVISIONS | | | GROUP SYMBOLS | TYPICAL NAMES | Undisturbed Sample | Auger Cuttings | | | |
|--|--|---|--|--|---|----------------------------|--|------------------|--------------|
| COARSE GRAINED SOILS (More than 50% of material is LARGER than No. 200 sieve size) | GRAVELS (More than 50% of coarse fraction is LARGER than the No. 4 sieve size) | CLEAN GRAVELS (Little or no fines) | GW | Well graded gravels, gravel - sand mixtures, little or no fines. | | Bulk Sample | | | |
| | | | GP | Poorly graded gravels or gravel - sand mixtures, little or no fines. | | | | Crandall Sampler | |
| | | GRAVELS WITH FINES (Appreciable amount of fines) | GM | Silty gravels, gravel - sand - silt mixtures. | | Pressure Meter | | | |
| | | | GC | Clayey gravels, gravel - sand - clay mixtures. | | | | No Recovery | |
| | SANDS (More than 50% of coarse fraction is SMALLER than the No. 4 Sieve Size) | CLEAN SANDS (Little or no fines) | SW | Well graded sands, gravelly sands, little or no fines. | | Water Table after 24 hours | | | |
| | | | SP | Poorly graded sands or gravelly sands, little or no fines. | | | Correlation of Standard Penetration Resistance with Relative Density and Consistency | | |
| | | SANDS WITH FINES (Appreciable amount of fines) | SM | Silty sands, sand - silt mixtures | SAND & GRAVEL SILT & CLAY | | | | |
| | | | SC | Clayey sands, sand - clay mixtures. | No. of Blows | Relative Density | | | No. of Blows |
| | | FINE GRAINED SOILS (More than 50% of material is SMALLER than No. 200 sieve size) | SILTS AND CLAYS (Liquid limit LESS than 50) | ML | Inorganic silts and very fine sands, rock flour, silty of clayey fine sands or clayey silts and with slight plasticity. | 0 - 4 | | | Very Loose |
| | | | | CL | Inorganic lays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays. | 5 - 10 | Loose | 3 - 4 | Soft |
| OL | Organic silts and organic silty clays of low plasticity. | | | 11 - 30 | Medium Dense | 5 - 8 | Firm | | |
| | | | | 31 - 50 | Dense | 9 - 15 | Stiff | | |
| SILTS AND CLAYS (Liquid limit GREATER than 50) | MH | | Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts. | Over 50 | Very Dense | 16 - 30 | Very Stiff | | |
| | CH | | Inorganic clays of high plasticity, fat clays | | | 31 - 50 | Hard | | |
| | OH | | Organic clays of medium to high plasticity, organic silts. | | | Over 50 | Very Hard | | |
| | Correlation of Dynamic Cone Penetration Resistance with Relative Density and Consistency (Piedmont Residual Soils) | | SAND & GRAVEL | | SILT & CLAY | | | | |
| | | | No. of Blows | Relative Density | No. of Blows | Consistency | | | |
| | HIGHLY ORGANIC SOILS | | PT | Peat and other highly organic soils. | 0 - 4 | Very Loose | 0 - 2 | Very Soft | |
| | | | | 5 - 15 | Loose | 3 - 4 | Soft | | |
| FILL | | | Fill | 16 - 30 | Medium Dense | 5 - 10 | Firm | | |
| | | | | | | 11 - 30 | Stiff | | |


BOUNDARY CLASSIFICATIONS: Soils possessing characteristics of two groups are designated by combinations of group symbols.

| | | | | | | | |
|--------------|--------|--------|--------------|--------|--------|-----|--------------------|
| SILT OR CLAY | SAND | | | GRAVEL | | | Cobbles Boulders |
| | Fine | Medium | Coarse | Fine | Coarse | | |
| | No.200 | No.40 | No.10 No.4 | 3/4" | 3" | 12" | |

U.S. STANDARD SIEVE SIZE

KEY TO SYMBOLS AND DESCRIPTIONS





AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMECC.GDT 4/15/20


DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: No GW encountered during drilling

AUGER BORING RECORD

BORING NO.: B-1
PROJECT: Fulton County Animal Services Building
LOCATION: Atlanta, Georgia
DRILLED: March 30, 2020
PROJECT NO.: 6162201408

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.





AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMECC.GDT 4/15/20


DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: No GW encountered during drilling

AUGER BORING RECORD

BORING NO.: B-2
PROJECT: Fulton County Animal Services Building
LOCATION: Atlanta, Georgia
DRILLED: March 30, 2020
PROJECT NO.: 6162201408



THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.




AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMECC.GDT 4/15/20

DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: GW encountered at 14 feet at time of drilling

| AUGER BORING RECORD | |
|-----------------------------------|--|
| BORING NO.: B-3 | PROJECT: Fulton County Animal Services Building |
| LOCATION: Atlanta, Georgia | DRILLED: March 30, 2020 |
| PROJECT NO.: 6162201408 | PAGE 1 OF 1 |
| | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.



AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMECC.GDT 4/15/20


DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: No GW encountered during drilling

AUGER BORING RECORD

BORING NO.: B-4
PROJECT: Fulton County Animal Services Building
LOCATION: Atlanta, Georgia
DRILLED: March 30, 2020
PROJECT NO.: 6162201408



THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.




AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMECC.GDT 4/15/20

DRILLER: Premier Drilling
 EQUIPMENT: CME-75 (Auto-Hammer)
 METHOD: 2 1/4" HSA
 HOLE DIA.: 6 inches
 REMARKS: GW encountered at 16 feet at time of drilling

| AUGER BORING RECORD | |
|---------------------|--|
| BORING NO.: | B-5 |
| PROJECT: | Fulton County Animal Services Building |
| LOCATION: | Atlanta, Georgia |
| DRILLED: | March 30, 2020 |
| PROJECT NO.: | 6162201408 |
| PAGE 1 OF 1 | |
| | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.



AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMEC.GDT 4/15/20


DRILLER: Premier Drilling
 EQUIPMENT: CME-75 (Auto-Hammer)
 METHOD: 2 1/4" HSA
 HOLE DIA.: 6 inches
 REMARKS: GW encountered at 16 feet at time of drilling

AUGER BORING RECORD

BORING NO.: B-6
PROJECT: Fulton County Animal Services Building
LOCATION: Atlanta, Georgia
DRILLED: March 30, 2020
PROJECT NO.: 6162201408



THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.




AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMEC.GDT 4/15/20

DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: No GW encountered during drilling

| AUGER BORING RECORD | |
|---------------------|--|
| BORING NO.: | B-7 |
| PROJECT: | Fulton County Animal Services Building |
| LOCATION: | Atlanta, Georgia |
| DRILLED: | March 30, 2020 |
| PROJECT NO.: | 6162201408 |
| PAGE 1 OF 1 | |
| | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.




AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMECC.GDT 4/15/20

DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: GW encountered at 9 feet at time of drilling

| AUGER BORING RECORD | |
|-----------------------------------|--|
| BORING NO.: B-8 | PROJECT: Fulton County Animal Services Building |
| LOCATION: Atlanta, Georgia | DRILLED: March 30, 2020 |
| PROJECT NO.: 6162201408 | PAGE 1 OF 1 |
| | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.



AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMEC.GDT 4/15/20


DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: GW encountered at 15 feet at time of drilling

AUGER BORING RECORD

BORING NO.: B-9
PROJECT: Fulton County Animal Services Building
LOCATION: Atlanta, Georgia
DRILLED: March 30, 2020
PROJECT NO.: 6162201408

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.






AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMEC.GDT 4/15/20

DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: GW encountered at 12 feet during drilling

| AUGER BORING RECORD | |
|---------------------|--|
| BORING NO.: | B-10 |
| PROJECT: | Fulton County Animal Services Building |
| LOCATION: | Atlanta, Georgia |
| DRILLED: | March 30, 2020 |
| PROJECT NO.: | 6162201408 |
| PAGE 1 OF 1 | |
| | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.




AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING LOGS.GPJ AMEC.GDT 4/15/20

DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: No GW encountered during drilling

| AUGER BORING RECORD | |
|---------------------|--|
| BORING NO.: | B-11 |
| PROJECT: | Fulton County Animal Services Building |
| LOCATION: | Atlanta, Georgia |
| DRILLED: | March 30, 2020 |
| PROJECT NO.: | 6162201408 |
| PAGE 1 OF 1 | |
| | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.




AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMEC.GDT 4/15/20

DRILLER: Premier Drilling
 EQUIPMENT: CME-75 (Auto-Hammer)
 METHOD: 2 1/4" HSA
 HOLE DIA.: 6 inches
 REMARKS: GW encountered at 13 feet during drilling

| AUGER BORING RECORD | |
|---------------------|--|
| BORING NO.: | B-12 |
| PROJECT: | Fulton County Animal Services Building |
| LOCATION: | Atlanta, Georgia |
| DRILLED: | March 30, 2020 |
| PROJECT NO.: | 6162201408 |
| PAGE 1 OF 1 | |
| | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.




AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMEC.GDT 4/15/20

DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: GW encountered at 12 feet during drilling

| AUGER BORING RECORD | |
|---------------------|--|
| BORING NO.: | B-13 |
| PROJECT: | Fulton County Animal Services Building |
| LOCATION: | Atlanta, Georgia |
| DRILLED: | March 30, 2020 |
| PROJECT NO.: | 6162201408 |
| PAGE 1 OF 1 | |
| | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.




AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMEC.GDT 4/15/20

DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: GW encountered at 16 feet during drilling

| AUGER BORING RECORD | |
|---------------------|--|
| BORING NO.: | B-14 |
| PROJECT: | Fulton County Animal Services Building |
| LOCATION: | Atlanta, Georgia |
| DRILLED: | March 30, 2020 |
| PROJECT NO.: | 6162201408 |
| PAGE 1 OF 1 | |
| | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.



AUGER BORING FULTON COUNTY ANIMAL SHELTER BUILDING BORING LOGS.GPJ AMEC.GDT 4/15/20

DRILLER: Premier Drilling
EQUIPMENT: CME-75 (Auto-Hammer)
METHOD: 2 1/4" HSA
HOLE DIA.: 6 inches
REMARKS: No GW encountered during drilling

| AUGER BORING RECORD | |
|---------------------|--|
| BORING NO.: | B-15 |
| PROJECT: | Fulton County Animal Services Building |
| LOCATION: | Atlanta, Georgia |
| DRILLED: | March 30, 2020 |
| PROJECT NO.: | 6162201408 |
| PAGE 1 OF 1 | |

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER.



Important Information about This

Geotechnical-Engineering Report

Subsurface problems are a principal cause of construction delays, cost overruns, claims, and disputes.

While you cannot eliminate all such risks, you can manage them. The following information is provided to help.

The Geoprofessional Business Association (GBA) has prepared this advisory to help you – assumedly a client representative – interpret and apply this geotechnical-engineering report as effectively as possible. In that way, clients can benefit from a lowered exposure to the subsurface problems that, for decades, have been a principal cause of construction delays, cost overruns, claims, and disputes. If you have questions or want more information about any of the issues discussed below, contact your GBA-member geotechnical engineer. Active involvement in the Geoprofessional Business Association exposes geotechnical engineers to a wide array of risk-confrontation techniques that can be of genuine benefit for everyone involved with a construction project.

Geotechnical-Engineering Services Are Performed for Specific Purposes, Persons, and Projects

Geotechnical engineers structure their services to meet the specific needs of their clients. A geotechnical-engineering study conducted for a given civil engineer will not likely meet the needs of a civil-works constructor or even a different civil engineer. Because each geotechnical-engineering study is unique, each geotechnical-engineering report is unique, prepared *solely* for the client. *Those who rely on a geotechnical-engineering report prepared for a different client can be seriously misled.* No one except authorized client representatives should rely on this geotechnical-engineering report without first conferring with the geotechnical engineer who prepared it. *And no one – not even you – should apply this report for any purpose or project except the one originally contemplated.*

Read this Report in Full

Costly problems have occurred because those relying on a geotechnical-engineering report did not read it *in its entirety*. Do not rely on an executive summary. Do not read selected elements only. *Read this report in full.*

You Need to Inform Your Geotechnical Engineer about Change

Your geotechnical engineer considered unique, project-specific factors when designing the study behind this report and developing the confirmation-dependent recommendations the report conveys. A few typical factors include:

- the client's goals, objectives, budget, schedule, and risk-management preferences;
- the general nature of the structure involved, its size, configuration, and performance criteria;
- the structure's location and orientation on the site; and
- other planned or existing site improvements, such as retaining walls, access roads, parking lots, and underground utilities.

Typical changes that could erode the reliability of this report include those that affect:

- the site's size or shape;
- the function of the proposed structure, as when it's changed from a parking garage to an office building, or from a light-industrial plant to a refrigerated warehouse;
- the elevation, configuration, location, orientation, or weight of the proposed structure;
- the composition of the design team; or
- project ownership.

As a general rule, *always* inform your geotechnical engineer of project changes – even minor ones – and request an assessment of their impact. *The geotechnical engineer who prepared this report cannot accept responsibility or liability for problems that arise because the geotechnical engineer was not informed about developments the engineer otherwise would have considered.*

This Report May Not Be Reliable

Do not rely on this report if your geotechnical engineer prepared it:

- for a different client;
- for a different project;
- for a different site (that may or may not include all or a portion of the original site); or
- before important events occurred at the site or adjacent to it; e.g., man-made events like construction or environmental remediation, or natural events like floods, droughts, earthquakes, or groundwater fluctuations.

Note, too, that it could be unwise to rely on a geotechnical-engineering report whose reliability may have been affected by the passage of time, because of factors like changed subsurface conditions; new or modified codes, standards, or regulations; or new techniques or tools. *If your geotechnical engineer has not indicated an "apply-by" date on the report, ask what it should be, and, in general, if you are the least bit uncertain about the continued reliability of this report, contact your geotechnical engineer before applying it.* A minor amount of additional testing or analysis – if any is required at all – could prevent major problems.

Most of the "Findings" Related in This Report Are Professional Opinions

Before construction begins, geotechnical engineers explore a site's subsurface through various sampling and testing procedures. *Geotechnical engineers can observe actual subsurface conditions only at those specific locations where sampling and testing were performed.* The data derived from that sampling and testing were reviewed by your geotechnical engineer, who then applied professional judgment to form opinions about subsurface conditions throughout the site. Actual sitewide-subsurface conditions may differ – maybe significantly – from those indicated in this report. Confront that risk by retaining your geotechnical engineer to serve on the design team from project start to project finish, so the individual can provide informed guidance quickly, whenever needed.

This Report's Recommendations Are Confirmation-Dependent

The recommendations included in this report – including any options or alternatives – are confirmation-dependent. In other words, *they are not final*, because the geotechnical engineer who developed them relied heavily on judgment and opinion to do so. Your geotechnical engineer can finalize the recommendations *only after observing actual subsurface conditions* revealed during construction. If through observation your geotechnical engineer confirms that the conditions assumed to exist actually do exist, the recommendations can be relied upon, assuming no other changes have occurred. *The geotechnical engineer who prepared this report cannot assume responsibility or liability for confirmation-dependent recommendations if you fail to retain that engineer to perform construction observation.*

This Report Could Be Misinterpreted

Other design professionals' misinterpretation of geotechnical-engineering reports has resulted in costly problems. Confront that risk by having your geotechnical engineer serve as a full-time member of the design team, to:

- confer with other design-team members,
- help develop specifications,
- review pertinent elements of other design professionals' plans and specifications, and
- be on hand quickly whenever geotechnical-engineering guidance is needed.

You should also confront the risk of constructors misinterpreting this report. Do so by retaining your geotechnical engineer to participate in prebid and preconstruction conferences and to perform construction observation.

Give Constructors a Complete Report and Guidance

Some owners and design professionals mistakenly believe they can shift unanticipated-subsurface-conditions liability to constructors by limiting the information they provide for bid preparation. To help prevent the costly, contentious problems this practice has caused, include the complete geotechnical-engineering report, along with any attachments or appendices, with your contract documents, *but be certain to note conspicuously that you've included the material for informational purposes only*. To avoid misunderstanding, you may also want to note that "informational purposes" means constructors have no right to rely on the interpretations, opinions, conclusions, or recommendations in the report, but they may rely on the factual data relative to the specific times, locations, and depths/elevations referenced. Be certain that constructors know they may learn about specific project requirements, including options selected from the report, *only* from the design drawings and specifications. Remind constructors that they may

perform their own studies if they want to, and *be sure to allow enough time* to permit them to do so. Only then might you be in a position to give constructors the information available to you, while requiring them to at least share some of the financial responsibilities stemming from unanticipated conditions. Conducting prebid and preconstruction conferences can also be valuable in this respect.

Read Responsibility Provisions Closely

Some client representatives, design professionals, and constructors do not realize that geotechnical engineering is far less exact than other engineering disciplines. That lack of understanding has nurtured unrealistic expectations that have resulted in disappointments, delays, cost overruns, claims, and disputes. To confront that risk, geotechnical engineers commonly include explanatory provisions in their reports. Sometimes labeled "limitations," many of these provisions indicate where geotechnical engineers' responsibilities begin and end, to help others recognize their own responsibilities and risks. *Read these provisions closely*. Ask questions. Your geotechnical engineer should respond fully and frankly.

Geoenvironmental Concerns Are Not Covered

The personnel, equipment, and techniques used to perform an environmental study – e.g., a "phase-one" or "phase-two" environmental site assessment – differ significantly from those used to perform a geotechnical-engineering study. For that reason, a geotechnical-engineering report does not usually relate any environmental findings, conclusions, or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. *Unanticipated subsurface environmental problems have led to project failures*. If you have not yet obtained your own environmental information, ask your geotechnical consultant for risk-management guidance. As a general rule, *do not rely on an environmental report prepared for a different client, site, or project, or that is more than six months old*.

Obtain Professional Assistance to Deal with Moisture Infiltration and Mold

While your geotechnical engineer may have addressed groundwater, water infiltration, or similar issues in this report, none of the engineer's services were designed, conducted, or intended to prevent uncontrolled migration of moisture – including water vapor – from the soil through building slabs and walls and into the building interior, where it can cause mold growth and material-performance deficiencies. Accordingly, *proper implementation of the geotechnical engineer's recommendations will not of itself be sufficient to prevent moisture infiltration*. Confront the risk of moisture infiltration by including building-envelope or mold specialists on the design team. *Geotechnical engineers are not building-envelope or mold specialists*.



Telephone: 301/565-2733

e-mail: info@geoprofessional.org www.geoprofessional.org

Copyright 2016 by Geoprofessional Business Association (GBA). Duplication, reproduction, or copying of this document, in whole or in part, by any means whatsoever, is strictly prohibited, except with GBA's specific written permission. Excerpting, quoting, or otherwise extracting wording from this document is permitted only with the express written permission of GBA, and only for purposes of scholarly research or book review. Only members of GBA may use this document or its wording as a complement to or as an element of a report of any kind. Any other firm, individual, or other entity that so uses this document without being a GBA member could be committing negligent

FCAS Equipment Schedule

10/25/2021

OWNER = FCAS
CONTRACTOR = GC

O/C C/C O/O

| EQUIPMENT NUMBER | EQUIPMENT DESCRIPTION | FURNISHED BY | INSTALLED BY | VENDOR | BLOCKING REQ'D | POWER REQ'D | DATA REQ'D | GAS REQ'D | MED GAS REQ'D | PLUMBING REQ'D | MANUFACTURER | MODEL | COUNT | EQUIPMENT NOTES | Unit Cost | Total Cost | C/C | O/O | O/C |
|--|---------------------------------|--------------|--------------|--------|----------------|-------------|------------|-----------|---------------|----------------|--------------------|---|-------|--|-----------|------------|-----|-----|-----|
| 01 GENERAL OFFICE EQUIPMENT | | | | | | | | | | | | | | | | | | | |
| 01-109B | DOG LEASH CLEAT/EYE HOOK | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | DOGHOOK.COM | SPECIFY MASONRY OR STUD WALL | 39 | CONTRACTOR TO COORDINATE FINAL HEIGHT AND LOCATION WITH OWNER; MOUNT EYE VERTICALLY | \$ 50 | | | | |
| 01-114 | FOOD PREP CART | OWNER | OWNER | | - | - | - | - | - | - | SHOR-LINE | | 10 | | \$ 315 | | | | |
| 01-115B | TRASH CAN - ON WHEELS | OWNER | OWNER | | - | - | - | - | - | - | | | 1 | | \$ 250 | | | | |
| 01-117C | LAUNDRY CART | OWNER | OWNER | | - | - | - | - | - | - | | | 6 | | \$ 250 | | | | |
| 01-118 | SMALL RECYCLE BIN - 13 GAL | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | | | 17 | | | | | | |
| 01-121 | WIRE RACK SHELVING | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | METRO | XXXXBR (MODEL NO. VARIES BASED ON SIZE) | 19 | | \$ 350 | | | | |
| 01-121A | WIRE RACK SHELVING | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | METRO | XXXXBR (MODEL NO. VARIES BASED ON SIZE) | 6 | | \$ 350 | | | | |
| 01-121B | WIRE RACK SHELVING | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | METRO | XXXXBR (MODEL NO. VARIES BASED ON SIZE) | 7 | | \$ 350 | | | | |
| 01-121C | WIRE RACK SHELVING | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | METRO | XXXXBR (MODEL NO. VARIES BASED ON SIZE) | 4 | | \$ 350 | | | | |
| 01-122E | SST WALL-MOUNTED SHELF | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | METRO | 1448NS | 5 | | \$ 350 | | | | |
| 01-122F | SST WALL-MOUNTED SHELF | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | METRO | 1460NS | 14 | | \$ 350 | | | | |
| 01-130A | DRY ERASE BOARD | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | | | 9 | | \$ 260 | | | | |
| 01-130B | GLASS DRY ERASE BOARD | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | 3-FORM | | 2 | 3.5'X5' LOW IRON, TEMPERED, GLOSS MARKERBOARD, COLOR: CHALK, FRAMED WITH ACCESSORY SHELF | \$ 300 | | | | |
| 01-130C | GLASS DRY ERASE BOARD | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | 3-FORM | | 1 | 4XX6' LOW IRON, TEMPERED, GLOSS MARKERBOARD, COLOR: CHALK, FRAMED WITH ACCESSORY SHELF | \$ 300 | | | | |
| 01-132 | BULLETIN BOARD | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | NORTH SCULPTURE | | 1 | FORBO FRAMED BULLETIN BOARD 48X96; COLOR: TBD | | | | | |
| 01-134 | SIGN HOLDER | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | | | 11 | C58 PAPER INSERT WINDOW; CONFIRM WITH COUNTY | | | | | |
| 01-135 | ACOUSTIC WALL PANEL | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SU | | 112 | | | | | | |
| 01-136 | ACOUSTIC WALL PANEL - IMAGE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | AUDIMUTE | SU | 24 | RE: INTERIOR ELEVATIONS FOR SIZE. RE: A 9.01 FOR MOUNTING DTL | | | | | |
| 01-140A | METAL LOCKERS - 2 TIER | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | RE: SPECIFICATIONS | | 16 | | | | | | |
| 01-140B | METAL LOCKERS - 3 TIER | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | RE: SPECIFICATIONS | | 7 | | | | | | |
| 01-142 | SAFE - BOLT TO FLOOR | OWNER | CONTRACTOR | | - | - | - | - | - | - | ULINE | DIGITAL SAFE H-5784 | 1 | CONTRACTOR TO UNLOAD, UNPACK & STORE | \$ 470 | | | | |
| 01-301 | STORAGE PALLET | OWNER | OWNER | | - | - | - | - | - | - | | | 6 | | \$ 150 | | | | |
| 01-302 | PALLET RACK - 42X120 | OWNER | OWNER | | - | - | - | - | - | - | GLOBAL INDUSTRIAL | | 2 | | \$ 500 | | | | |
| 01-305 | ELECTRIC PALLET JACK - 3300 LB | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | GLOBAL INDUSTRIAL | WG988993 | 1 | ELECTRIC PALLET JACK - 3300 LB | \$ 2,900 | | | | |
| 01-401 | SST WORKTABLE - ROLLED EDGE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | ULINE | DELUXE H-7566 | 1 | 72" X 36" W/ BOTTOM SHELF | \$ 568 | | | | |
| 02 FURNITURE & SIGNAGE | | | | | | | | | | | | | | | | | | | |
| 02-201 | ROLLER SHADE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | MECHOSHADE | MECH/5 | 14 | TO HAVE FRONT AND BACK FASCIA; SHADE COLOR TBD; SEE SPECIFICATIONS FOR MORE INFORMATION | | | | | |
| 03 COMMUNICATION & SECURITY | | | | | | | | | | | | | | | | | | | |
| 03-101 | COMPUTER | OWNER | OWNER | | - | YES | YES | - | - | - | | | 93 | | \$ 800 | | | | |
| 03-105 | COMPUTER - LAPTOP | OWNER | OWNER | | - | YES | YES | - | - | - | | | 4 | | \$ 800 | | | | |
| 03-106 | WALL MOUNTED COMP STATION | OWNER | CONTRACTOR | | YES | YES | YES | - | - | - | ERGOTRON | 2140229 | 1 | COORDINATE LOCATION & HEIGHT WITH OWNER | \$ 2,000 | | | | |
| 03-301 | CREDIT CARD MACHINE | OWNER | OWNER | | - | YES | YES | - | - | - | | | 6 | | \$ 200 | | | | |
| 03-401 | TELEVISION - WALL MOUNTED 42" | CONTRACTOR | CONTRACTOR | | YES | YES | YES | - | - | - | | | 1 | CONFIRM HEIGHT & LOCATION W/ OWNER | \$ - | | | | |
| 03-401D | SECURITY MONITOR - WALL MOUNTED | CONTRACTOR | CONTRACTOR | | YES | YES | YES | - | - | - | | | 2 | CONFIRM WITH COUNTY IT | \$ - | | | | |

| | | | | | | | | | | | | | | | | | | | |
|---------|-------------------------------|------------|------------|--|-----|-----|-----|---|---|---|--|--|---|---|--------|--|--|--|--|
| 03-401E | TELEVISION - WALL MOUNTED 75" | CONTRACTOR | CONTRACTOR | | YES | YES | YES | - | - | - | | | 3 | PROVIDE ELECTRICAL OUTLET AND COAX CABLE CONNECTION AT HEIGHT SUCH THAT THEY WILL BE CONCEALED BEHIND THE TELEVISION. * CONFIRM HEIGHT AND LOCATION WITH OWNER PRIOR TO INSTALLATION; PROVIDE WALL MOUNT BRACKET; COORDINATE TELEVISION MODEL WITH OWNER'S A/V RE | \$ - | | | | |
| 03-401F | TELEVISION - WALL MOUNTED 85" | CONTRACTOR | CONTRACTOR | | YES | YES | YES | - | - | - | | | 3 | PROVIDE ELECTRICAL OUTLET AND COAX CABLE CONNECTION AT HEIGHT SUCH THAT THEY WILL BE CONCEALED BEHIND THE TELEVISION. * CONFIRM HEIGHT AND LOCATION WITH OWNER PRIOR TO INSTALLATION; PROVIDE WALL MOUNT BRACKET; COORDINATE TELEVISION MODEL WITH OWNER'S A/V REQUIREMENTS | \$ 800 | | | | |
| 03-502 | LABEL PRINTER | OWNER | OWNER | | - | YES | YES | - | - | - | | | 1 | | \$ 200 | | | | |
| 03-503 | PRINTER / COPIER - ON FLOOR | OWNER | OWNER | | - | YES | YES | - | - | - | | | 3 | | | | | | |
| 03-504 | PRINTER / COPIER - ON COUNTER | OWNER | OWNER | | - | YES | YES | - | - | - | | | 2 | | \$ 200 | | | | |
| 03-506 | MULTIFUNCTION PRINTER | OWNER | OWNER | | - | YES | YES | - | - | - | | | 3 | | | | | | |
| 03-902 | PROJECTION SCREEN - MOTORIZED | CONTRACTOR | CONTRACTOR | | YES | YES | - | - | - | - | | | 1 | COORDINATE WITH COUNTY | | | | | |
| 03-903 | PROJECTOR - CEILING MOUNTED | CONTRACTOR | CONTRACTOR | | YES | YES | - | - | - | - | | | 1 | COORDINATE WITH COUNTY | | | | | |

04 APPLIANCES

| | | | | | | | | | | | | | | | | | | | |
|---------|---|------------|------------|--|-----|-------------------|-----|-----|---|-----|----------------|-------------------|---|---|-----------|--|--|--|--|
| 04-101 | REFRIGERATOR / FREEZER | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | KENMORE | 60119 | 5 | | \$ 1,200 | | | | |
| 04-102B | REFRIGERATOR / FREEZER - WITH WATER | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | YES | KENMORE | 71323 | 1 | | \$ 1,100 | | | | |
| 04-103 | REFRIGERATOR - UNDER COUNTER | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | KENMORE | 99059 | 6 | | \$ 380 | | | | |
| 04-103B | REFRIGERATOR - UNDER COUNTER ADA HEIGHT | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | KENMORE | 99029 | 8 | | \$ 380 | | | | |
| 04-105 | REFRIGERATOR - COMMERCIAL UPRIGHT | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | CARRIER | EF34 | 2 | | \$ 2,000 | | | | |
| 04-107 | FREEZER - RESIDENTIAL CHEST | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | KENMORE | 46-16082 | 1 | | \$ 800 | | | | |
| 04-204 | WASHER/EXTRACTOR - COMMERCIAL 60 LB | CONTRACTOR | CONTRACTOR | | - | YES - CONFIRM | - | - | - | YES | SPEED QUEEN | SC60 | 3 | | \$ 12,000 | | | | |
| 04-205 | DRYER - COMMERCIAL - ST075 | CONTRACTOR | CONTRACTOR | | - | YES | - | YES | - | YES | SPEED QUEEN | ST075 | 3 | PLUMBING CONNECTION REQUIRED IF NOT ELECTRIC | \$ 16,000 | | | | |
| 04-206 | STACKED WASHER / DRYER - COMMERCIAL | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | YES | UNIMAC | LTUA7 | 6 | | \$ 1,200 | | | | |
| 04-301 | MICROWAVE - ON COUNTER | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | KENMORE | 73772 | 3 | IF MOUNTED ON CABINET SHELF COORDINATE REQUIRED DEPTH OF SHELF | \$ 300 | | | | |
| 04-401B | DISHWASHER - UNDER COUNTER ADA | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | YES | KENMORE | 12333 | 1 | | \$ 800 | | | | |
| 04-404 | DISHWASHER - COMMERCIAL | CONTRACTOR | CONTRACTOR | | - | YES - CONFIRM REQ | - | - | - | YES | HOBART | AM16VLT-BAS | 1 | | \$ 15,000 | | | | |
| 04-504 | HOOD VENT - SMALL | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | RE: MECHANICAL | | 1 | | | | | | |
| 04-601 | WATER COOLER | OWNER | OWNER | | - | - | - | - | - | - | | | 1 | | | | | | |
| 04-603 | ELECTRIC WATER COOLER W/ BOTTLE FILLER | CONTRACTOR | CONTRACTOR | | YES | YES | - | - | - | YES | RE: PLUMBING | | 3 | SEE PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION | | | | | |
| 04-701 | GARBAGE DISPOSAL | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | YES | INSINKERATOR | EVOLUTION COMPACT | 1 | SEE PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION | | | | | |
| 04-702B | COFFEE MACHINE | OWNER | OWNER | | - | YES | - | - | - | YES | | K3000SE | 2 | *CONTRACTOR TO COORDINATE WITH OWNER TO DETERMINE WHETHER WATER LINE REQUIRED | \$ 100 | | | | |
| 04-801 | VENDING MACHINE | OWNER | OWNER | | - | YES | YES | - | - | - | | | 2 | *CONTRACTOR TO COORDINATE WITH OWNER TO DETERMINE WHETHER CONNECTION TO DATA REQUIRED | \$ 3,500 | | | | |

05 MEDICAL EQUIPMENT

| | | | | | | | | | | | | | | | | | | | |
|---------|---|------------|------------|--|-----|-----|---|---|---|---|----------------------|--------------------|----|---|-----------|--|--|--|--|
| 05-101B | WALK-ON SCALE | OWNER | CONTRACTOR | | - | YES | - | - | - | - | SHOR-LINE | 905.5010.47 | 4 | CONTRACTOR TO PROVIDE CONDUIT; RE: 11&14/A9.01 | \$ 1,075 | | | | |
| 05-103 | COUNTER SCALE | OWNER | OWNER | | - | - | - | - | - | - | SHOR-LINE | | 7 | | \$ 290 | | | | |
| 05-117A | IV TRACK - 48" | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | AR NELSON | 1100IV - IV TRACK | 10 | CONTRACTOR TO COORDINATE FINAL HEIGHT AND LOCATION WITH OWNER | \$ 220 | | | | |
| 05-130 | DENTAL DELIVERY SYSTEM - ON CART | OWNER | OWNER | | - | YES | - | - | - | - | DENTALAIRE | PRESTIGE | 1 | | \$ 15,000 | | | | |
| 05-141 | MAYO STAND | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | 803.0010.00 | 4 | CONTRACTOR TO UNLOAD, UNPACK & STORE | \$ 2,000 | | | | |
| 05-153 | PATIENT MONITORING EQUIPMENT - SINGLE PARAMETER | OWNER | OWNER | | - | YES | - | - | - | - | | | 9 | | | | | | |
| 05-193 | POWER REEL | CONTRACTOR | CONTRACTOR | | YES | YES | - | - | - | - | HUBBELL INCORPORATED | PRO REEL 500A-30GF | 8 | | | | | | |
| 05-194 | CLIPPERS | OWNER | OWNER | | - | YES | - | - | - | - | ANDIS | | 4 | | \$ 150 | | | | |
| 05-201A | SST FOLD UP WALL MOUNT EXAM TABLE; RE: 5/A9.01 | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | TRISTAR | 400-23 | 6 | | \$ 1,100 | | | | |
| 05-201B | SST FOLD UP (TO USE) WALL-MOUNTED EXAM TABLE; ANCHOR PER MANUF. | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | TRISTAR | 400-25 | 2 | | \$ 1,100 | | | | |

| | | | | | | | | | | | | | | | | | | |
|---------|---|------------|------------|--|--------------------------|-----|---|---|-----|-----|----------------------|--------------------------------|----|--|-----------|--|--|--|
| 05-202 | SST LATERAL EXAM TABLE - FOLD UP, WALL-MOUNTED; RE: 5/A9.01 | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | SHOR-LINE | 903.1130.05 | 2 | | \$ 1,100 | | | |
| 05-206 | SURGERY TABLE- FLAT TOP, HEATED | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | SHOR-LINE | 903.4200.01 | 3 | | \$ 2,500 | | | |
| 05-207 | SURGERY TABLE - V-TOP | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | SHOR-LINE | 903.4400.01 | 1 | CONTRACTOR TO UNLOAD, UNPACK, & STORE | \$ 2,500 | | | |
| 05-217 | MOBILE LIFT TABLE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | 903.3120.00 | 4 | NEEDS RECHARGED | \$ 3,450 | | | |
| 05-301 | DOUBLE SURGERY LIGHT | CONTRACTOR | CONTRACTOR | | YES - STRUCTURAL SUPPORT | YES | - | - | - | - | MEDICAL ILLUMINATION | SYSTEM TWO | 4 | STRUCTURAL SUPPORT REQ'D. | \$ 6,950 | | | |
| 05-302 | SINGLE SURGERY LIGHT | CONTRACTOR | CONTRACTOR | | YES - STRUCTURAL SUPPORT | YES | - | - | - | - | MEDICAL ILLUMINATION | MI 1000 | 5 | STRUCTURAL SUPPORT REQ'D. | \$ 4,250 | | | |
| 05-310 | LIGHT MOUNT | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | ACCU-MOUNT | 200 SERIES | 4 | | \$ 2,500 | | | |
| 05-311 | LIGHT MOUNT | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | ACCU-MOUNT | 100 SERIES | 5 | | \$ 3,500 | | | |
| 05-410 | MICROSCOPE - SINGLE | OWNER | OWNER | | - | YES | - | - | - | - | | | 1 | | \$ 1,250 | | | |
| 05-421 | BLOOD CHEMISTRY MACHINE | OWNER | OWNER | | - | YES | - | - | - | - | IDEXX | CATALYST DX CHEMISTRY ANALYZER | 1 | PROVIDE CONNECTION TO UNINTERRUPTIBLE POWER SUPPLY (UPS) | \$ 20,000 | | | |
| 05-503B | OXYGEN OUTLET - CEILING | CONTRACTOR | CONTRACTOR | | - | - | - | - | YES | - | RE: MED GAS DRAWINGS | | 17 | CONFIRM HEIGHT & LOCATION WITH OWNER | | | | |
| 05-506 | OXYGEN MANIFOLD | CONTRACTOR | CONTRACTOR | | YES | YES | - | - | YES | - | RE: MED GAS DRAWINGS | | 1 | | | | | |
| 05-507B | OXYGEN TANK - H | OWNER | OWNER | | - | - | - | - | - | - | | | 6 | CAN STORE UP TO 3000 CU.FT.OF OXYGEN IN AN UNSPRINKLERED 1 HR. FIRE RATE ROOM (UP TO 6000CU.FT. IF SPRINKLERED) | | | | |
| 05-515 | ANESTHESIA MACHINE - ON CART | OWNER | OWNER | | - | - | - | - | - | - | SUPERA | OC6200 | 6 | | \$ 3,670 | | | |
| 05-517 | ANESTHESIA MACHINE - WALL | OWNER | CONTRACTOR | | YES | - | - | - | - | - | MATRX | VME2 | 3 | | \$ 30,000 | | | |
| 05-520B | ANESTHESIA SCAVENGER OUTLET - CEILING | CONTRACTOR | CONTRACTOR | | - | - | - | - | YES | - | RE: MED GAS DRAWINGS | | 14 | CONTRACTOR TO COORDINATE FINAL HEIGHT AND LOCATION WITH OWNER | | | | |
| 05-521 | ANESTHESIA SCAVENGER FAN | CONTRACTOR | CONTRACTOR | | YES | YES | - | - | YES | - | RE: MED GAS DRAWINGS | | 1 | PROVIDE EXHAUST DIRECT TO OUTSIDE. THE EXHAUST FROM THE BUILDING MUST BE A MIN. OF 10' ABOVE GRADE AND A MIN. OF 10' AWAY FROM AND FRESH AIR INTAKE. | | | | |
| 05-610 | AUTOCLAVE - COUNTER | OWNER | OWNER | | - | YES | - | - | - | - | | | 2 | | \$ 4,500 | | | |
| 05-615 | ULTRASONIC CLEANER | CONTRACTOR | CONTRACTOR | | - | YES | - | - | - | - | MIDMARK | M250 SONICLEAN | 1 | LOCATE NEAR SINK, NEEDS TO DRAIN PERIODICALLY | \$ 980 | | | |
| 05-703 | SST GROOMING TUB - 55" w/ Ramp | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | YES | SHOR-LINE | 904.0702.40 | 3 | OWNER TO CONFIRM CONFIGURATION | \$ 3,500 | | | |
| 05-706 | SST 46" TUB TABLE - RIGHT HAND KNEE SPACE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | YES | SHOR-LINE | 904.5000.09 | 1 | OWNER TO CONFIRM CONFIGURATION | \$ 2,400 | | | |
| 05-708 | SST 60" TUB TABLE - RIGHT HAND KNEE SPACE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | YES | SHOR-LINE | 904.5000.00 | 1 | OWNER TO CONFIRM CONFIGURATION | \$ 2,850 | | | |
| 05-708A | SST 60" TUB TABLE - LEFT HAND KNEE SPACE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | YES | SHOR-LINE | 904.5000.01 | 2 | OWNER TO CONFIRM CONFIGURATION | \$ 2,850 | | | |
| 05-720 | SCRUB SINK - SINGLE | CONTRACTOR | CONTRACTOR | | YES | YES | - | - | - | YES | RE: PLUMBING | | 2 | | \$ 3,200 | | | |
| 07-010 | INCUBATOR | OWNER | OWNER | | - | YES | - | - | - | - | | | 2 | | \$ 20,000 | | | |

06 IMAGING

| | | | | | | | | | | | | | | | | | | |
|--------|-------------------------------------|------------|------------|--|-----|---------------|---|---|---|---|-----------|-----------|---|------------------------|-----------|--|--|--|
| 06-109 | DIGITAL DENTAL X-RAY - WALL MOUNTED | OWNER | CONTRACTOR | | YES | YES | - | - | - | - | MIDMARK | VETPRO DC | 1 | | \$ 20,000 | | | |
| 06-111 | DIGITAL X-RAY | OWNER | OWNER | | - | YES - CONFIRM | - | - | - | - | | | 1 | CONFIRM SHIELDING REQ. | \$ 75,000 | | | |
| 06-117 | LEAD APRON RACK | CONTRACTOR | CONTRACTOR | | YES | - | - | - | - | - | JORGENSEN | J0676R | 1 | | \$ 175 | | | |

07 ANIMAL HOUSING

| | | | | | | | | | | | | | | | | | | |
|---------|--|------------|------------|--|---|---|---|---|---|---|-------------------------|---------|----|------------------------------------|----------|--|--|--|
| 07-030 | SMALL MAMMAL CAGE | OWNER | OWNER | | - | - | - | - | - | - | CRITTER NATION | 2 LEVEL | 1 | | \$ 300 | | | |
| 07-102 | CAGE WHEELS | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | BY MFR. OF CAGING ABOVE | CUSTOM | 3 | | \$ 110 | | | |
| 07-104 | CAGE STORAGE - DRAWERS | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | BY MFR. OF CAGING ABOVE | CUSTOM | 40 | | | | | |
| 07-105 | CAGE STORAGE - CLOSED, DOOR | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | BY MFR. OF CAGING ABOVE | CUSTOM | 20 | | | | | |
| 07-110A | SST CAGE, 30"W X 30" T, GRILLE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 14 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 600 | | | |
| 07-110B | SST CAGE,36"W X 30"T, GRILLE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 22 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 650 | | | |
| 07-110C | SST CAGE, 42"W X 30"T, GRILLE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 12 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 750 | | | |
| 07-110D | SST CAGE, 48"W X 30"T, GRILLE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 12 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 980 | | | |
| 07-110E | SST DOUBLE CAGE, 60" W x 30"T, GRILLE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 17 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 1,230 | | | |
| 07-110F | SST CAGE - 60"W X 36"T - GRILLE, WITH DIVIDER | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 3 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 1,435 | | | |
| 07-110G | SST CAGE - 72"W X 30"T - GRILLE, WITH DIVIDER | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 2 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 1,725 | | | |
| 07-115A | SST CONDO - DOUBLE WIDE, 48"W X 30"T, GLASS/GRILLE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 6 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 980 | | | |
| 07-115B | SST CONDO - DOUBLE WIDE, 54"W X 30"T, GLASS/GRILLE | CONTRACTOR | CONTRACTOR | | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 14 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 1,435 | | | |

| | | | | | | | | | | | | | | | | | | | |
|---------|---|------------|------------|-----|---|---|---|---|---|---|-------------------------|---------------------|-----|--|----------|--------|--|--|--|
| 07-135A | LAMINATE CONDO - 58"W X 31"T, FROSTED, GLASS BACK | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SNYDER | CUSTOM | 20 | VENTED, PORTAL, FROSTED GLASS/ BAR FRONT, GLASS BACK, BENCH AND INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 1,750 | | | | |
| 07-135B | LAMINATE CONDO - 58"W X 31"T, FROSTED | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SNYDER | CUSTOM | 8 | VENTED, PORTAL, FROSTED GLASS/ BAR FRONT, BENCH AND INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 1,750 | | | | |
| 07-140A | LAMINATE CONDO - SPLIT DOUBLE - VENTED, 58"W X 32"T, GLASS/GRILLE | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SNYDER | CUSTOM | 12 | INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 2,000 | | | | |
| 07-190B | MEDIUM CAT TOWER | OWNER | OWNER | - | - | - | - | - | - | - | CRIFO PET PRODUCTS, LLC | MT | 2 | | \$ 500 | | | | |
| 07-202 | DOG RUN - GATE | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 148 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY, NO BOTTOM BAR AT RUN GATE AND INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 740 | | | | |
| 07-203A | DOG RUN - GATE - 2 PANEL | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 202 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY, NO BOTTOM BAR AT RUN GATE AND INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 1,050 | | | | |
| 07-203B | DOG RUN - GATE, 2 PANEL, 30"W x 78"T, GLASS/BARS | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 92 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY, NO BOTTOM BAR AT RUN GATE AND INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 1,050 | | | | |
| 07-203C | CAT RUN - GATE, 2 PANEL, 30"W x 78"T, GLASS/BARS | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 5 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY, NO BOTTOM BAR AT RUN GATE AND INCLUDE CAGE CARD HOLDER ACCESSORY | \$ 1,050 | | | | |
| 07-204A | DOG RUN - FLAG PANEL 2'-6" | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 168 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY | | | | | |
| 07-204B | DOG RUN - CLERESTORY PANEL | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 8 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY | \$ 675 | | | | |
| 07-204C | CAT RUN - CLERESTORY PANEL, GLASS/SST | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 5 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY | \$ 675 | | | | |
| 07-204D | CAT RUN - SIDE, 2 PANEL, GLASS/PLAM | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 4 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY | \$ 1,100 | | | | |
| 07-205A | DOG RUN - SIDE PANEL | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 142 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY | | | | | |
| 07-205B | DOG RUN - SIDE PANEL, 78" T , GLASS/SST | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHORLINE | CUSTOM | 28 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY | \$ 950 | | | | |
| 07-207 | DOG RUN - BACK PANEL | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 117 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY | \$ 900 | | | | |
| 07-208 | DOG RUN - TOP PANEL | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 167 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY | \$ 800 | | | | |
| 07-210 | GUILLOTINE DOOR - IN RUN PANEL | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 117 | | \$ 250 | | | | |
| 07-211 | GUILLOTINE DOOR - IN WALL | CONTRACTOR | CONTRACTOR | YES | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 96 | CONFIRM BLOCKING REQUIREMENTS WITH MANUF. BASED ON WALL ASSEMBLY | \$ 250 | | | | |
| 07-212 | SALOON DOOR | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | BITEGUARD | BG 1624 | 90 | | \$ 1,000 | | | | |
| 07-214 | CAT DOOR - IN GLASS | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | HALE | DOOR - SMALL MEDIUM | 7 | | | | | | |
| 07-232 | CAT PERCH | OWNER | OWNER | YES | - | - | - | - | - | - | | | 6 | | | | | | |
| 07-235 | CAT SHELF | CONTRACTOR | CONTRACTOR | YES | - | - | - | - | - | - | SHOR-LINE | CUSTOM | 5 | 8" X 24" SOLID SURFACE, RE: EQUIP DTLS | \$ 180 | | | | |
| 07-241 | KARUNDA BED | OWNER | OWNER | - | - | - | - | - | - | - | KARUNDA | | 12 | | \$ 150 | | | | |
| 07-651 | BARN TROUGH | OWNER | OWNER | - | - | - | - | - | - | - | HUMANE | | 6 | | | \$ 400 | | | |
| 07-652 | STALL MAT | OWNER | OWNER | - | - | - | - | - | - | - | HUMANE | | 6 | 1 1/2" MIN THICKNESS | | \$ 200 | | | |
| 07-653 | HORSE FEEDER | OWNER | OWNER | - | - | - | - | - | - | - | | | 6 | | | \$ 400 | | | |
| 07-654 | HOG - GOAT FEEDER | OWNER | OWNER | - | - | - | - | - | - | - | | | 6 | | | \$ 400 | | | |
| 07-655 | CHICKEN COOP | CONTRACTOR | CONTRACTOR | - | - | - | - | - | - | - | CAROLINA COOPS | AMERICAN COOP | 1 | PRE-MANUFACTURED CHICKEN COOP, COORDINATE WITH OWNER ON ACCESSORIES | \$ 7,000 | | | | |

| FULCO IT/PHONE/SECURITY ITEM | Type | Responsibility | |
|---|---------|----------------|-----|
| | | FULCO | WJG |
| Networking | | X | |
| Server Racks | Equip | | X |
| Servers - Switches | Equip | X | |
| Phones | Equip | X | |
| Desktop Computers | Equip | X | |
| Laptop Computers | Equip | X | |
| Laptop Docking Stations | Equip | X | |
| Computer Monitors | Equip | X | |
| Printers | Equip | X | |
| Credit Card Reader | Equip | X | |
| Camera Switches | | | X |
| Cameras | Turnkey | | X |
| Card Readers - Access Control | Turnkey | | X |
| Cabling | Turnkey | | X |
| Security Monitors | Equip | X | |
| VoIP - Phones | Equip | X | |
| Wireless Access Points - backbone | Cabling | | X |
| Wierless Access Points - | Equip | X | |
| Analog Lines - (AT&T, backbone) | | | X |
| UPS | | | X |
| Electrical Circuits - Add to Const. Docs | | | X |
| AT&T Circuit (Abdias) | | X | |
| Comcast Circuit (Abdias) | | X | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| RFI # | Date Issued | Drawing/Spec Reference | Description - RFI (by WJG u.n.o.) | Response Date | Description - RESPONSE (by PGAL u.n.o.) |
|-------|-------------|------------------------------|---|---------------|---|
| 1.01 | 10/20/21 | Elevation 1/A6.13 | Drawing calls out the same item as a "composite wood tellis system" and a "painted metal trellis." Please clarify which one is correct. | | Composite Wood Trellis system is correct. |
| 1.02 | " | " | Please confirm that there will be no multi-color storefront framing finishes (Section 084113, 2.3A.1.a) , i.e. dark bronze on one side and clear anodized on the other. | | All storefront systems will be anodized bronze throughout. We will revise the specifications accordingly. |
| 1.03 | " | A2.13, A2.14, A2.23, A2.24 | Please furnish specifications and detail for the canopy/trellis systems at the yards typical of room #207. | | Trellis system is to be a pre-manufactured and prefinished aluminum trellis. Basis of Design: Awnex, Tuscany system, sun shade panel option. This is applicable to room #080, #146/7, #205 & 206, #207 & 208, #307 & 308, #407 & 408, #507 & 508, #607 & 608. |
| 1.04 | " | 2/A7.55 | Would products by Mitchell Metals or Peachtree Protective Covers be acceptable for the exterior rod-hung doorway canopies? | | Yes, these should be acceptable pending architectural review of submitted product. |
| 1.05 | " | | Please specify location of the CW3-designated curtainwall system. | | CW3 curtain wall system drawing is incorrect in the documents. Please see the attached revised curtain wall elevation. It is located along column line A to the east of 11.5. |
| 1.06 | " | | Please clarify the type of countertops in rooms numbered 110 Dental, 112 Pharmacy, and typical Exam rooms - solid surface or plastic laminate countertops? | | Plastic laminate with the specified edge banding is correct. |
| 1.07 | " | Section 084113, 2.3A.1.a | Please confirm that there will be no multi-color storefront framing finishes as discussed at the 8-18-2021 meeting. | | See RFI response 1.02 |
| 1.08 | " | Section 084113, 2.3E | Please advise on locations of Vent Windows on the project. | | See revised drawings |
| 1.09 | " | | Please furnish specification for the freezer system for the room #159. Freezer. | | See Spec 114000, 2.3C |
| 1.10 | " | Specification Section 122413 | Please advise on the selection of rooms and locations to receive the roller shades | | Room #009 @ window and storefront, #025 both, #026, #099, #098 both, #104, #105, #106 all, #119, #126 |
| 1.11 | " | C4.40 | Please advise on the diameter of the OCS | | Response from Lowe Engineers: The Diameter of the OCS (Structure 1.1) is 6ft |
| 1.12 | " | A0.10 | Partition types for all masonry walls show them as fully grouted. This does not match the requirements of S4.01. Please clarify. | | Architectural drawings will revise wall section to indicate "For grouting and reinforcing requirements, see structural drawings." |
| 1.13 | " | A1.10 | This sheets shows a gravel path for Ga Power access. Keynote 30 on C3.02 calls this out as a dirt path. Please clarify. | | Civil is correct, Architectural will revise note. |
| 1.14 | " | A1.10 | Please confirm that the EV ready spaces for the employee parking lot are correctly identified per sheet E1.03. | | Confirmed. 7 standard EV-ready spaces in parking lot. 20 oversized EV-ready spaces along drive. |
| 1.15 | " | A1.10 | The note for the public parking area calls for 7 EV ready spaces. Sheet E1.02 has circuiting for 5 spaces identified. Please clarify. | | E1.02 is correct, architectural will revise. |
| 1.16 | " | 4/A1.10 | Dock lift pit width dimension is shown as 6'6", but the notes call for the width to be 6'2". Please clarify. | | Please see revised detail and mfr. documentation regarding pit dimensions |
| 1.17 | " | A2.02 | No depression is shown for the freezer on this sheet but S2.12 does show a depression. Please clarify | | Arch to update on the EOS plan. |
| 1.18 | " | A2.02, P2-12 | A floor drain is shown in the freezer. Is the intent for this drain to be under the freezer floor or actually cut into the freezer? | | The drain is in the slab, freezer will not have a floor system (slab serves as the freezer floor). |

| | | | | | |
|------|---|------------------------------|--|--|---|
| 1.19 | " | A7.50, A7.52 | Various details on these sheets show a perimeter drainage system. No further information was found. Please clarify. | | No perimeter drainage system, arch to revise details. However, downspouts that are NOT within dog kennel yards will be tied into the storm system below grade. Civil is revising their documents. |
| 1.20 | " | A1.20, 4/A7.58, S2.22 | No support is shown for the upper run of the roof stair at the garage. Please advise. | | There will be posts from the top landing down to grade, as well as posts up from the CMU parapet to support the walk-over and stairs down to the roof side. Structural: Detail 5/S5.09 has been added showing the stair supported on the CMU wall and floating above the roof. |
| 1.21 | " | G1.10 | Please advise which fire extinguisher cabinets are surface mounted and which are recessed. All the symbols are the same. | | All cabinets are to be fully recessed. If a cabinet can not be fully-recessed due to unforeseen construction circumstances, then semi-recessed is acceptable. No cabinets should be surfaced mounted. |
| 1.22 | " | A2.12, room 162 | The north and west walls in the mechanical room are scheduled as M580. Should these walls go to the deck? | | Yes. Arch to revise to M880 partition type. |
| 1.23 | " | 3/A9.03 | Please advise on how the veneer be supported above the saloon doors. No structural section was found for this condition. | | Steel angle lintel, see structural for sizing requirements. Structural: Veneer above the saloon door shall be supported by loose lintel. Loose lintel schedule has been added. Arch will revise the detail. |
| 1.24 | " | A7.12, 2/A7.30 | Sections 3 and 4 on A7.12 call out detail 2/A7.30 in multiple locations. This does not appear to be correct. Please clarify. | | Wall section is typical to the wall section shown on 2/A7.30, however exterior slab condition is different. Arch. to provide additional detail for clarity, see RFI 1.35 for more information. |
| 1.25 | " | E1.03 | Utility Pad Mount – Keynote 12, EC to provide and install all Primary conduit between nearest utility switch and the Pad Mount for the Building. Please advise on location of the nearest utility switch. | | Per coordination call with Georgia Power, it's understood there is a current project in progress along Fulton Industrial Blvd that is covering existing primary overhead lines to underground. It was noted that GP would be able to "splice and connect for service to our building anywhere along the frontage of our building as a result of everything being underground." Now that 100% CDs are complete, next steps can be taken with GP to finalize the location of the primary connection point, which is intended to be due north of the service transformer on the south side of Fulton Industrial Blvd as indicated on the electrical site plan. It's understood a new switch or tap enclosure will be provided by GP. |
| 1.26 | " | E3.11 | Light Fixture types not called out for Day Foster Office 076A. | | L1-4' |
| 1.27 | " | E3.11 | Light Fixture types not called out for Rescue Coord Office 076B. | | L1-4' |
| 1.28 | " | E3.11, E3.12, E3.13 | Please confirm that the ceiling fan and its controls are to be Owner-Furnished, Owner-Installed. Contractor only provide power to the fan location. | | Ceiling fans to be contractor provided / contractor installed. Ceiling fan basis of design: Big Ass Fans, Essence, 8', Oil Rubbed Bronze finish, LED light kit. |
| 1.29 | " | e.g. 4/A7.52 | The drawing details show an "air/moisture barrier" on top of the substrate board. This is not called for in the specifications. Please clarify. | | Air barrier not required above substrate board at roof. Arch to revise. |
| 1.30 | " | Section 075423, e.g. 4/A7.53 | The drawing details call for the substrate board to be 5/8" but the specification section 075423, Paragraph 2.5, A is calling for a 1/2" | | 1/2" substrate board is acceptable. Arch to revise. |
| 1.31 | " | E1.03 | Utility Pad Mount – Keynote 12, EC to provide and install all Primary conduit between nearest utility switch and the Pad Mount for the Building. Please advise on location of the nearest utility switch. | | Duplicate to RFI 1.25 |
| 1.32 | " | E1.03 | Utility Pad Mount – Keynote 12, electrical contractor to provide and install all Primary conduit between nearest utility switch and the Pad Mount for the Building. Please advise on location of the nearest utility switch. | | Duplicate to RFI 1.25 |

| | | | | |
|------|---|------------------------|--|---|
| 1.33 | " | E6.01 | The breaker on feeder from the main switchboard to the mechanical chiller is designated as 110A/3ph, which seems inconsistent with the chiller schedule information on sheet M1-03. If incorrect, please advise on correct breaker size. | The breaker for Chiller Circuit 2 connected to the MSB is understood to be 250A/3P. Chiller Circuit 1 is 350A/3P and connected to standby panel HSA. Electrical one-line diagram and schedules will be revised to clarify correct chiller circuit labeling and corresponding breaker sizes. |
| 1.34 | " | A2.12 | What is the partition type that separates courtyards 146 and 147? | 8" Masonry wall with 4" Trenwyth block (both sides) to match surrounding courtyard walls, provide cast stone coping at the top, similar wall section to monumental sign. Height to be 8'-8" to bottom of cast stone coping. Arch to provide detail revision in updated drawings. |
| 1.35 | " | A2.11, A2.12, 13/A1.19 | If the K9 grass called out on 13/A1.19 is to be installed in courtyards 80, 146 and 147, won't these slabs need to be depressed? If so, please provide details. | Yes, slabs will be depressed. Arch to provide detail. |
| 1.36 | " | S2.21, S2.22, 4/S5.05 | Please provide connection details for the L8x4x1/2 shown at the north and south ends of courtyards 80, 146 and 147. The section cut through these areas, 4/S5.05 does not include them. | Structural: Connection is similar to connection shown in detail 5/S5.07. Clarification has been made. |

| RFI # | Date Issued | Drawing/Spec Reference | Description - RFI (by WJG u.n.o.) | Response Date | Description - RESPONSE (by PGAL u.n.o.) |
|-------|-------------|--------------------------------|---|---------------|--|
| 2.01 | 10/26/21 | A1.15B | Please advise on the paver color selections. | | Light Pavers: Techo Paver HD smooth, Shale Grey, 051353; Dark Pavers (dark hatch on drawings): Techo Paver HD Smooth, Greyed Nickel 051310 |
| 2.02 | " | A1.15B | The paver system specs call for #57 stone, #8 stone, geofabric and sand. Please provide section cut detailing the thicknesses of the layers. | | See attached detail from manufacturer |
| 2.03 | " | | We assume that heat required in room 114? Please confirm. | 10/26/21 | Heat is not required in this room. |
| 2.04 | " | | Is heat required in room 115? | 10/26/21 | Yes, heat is required. We will add a 3kW electric cabinet unit heater in future revised drawings. |
| 2.05 | " | M2-12 | Does code allow ductwork in the electrical room as is currently? | 10/26/21 | Ductwork is allowed in the electrical room, but will need to be re-routed to avoid running above electrical panels. Updated duct routing will be provided in future revised drawings. |
| 2.06 | " | Section 230923 | There are no manufacturers listed for the Direct Digital Control (DDC) system for the HVAC. Please provide acceptable manufacturers so we can solicit multiple providers for competitive pricing. | 10/26/21 | 20/20 Engineering's only requirement is that the manufacturer be approved for use by Fulton County. |
| 2.07 | " | Section 084113, A0.31 | Paragraph 2.4A.1 aluminum entrance door specifications call for narrow stile YKK 20D series doors, which are 1¾" thick. Same specification calls for 2" thermal (even at interior) doors which is medium stile. Furthermore, hardware schedule specify door types FG1 and FG2 as medium and wide stile doors. Please advise on what aluminum entrance door specifications to price. | | No narrow stile doors; Specs to be updated to include medium and wide stile doors. Aluminum entrance doors to be medium stile doors. |
| 2.08 | " | drawing detail 2/P4-00 | Detail references slack cables and spring hangers. Is this something that needs to be on all of our hangers? Or just certain sizes? | 10/26/21 | Slack cables and spring hangers are not required on every hanger. Specific locations to be determined at a later date based on the total weight being supported. |
| 2.09 | " | sections 083323, 08330, 083613 | It appears that "Section 083323 Overhead Coiling Doors" and "Section 083330 Overhead Coiling Grilles" are the only overhead door systems applicable to the project, and are at the intake garage and the reception area respectively. Please confirm. Is provide door number on the door schedule for the overhead grille. | | Yes - only (4) Overhead Coiling Doors in the project and are located at the Intake Garage. Only (1) Overhead Coiling Grille and is located at the Adoption Lobby. Door Number can be given for the grille. |
| 2.10 | " | | Can the AISC certification requirement for the fabricator be waived if they can furnish an annual independent review of their shop policies and procedures, and can offer a 'job specific' inspection during fabrication for this project? | | This will require further review and response sent in the few days. |
| 2.11 | " | section 042000 | Paragraphs 3.5 and 3.6 call for cavity rigid insulation to be adhered to the masonry block. Please confirm this is not required? | | Not required to be adhered to the block, but must be secured in place. |
| 2.12 | " | section 042001 | Paragraph 2.10 is calling for Loose-Fill Insulation "Perlite." Please confirm that this is not needed as the cavity has rigid insulation. | | This is not for cavity insulation, but for masonry cell fill insulation. Given that there is no longer any single wythe exterior wall construction on the project, this application would not be necessary. |
| 2.13 | " | A1.18 | Please clarify the dimensions and model of the chicken coop. | | Dimensions have been added - see sketch |
| 2.14 | " | C3.02 | Regarding Key Note 29 can you clarify the crosswalk work that is shown? Does it need to be done or do we need to exclude it based on the note saying that a revision is "to be designed an permitted in a separate document sent to GDOT"? | 10/26/21 | Lowe Engineers: The crosswalk that is being referenced in Key Note 29 is referring the existing GDOT crosswalk at our signalized driveway entrance. This is detailed more in the plans that we submitted to GDOT. Plans can be provided to PGAL and WJG if needed. |

| | | | | | |
|------|---|-------------------------|--|----------|---|
| 2.15 | " | " | Can details be provided for the building perimeter downspout tie-ins to the storm drain system along with the secondary storm drainage layout? | 10/26/21 | Low Engineers: We spoke with PGAL and Low Engineers will show downspout connections to the proposed stormwater system rather than having a full perimeter system. PGAL: All Downspouts are to be connected to offset powder coated gray iron downspout boots. These will be connected to the storm system. At dog runs, downspouts are pvc pipes to drain to yard. |
| 2.16 | " | C5.01, C5.02 | What class DIP sewer pipe is needed? | 10/26/21 | Low Engineers: Class 250 with a minimum of a Class "C" bedding |
| 2.17 | " | C5.01 | A sized jack and bore is indicated for the water tap on Fulton Industrial Boulevard. None is shown for the sanitary sewer tap. Please advise on whether the sewer line A1 to A0 (tie-in to existing) needs to be jack and bore, and if so what size is required? | 10/26/21 | Low Engineers: ±42 LF of Jack & Bore with 16" steel encasement. For the water line we used a 5ft wide pit. If this needs to be modified to allow easier access please let us know and we will denote it on our plans. |
| 2.18 | " | C3.01, Key note 29 | Regarding the curb and gutter re-configuration in the middle of Fulton Industrial Blvd. at the southern entrance, we assume this work is to be performed by the owner outside of Winter Johnson's scope of work? Please confirm. | 10/26/21 | Low Engineers: We can speak with GDOT District 7 to determine who will need to perform the work. We are proposing the medians to force a right-in/right-out only at the unsignalized intersection. |
| 2.19 | " | " | Please clarify what the GDOT asphalt paving profile is for the decel lanes shown on Fulton Industrial Boulevard. | 10/26/21 | Low Engineers: We can add a paving profile to our plans for the next submittal unless needed sooner for internal coordination |
| 2.20 | " | HVAC | Please advise whether equivalent Chilled Water & Hot Water AHUs, Air Cooled Heat Recovery Chiller, Chilled Water & Gas Heating DOAS, Ductless Split System Heat Pump, VAV Box, Energy Recovery Unit, DDC Controls systems from Trane are acceptable. | 10/26/21 | Trane will be considered as an approved alternate if all equivalent components match the performance listed as well as the accessories, dimensions, weights, and electrical specifications. Any additional engineering or design support will be financially responsible by the vendor/contractor prior to approval. |
| 2.21 | " | Sections 084113, 102219 | Are Doors #002A, 002B, 004, 005 & 007 supposed to be a part of the demountable partitions system, or interior storefront (with Sliding Doors)? | | Doors 002A, 002B, 004, 005, 007, and 008A are to be part of demountable partition systems. |
| 2.22 | " | A2.11, S2.11 | Please provide details/direction for operable partition support steel. | | Detail provided on 4/A3.20 |
| 2.23 | " | Sections 084113, 084413 | Please confirm if equivalents of the specified YKK storefront, curtainwall, and aluminum entrance systems from Kawneer, EFCO or Tubelite would be acceptable. | | Yes, they are acceptable as long as the products being priced meet the performance / function / quality level as specified in the YKK systems |
| 2.24 | " | section 096723 | Please confirm if Key Resin Company's equivalent to the Dur-A-Flex system specified for Resinous Flooring is acceptable? | | Currently being studied |
| 2.25 | " | section 075423 | Paragraphs 3.5, C, 1 & 2 state to loose lay the substrate board, mechanically attach the first layer of polyisocyanurate, loose lay or adhere the second layer of Polyisocyanurate then adhere the cover board. The roof system is mechanically attached as stated in paragraph 1.2 A1. Please confirm that it is acceptable to gang fasten all layers simultaneously, and then mechanically attach the TPO. This will not have any effect on the manufacturer's warranty. | | Technically, this is acceptable. PGAL has reached out to the County for confirmation that the installation method and warranty would be acceptable to the County. |
| 2.26 | " | HVAC | Chilled Water & Hot Water AHUs, Air Cooled Heat Recovery Chiller, Chilled Water & Gas Heating DOAS, Ductless Split System Heat Pump, VAV Box, Energy Recovery Unit, DDC Controls | 10/26/21 | Question is unclear. |
| 2.27 | " | S2.21 | Per the marked up drawing sheet S2.21 attachment, please furnish clarifications regarding the HSS 4x4 column. | | Clarification has been provided in "GMP Structural Revisions" package |
| 2.28 | " | S2.22 | Per the marked up drawing sheet S2.22 attachment, please furnish clarifications regarding the HSS beam. | | Clarification has been provided in "GMP Structural Revisions" package |
| 2.29 | " | S7.01 | Per the marked up drawing sheet S7.01 attachment, please furnish clarifications regarding the location of some steel members. | | Clarification has been provided in "GMP Structural Revisions" package |
| 2.30 | " | sections 074213 | Would equivalent metal wall panel systems by Alfrex be acceptable for the project? | | Yes, this is acceptable. PGAL has asked if any of the sub-contractors have experience with the product and where it has been installed previously. |

| RFI # | Date Issued | Drawing/Spec Reference | Description - RFI (by WJG u.n.o.) | Response Date | Description - RESPONSE (by PGAL u.n.o.) |
|-------|-------------|------------------------|---|---------------|--|
| 3.01 | 10/27/21 | A2.01 & A 2.02 | There appear to be raised areas shown on the slab plans on A2.01 and A2.02 noted 0'-4", 0'-6" or 0'-8". Are these areas intended to be raised concrete housekeeping pads per detail 9/S3.03? | 10/28/21 | The raised areas are concrete or wood curbs noted with a material tag for built in animal housing. Detail 9/S3.03 is for the concrete pad under the washing machines in laundry. Reference sheets A9.04 and A9.05 for details of curb conditions. |
| 3.02 | " | 2 & 3/S6.01 | What is the edge of slab condition at the Yards/Outdoor Runs? 2 & 3/S6.01 appear to show a turn-down but no section or detail is provided. Please provide a section or detail that shows required dimensions and reinforcing if a turn-down is required. | | The edge condition at the yards is a 1'-0" wide x 2'-8" deep turn-down, similar to, and reinforced, like one shown in detail 2/S3.04. |
| 3.03 | " | A1.18 | Please provide foundation/slab plan and details for the barn structure | 10/28/21 | The barn manufacturer does all the engineering for the barn including foundation and slab. All details will be provided by the manufacturer. That will be coordinated as a submittal later. |
| 3.04 | " | 1/S3.01 | Footing types F5.0, F6.0SP, F6.0x10.0 and F6.0x12.0 are listed on the footing schedule on 1/S3.01 but are not shown on the foundation plans. Please verify these footings types are not applicable to the project. | | Confirmed. Footings not shown on plan are not applicable to the project. |
| 3.05 | " | Section 051213 | The specifications mention AESS. Please confirm that AESS is not required on the project. | 10/28/21 | There is architecturally exposed structural steel on the project. Please adhere to specifications. |
| 3.06 | " | S0.01 | SS-1.4 states that all steel permanently exposed to weather is to be galvanized. Is the exposed galvanized steel to be finish painted. If so, please identify specific members and paint finish type. | 10/28/21 | Painted Steel does not need to be galvanized. To have Primer Coat of Carbozinc 859 VOC, Mid Coat of Carboguard 890 VOC, and Top Coat of Carbothane 134 MC. All from Carboline. See attached specs. |
| 3.07 | " | Section 087100 | Are doors 017, 104, 107A, 108A, 135 and 300B hollow metal, wood, or aluminum? If aluminum, what hardware set should be priced? | 10/28/21 | All doors listed are Aluminum doors |
| 3.08 | " | L1.0 & A1.17 | A1.17 details RT-1 as the dog yard floor material. L1.0 notes pea gravel. Please clarify which material is correct. If rubber turf is the correct material, please confirm that Spec Section 027920 applies to this location. Please also confirm that no drainage is required for these dog yards. | 10/28/21 | RT-1 is correct for the dog yards. That is the correct spec section. No drains are shown for these yards. Reference detail 10/A1.19 fence detail for keeping the rubber in the fence. |
| 3.09 | " | C3.02 | Please provide additional detail or narrative for Note 30 "Dirt Path" Are there compaction requirements? Are there transition details between asphalt and dirt? | 10/28/21 | Per the geotech provided by Wood PLC dated 4/14/2020 We should anticipate a compaction of at least 95% in thin 8" lifts (ASTM D 698). We do not have a transition detail between the asphalt and gravel at this time. We are showing a curb cut at each of the entrances to the dirt path with fencing as well. If needed we can provide one in the next submittal |
| 3.10 | " | | Detail 2 on A1.17 shows fence type FC-1, FC-2 and FS-2 but there are no details associated with those types. Please provide additional fence details or advise on the correct fence type tag. | 10/28/21 | Fencing Types legend on A1.17 states the special conditions of "C and S" for fences and the types. For example, FS-2 is F-2 fence type with privacy slats. |
| 3.11 | " | A1.15 through A1.18 | Except for the 8' aluminum picket fencing on the site retaining wall at Fulton Industrial boulevard, the heights of the remainder of the fencing is not stated. Please clarify heights of each fence type. | 10/28/21 | See attached sketch for additional site fence heights. Fence heights around the dog yards are called out on Fencing Type Legend on Sheet A1.17 |
| 3.12 | " | G1.10 through G1.1 | Symbol legend refers to FER-C as both surface mounted and fully recessed. Please clarify. | 10/28/21 | Fully Recessed FECs are to remain as FEC-R. Surface Mounted FECs are renamed to FEC-S. Please see attached updated LS drawings. |


| | | | | | |
|------|---|---------------------------|--|----------|--|
| 3.13 | " | C3.01. C3.02 and C9.00 | Is any thermoplastic striping required? Please advise. | 10/28/21 | Yes. We are planning on using thermoplastic striping for the parking and turn lane stripes. Let us know if you need further information or if there is a preferred alternative |
|------|---|---------------------------|--|----------|--|

| RFI # | Date Issued | Drawing/Spec Reference | Description - RFI (by WJG u.n.o.) | Response Date | Description - RESPONSE (by PGAL u.n.o.) |
|-------|-------------|-----------------------------|--|---------------|--|
| 4.01 | 10/28/21 | Section 088000 | GL-S glass type is requiring sound insulation. What is the STC requirement? | 10/29/21 | There is no STC requirement. Insulated glazing is required at sound walls to provide a higher level of acoustic performance in that particular wall assembly, however no STC rating is required for the glazing itself. Typical 1" insulated glass has been tested to achieve a value of STC 35. Glazing to match specifications for glazing thickness and total assembly thickness. |
| 4.02 | " | Section 088000 | Frames M and Z on A0.40 do not have detail call outs or glass type call outs. Please advise. | 10/29/21 | Glass Type for "M" and "Z" frames is to be GL-I. Note that both M and Z frames are found at the Surgery Rm #106. The window labeled "R4" is mislabeled and should be the "M" type window. This will be corrected on the drawings. |
| 4.03 | " | A5.12 | Detail indicates a thin layer on CMU wall projection in detail 2. The typical elevations of this wall on 3/A6.10 show CMU continuing to the end of the projection. Please specify what coating or paint goes on this wall projection. | 10/29/21 | Detail2/A5.12 shows the transition between the CMU exterior wall of the building envelope and the single-wythe CMU wall that extends out from the building. There is no coating or paint to be applied to the CMU in the single-wythe wall extension. I believe that there may be some confusion graphically associated with a line that is appearing around that wall. The line will be removed or noted separately. The wall is intended to be decorative Trenwythe CMU only with no additional coating or painting. |
| 4.04 | " | C2.01, C2.02 | Key note #4 states "STORMWATER STRUCTURE TO BE RELOCATED. SEE GDOT PLANS BY LOWE ENGINEERS DATED XX/XX/2021." The note is referencing the existing Catch Basins along Fulton Industrial Blvd. Please confirm that this work is part of the GDOT package to be performed outside Winter Johnson's scope of work. | 11/1/21 | The permit approval and process is through GDOT but the actual work to be completed with the turn lanes will need to be done by the Contractor whether its WJG or someone else. |
| 4.05 | " | P1-03 | Please provide direction on location of trap primers and or trap guards. Trap guards are only shown on the floor sinks FS-1 but our plumbers do not recommend that they be used in any area that has a high likelihood of large amounts of hair and or large debris due to the risk of repeat clogging. | | Trap guards to be provided on all floor drains/sinks that do not see frequent wash downs. Locations to be further detailed on a future ASI. (20/20 Engineering, Inc.) |
| 4.06 | " | P4-00 | Please provide direction on spring hanger requirements for plumbing piping. They are shown for all hangers on detail 2/P4-00 but they are not listed in the specs. Spring hangers for all piping will be a significant cost. | | Spring isolation is not required on any plumbing system piping (20/20 Engineering). |
| 4.07 | " | P1-03,A10.11 | SV-1 mixing valve is listed on the plumbing equipment schedule but not shown on any of the plans. Please provide direction as to where this mixing valve should be used. 09-620 is a Accel Mixing Station and locations are shown for this on A10.01-04. Please provide direction if these are for the same use. | | SV-1 is not included in the project's scope of work. Accel Mixing Stations are for chemical mixing for sanitary wash down procedures. These should not be included in the plumbing scope of work. (20/20 Engineering). |
| 4.08 | " | P2-23, P2-24, P2-34 1/A7-28 | Roof drain piping shown going to the roof in areas C&D but no roof drains shown. If these areas will be served by gutters and downspouts please provide direction on how the downspouts will be tied into the storm piping. | | Roof gutter and downspout outlets will connect to the 4" storm risers referenced on the plumbing plans. Detail to be incorporated on future ASI (20/20 Engineering). |
| 4.09 | " | P4-00, P1-03 | Please clarify if the hair traps HT-1 will be supplied with the associated equipment and should just be installed by the plumbing contractor or if they should be supplied by the plumber and they included equipment drains modified. | | Plumbing contractor to provide and install HT-1 as specified. HT-1 is a replacement basket strainer and tailpiece for the fixture (20/20 Engineering). |

| | | | | | |
|------|---|--|--|----------|--|
| 4.10 | " | E3.11 | Please provide labels for lights in rooms 076A and 076B at the matchline in sector B. | | |
| 4.11 | " | RFI 2.19 response | The GDOT asphalt paving profile for the decel lanes shown on Fulton Industrial Boulevard is needed now for pricing solicitation from bidding subcontractors. | | 1.5" of 9.5mm Superpave Asphaltic Conc. Surface Course, 2" of 19 mm Superpave Asphaltic Concrete Binder Course, and an 8" Graded Aggregate Base |
| 4.12 | " | A6.20 | Please clarify what the three CMU colors 1, 2, and 3 are. | 10/29/21 | Echelon Trendstone: CMU-1 Ground Face Color #4107, CMU-2 Ground Face Color #4205, CMU-3 Ground Face Color #4301 |
| 4.13 | " | section 042200, par. 2.5A; RFI 1.34 response | Please confirm that glazed block is eliminated from the project per VE #A14. | 10/29/21 | Correct Glazed Block is no longer to be installed in the project. Section will be removed from the specifications |
| 4.14 | " | section 042200, par. 2.5A; 6/A6.20 | Please confirm that Trendstone is not included on the project. | 10/29/21 | Trendstone is included and is scheduled to be the exterior masonry product for this project. Astraglaze product is no longer included on the project. Color selections as noted in detail 6/A6.20 to be priced, however final color/size decisions in the walls shown in details 6, 7, 8/A6.20 are TBD. |
| 4.15 | " | | Would it be acceptable to change structural steel canopies with roofing to pre-manufactured aluminum canopies? | 10/29/21 | Yes, that would be acceptable provided that the skyward side of the canopy system would be finished in white or light grey to prevent a heat island effect. |
| 4.16 | " | | Is every window location that gets rollershades indicated on the A8.? Please confirm. | 10/29/21 | See response to RFI 1.10 |
| 4.17 | " | | Is the DIRTT an acceptable substitution for the demountable systems? | 10/29/21 | Yes, provided that the dark bronze finish is available in the DIRTT system and that they can provide glazing over sliding glass doors at reception area. |



10/21/2021 GMP Impact Items - Narrative

1. Color for PL-1 changed from Vapor Strandz 4939K-18 to Dove Geo Y0677-60 (2-4 week lead time)
2. Color for PL-2 changed from Washi Gold 5019-38 to White Cascade 5003-38
3. Color for SS-1 changed from Oatmeal 9101GS to Frosty White Mirage 1573MG
4. Dog Gallery and Hall 010 are open to structure. Areas highlighted in red to have drywall bulkhead to go up to deck to close off plenum space in this area.




5. Sheet A4.11 shows Herringbone pattern tile in Single-Use Restrooms. This tile will be CWT-1 and will have 33% offset subway tile pattern (similar to elevations of restroom 049 and 050 on 3/A4.10).
6. Revisions to Equipment Schedule (per 10/18/21 meeting) – Revisions to be sent out on 10/22/21

- 7. Concrete Bench Seat - Possible product: Manufacturer: Vestre, Product: Corner




- 8. Study if Solid Wood doors should be stained or laminated



- 9. 022 Placement Coordinator Door to be Wood Door with HM Frame and moved for better privacy




- 10. Call boxes, keypads, card readers at gated entries to be added




11. Bollards around exterior equipment to be added




- 12. CMU veneer coursing to be studied (larger air gap vs expanding building to work with exterior coursing) – GC to contact mason.



- 13. Power to be added for Building Mounted Fulton County Sign
- 14. Revised Door Schedule Sent to GC on 10/20. 022, 119B, 120B, 121B, 122B, 126A, 127A to be wood doors; 503B to be Half Glass panel.
- 15. Dock lift to have drain (see email from Greg Mullin 10/21/21)




16. Downspouts to be tied into storm



10/25/2021 GMP Impact Items - Narrative

- 17. Walk Off Mats to be added to meet LEED Requirements (see attached diagram for locations)
- 18. Exterior Signage to be added at Intake Lobby/Clinic area. Will not need power
- 19. No Smoking Sign at all entries per attached diagram
- 20. Demountable Partitions at lobby to be priced out. Will be sent to GC week of 10/25.



11/2/2021 GMP Impact Items – Narrative

21. Door 200A to be changed to Aluminum – Full Glass
22. Add shades at interior door and glazing at conference room for privacy

11/18/2021



Aluminum Canopies • Walkway Covers • Metal Awnings

Fulton County Animal Facility

| | |
|--------------------------------------|--|
| Type of Canopy: | Extruded Aluminum Walkway Covers, Overhead Supported Rod Canopies and Trellis Structures: |
| Post Supported Walkway Sizes: | (A) 1 @ 18'-0" x 31'-0" x 12'-6" / (F) 1 @ 11'-0" x 13'-0" x 12'-6" / (G) 1 @ 10'-6" x 84'-0" x 12'-8" (H) 5 @ 12'-0" x 84'-0" x 12'-6" / (I) 3 @ 6'-6" x 84'-0" (J) 1 @ 6'-6" x 95'-6" x 12'-6" (K) 1 @ 8'-0" x 12'-0" x 12'-6" (L) 3 @ 9'-6" x 12'-0" x 12'-6" (M) 8 @ 8'-0" x 12'-0" x 12'-6" |
| Rod supported Canopies Sizes: | (B) 1 @ 3'-0" x 41'-0" (N) 5 @ 4'-0" x 19'-0" |
| Trellis Sizes: | (C) 1 @ 17'-6 x 69'-6" 12'-6 (D) 2 @ 12'-3" x 33'-0" x 12'-6" (E) 12 @ 12'-0" x 30'-0" |

Materials:

| | |
|-------------------------|--|
| Columns: | 4" x 4" / 4" x 6" / 6" x 6" Extruded Aluminum |
| Beams: | 4" x 6" / 6" x 8" Extruded Aluminum |
| Trellis Tubes: | 2" x 6" Extruded Aluminum |
| Gutter / Fascia: | 6" Extruded Aluminum |
| Decking: | 3" x 6" Extruded Aluminum Cap & Pan |
| Overhead Rods: | 2" x 2" Extruded Aluminum Tube |
| Color / Finish: | Kynar 2-coat – one color only, from Mitchell Metals Standard Kynar Colors. Custom Kynar colors available with a 3 to 4-week additional lead time. |

Notes & Exclusions:

- Mitchell Metals is providing custom designed systems utilizing the standard Prefabricated / Pre-engineered Parts and pieces listed above (See attached sketch).
- No specifications were provided for this scope of work.
- Price is based on Mitchell Metals interpretation of the Scope provided by Winter Construction
- Footing design and installation excluded. Mitchell Metals to provide Styrofoam block outs with installation by others.
- Blocking (if required) to support canopy gutter and overhead rods EXCLUDED. Blocking to be furnished and installed by others per Mitchell Metals' APPROVED Shop Drawings. *Blocking must be accessible during time of canopy installation to allow for proper canopy attachment.* Wall conditions: Brick/CMU
- Any demolition, lighting, conduit covers, thru-wall flashing, bonds and Davis Bacon Wage Rates excluded.
- Canopies are not designed to handle building roof drainage and will result in overflow of canopy system.

General Notes:

- **Georgia** PE sealed drawings and design calculations are included in this price. Canopy is designed to meet IBC with Wind Load requirements of 120mph, 20 psf Live Load and 5 psf Snow Load, Exposure Category – C, Risk Category – II.

Project Lead Time: May 17th, 2022 – Mitchell Metals minimum lead time based on bid date above.



RCP - OVERALL 1


| GENERAL NOTES | |
|---------------|--|
| 1. | ALL DIMENSIONS ARE UNLESS OTHERWISE NOTED. |
| 2. | ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL BUILDING CODE (IBC) AND ALL APPLICABLE LOCAL, STATE AND FEDERAL CODES. |
| 3. | ALL MATERIALS AND METHODS SHALL BE APPROVED BY THE ARCHITECT. |
| 4. | ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL BUILDING CODE (IBC) AND ALL APPLICABLE LOCAL, STATE AND FEDERAL CODES. |

| FINISH LEGEND | |
|---------------|------------|
| 001 | CONCRETE |
| 002 | PAINT |
| 003 | WOOD |
| 004 | GLASS |
| 005 | METAL |
| 006 | CEILING |
| 007 | FLOORING |
| 008 | WALLS |
| 009 | ROOFING |
| 010 | MECHANICAL |
| 011 | ELECTRICAL |
| 012 | PLUMBING |
| 013 | MECHANICAL |
| 014 | ELECTRICAL |
| 015 | PLUMBING |
| 016 | MECHANICAL |
| 017 | ELECTRICAL |
| 018 | PLUMBING |
| 019 | MECHANICAL |
| 020 | ELECTRICAL |
| 021 | PLUMBING |
| 022 | MECHANICAL |
| 023 | ELECTRICAL |
| 024 | PLUMBING |
| 025 | MECHANICAL |
| 026 | ELECTRICAL |
| 027 | PLUMBING |
| 028 | MECHANICAL |
| 029 | ELECTRICAL |
| 030 | PLUMBING |
| 031 | MECHANICAL |
| 032 | ELECTRICAL |
| 033 | PLUMBING |
| 034 | MECHANICAL |
| 035 | ELECTRICAL |
| 036 | PLUMBING |
| 037 | MECHANICAL |
| 038 | ELECTRICAL |
| 039 | PLUMBING |
| 040 | MECHANICAL |
| 041 | ELECTRICAL |
| 042 | PLUMBING |
| 043 | MECHANICAL |
| 044 | ELECTRICAL |
| 045 | PLUMBING |
| 046 | MECHANICAL |
| 047 | ELECTRICAL |
| 048 | PLUMBING |
| 049 | MECHANICAL |
| 050 | ELECTRICAL |
| 051 | PLUMBING |
| 052 | MECHANICAL |
| 053 | ELECTRICAL |
| 054 | PLUMBING |
| 055 | MECHANICAL |
| 056 | ELECTRICAL |
| 057 | PLUMBING |
| 058 | MECHANICAL |
| 059 | ELECTRICAL |
| 060 | PLUMBING |
| 061 | MECHANICAL |
| 062 | ELECTRICAL |
| 063 | PLUMBING |
| 064 | MECHANICAL |
| 065 | ELECTRICAL |
| 066 | PLUMBING |
| 067 | MECHANICAL |
| 068 | ELECTRICAL |
| 069 | PLUMBING |
| 070 | MECHANICAL |
| 071 | ELECTRICAL |
| 072 | PLUMBING |
| 073 | MECHANICAL |
| 074 | ELECTRICAL |
| 075 | PLUMBING |
| 076 | MECHANICAL |
| 077 | ELECTRICAL |
| 078 | PLUMBING |
| 079 | MECHANICAL |
| 080 | ELECTRICAL |
| 081 | PLUMBING |
| 082 | MECHANICAL |
| 083 | ELECTRICAL |
| 084 | PLUMBING |
| 085 | MECHANICAL |
| 086 | ELECTRICAL |
| 087 | PLUMBING |
| 088 | MECHANICAL |
| 089 | ELECTRICAL |
| 090 | PLUMBING |
| 091 | MECHANICAL |
| 092 | ELECTRICAL |
| 093 | PLUMBING |
| 094 | MECHANICAL |
| 095 | ELECTRICAL |
| 096 | PLUMBING |
| 097 | MECHANICAL |
| 098 | ELECTRICAL |
| 099 | PLUMBING |
| 100 | MECHANICAL |

| CEILING LEGEND | |
|----------------|------------|
| 001 | CONCRETE |
| 002 | PAINT |
| 003 | WOOD |
| 004 | GLASS |
| 005 | METAL |
| 006 | CEILING |
| 007 | FLOORING |
| 008 | WALLS |
| 009 | ROOFING |
| 010 | MECHANICAL |
| 011 | ELECTRICAL |
| 012 | PLUMBING |
| 013 | MECHANICAL |
| 014 | ELECTRICAL |
| 015 | PLUMBING |
| 016 | MECHANICAL |
| 017 | ELECTRICAL |
| 018 | PLUMBING |
| 019 | MECHANICAL |
| 020 | ELECTRICAL |
| 021 | PLUMBING |
| 022 | MECHANICAL |
| 023 | ELECTRICAL |
| 024 | PLUMBING |
| 025 | MECHANICAL |
| 026 | ELECTRICAL |
| 027 | PLUMBING |
| 028 | MECHANICAL |
| 029 | ELECTRICAL |
| 030 | PLUMBING |
| 031 | MECHANICAL |
| 032 | ELECTRICAL |
| 033 | PLUMBING |
| 034 | MECHANICAL |
| 035 | ELECTRICAL |
| 036 | PLUMBING |
| 037 | MECHANICAL |
| 038 | ELECTRICAL |
| 039 | PLUMBING |
| 040 | MECHANICAL |
| 041 | ELECTRICAL |
| 042 | PLUMBING |
| 043 | MECHANICAL |
| 044 | ELECTRICAL |
| 045 | PLUMBING |
| 046 | MECHANICAL |
| 047 | ELECTRICAL |
| 048 | PLUMBING |
| 049 | MECHANICAL |
| 050 | ELECTRICAL |
| 051 | PLUMBING |
| 052 | MECHANICAL |
| 053 | ELECTRICAL |
| 054 | PLUMBING |
| 055 | MECHANICAL |
| 056 | ELECTRICAL |
| 057 | PLUMBING |
| 058 | MECHANICAL |
| 059 | ELECTRICAL |
| 060 | PLUMBING |
| 061 | MECHANICAL |
| 062 | ELECTRICAL |
| 063 | PLUMBING |
| 064 | MECHANICAL |
| 065 | ELECTRICAL |
| 066 | PLUMBING |
| 067 | MECHANICAL |
| 068 | ELECTRICAL |
| 069 | PLUMBING |
| 070 | MECHANICAL |
| 071 | ELECTRICAL |
| 072 | PLUMBING |
| 073 | MECHANICAL |
| 074 | ELECTRICAL |
| 075 | PLUMBING |
| 076 | MECHANICAL |
| 077 | ELECTRICAL |
| 078 | PLUMBING |
| 079 | MECHANICAL |
| 080 | ELECTRICAL |
| 081 | PLUMBING |
| 082 | MECHANICAL |
| 083 | ELECTRICAL |
| 084 | PLUMBING |
| 085 | MECHANICAL |
| 086 | ELECTRICAL |
| 087 | PLUMBING |
| 088 | MECHANICAL |
| 089 | ELECTRICAL |
| 090 | PLUMBING |
| 091 | MECHANICAL |
| 092 | ELECTRICAL |
| 093 | PLUMBING |
| 094 | MECHANICAL |
| 095 | ELECTRICAL |
| 096 | PLUMBING |
| 097 | MECHANICAL |
| 098 | ELECTRICAL |
| 099 | PLUMBING |
| 100 | MECHANICAL |

| WORK NOTES | |
|------------|--|
| 1. | ALL DIMENSIONS ARE UNLESS OTHERWISE NOTED. |
| 2. | ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL BUILDING CODE (IBC) AND ALL APPLICABLE LOCAL, STATE AND FEDERAL CODES. |
| 3. | ALL MATERIALS AND METHODS SHALL BE APPROVED BY THE ARCHITECT. |
| 4. | ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL BUILDING CODE (IBC) AND ALL APPLICABLE LOCAL, STATE AND FEDERAL CODES. |

| CEILING LEGEND | |
|----------------|------------|
| 001 | CONCRETE |
| 002 | PAINT |
| 003 | WOOD |
| 004 | GLASS |
| 005 | METAL |
| 006 | CEILING |
| 007 | FLOORING |
| 008 | WALLS |
| 009 | ROOFING |
| 010 | MECHANICAL |
| 011 | ELECTRICAL |
| 012 | PLUMBING |
| 013 | MECHANICAL |
| 014 | ELECTRICAL |
| 015 | PLUMBING |
| 016 | MECHANICAL |
| 017 | ELECTRICAL |
| 018 | PLUMBING |
| 019 | MECHANICAL |
| 020 | ELECTRICAL |
| 021 | PLUMBING |
| 022 | MECHANICAL |
| 023 | ELECTRICAL |
| 024 | PLUMBING |
| 025 | MECHANICAL |
| 026 | ELECTRICAL |
| 027 | PLUMBING |
| 028 | MECHANICAL |
| 029 | ELECTRICAL |
| 030 | PLUMBING |
| 031 | MECHANICAL |
| 032 | ELECTRICAL |
| 033 | PLUMBING |
| 034 | MECHANICAL |
| 035 | ELECTRICAL |
| 036 | PLUMBING |
| 037 | MECHANICAL |
| 038 | ELECTRICAL |
| 039 | PLUMBING |
| 040 | MECHANICAL |
| 041 | ELECTRICAL |
| 042 | PLUMBING |
| 043 | MECHANICAL |
| 044 | ELECTRICAL |
| 045 | PLUMBING |
| 046 | MECHANICAL |
| 047 | ELECTRICAL |
| 048 | PLUMBING |
| 049 | MECHANICAL |
| 050 | ELECTRICAL |
| 051 | PLUMBING |
| 052 | MECHANICAL |
| 053 | ELECTRICAL |
| 054 | PLUMBING |
| 055 | MECHANICAL |
| 056 | ELECTRICAL |
| 057 | PLUMBING |
| 058 | MECHANICAL |
| 059 | ELECTRICAL |
| 060 | PLUMBING |
| 061 | MECHANICAL |
| 062 | ELECTRICAL |
| 063 | PLUMBING |
| 064 | MECHANICAL |
| 065 | ELECTRICAL |
| 066 | PLUMBING |
| 067 | MECHANICAL |
| 068 | ELECTRICAL |
| 069 | PLUMBING |
| 070 | MECHANICAL |
| 071 | ELECTRICAL |
| 072 | PLUMBING |
| 073 | MECHANICAL |
| 074 | ELECTRICAL |
| 075 | PLUMBING |
| 076 | MECHANICAL |
| 077 | ELECTRICAL |
| 078 | PLUMBING |
| 079 | MECHANICAL |
| 080 | ELECTRICAL |
| 081 | PLUMBING |
| 082 | MECHANICAL |
| 083 | ELECTRICAL |
| 084 | PLUMBING |
| 085 | MECHANICAL |
| 086 | ELECTRICAL |
| 087 | PLUMBING |
| 088 | MECHANICAL |
| 089 | ELECTRICAL |
| 090 | PLUMBING |
| 091 | MECHANICAL |
| 092 | ELECTRICAL |
| 093 | PLUMBING |
| 094 | MECHANICAL |
| 095 | ELECTRICAL |
| 096 | PLUMBING |
| 097 | MECHANICAL |
| 098 | ELECTRICAL |
| 099 | PLUMBING |
| 100 | MECHANICAL |



CLIENT
FULTON COUNTY
Fulton County Georgia
141 Peach Street, SW
Atlanta, GA 30333
T 404 802 3800
F 404 802 3810
www.fulton.ga.gov

ARCHITECT
PCAL
PCAL
1425 Edgewood Industrial
Suite 10
Atlanta, GA 30318
T 404 802 3800
F 404 802 3810
www.pcal.com

CONSULTANT

REGISTRATION
Copyright © 2021
RELEASED FOR
CONSTRUCTION
FOR REGULATORY APPROVAL,
ISSUING PERMITS OR
CONSTRUCTION PURPOSES.


PROJECT NAME
Fulton County
Animal Services
Facility


PROJECT LOCATION
1251 Fulton Industrial
Boulevard
Atlanta, GA 30318

PROJECT NUMBER
1004636.00

SHEET TITLE
OVERALL
REFLECTED
CEILING PLAN

SHEET NUMBER
A3.10





10/26/2021



Sierra Dennis, LEED AP BD+C, WELL AP, Fitwel Ambassador | Sustainability Consultant

Integral Consulting Engineering | **Trust** | **Nurture** | **Inspire**

P: 404.481.5686x1611

integralgroup.com | Sierra.Dennis@integralgroup.com

1000 Marietta St, NW, Suite 238, Atlanta, GA 30318 | [Just released! Read the WorldGBC's *Beyond Buildings* report](#)

This email may contain confidential and/or privileged information. If you are not the intended recipient or have received this email in error, please notify the sender immediately this email. Any unauthorized copying, disclosure or distribution of the information contained on this email is prohibited.

Integral Group, Integral Consulting Engineering and Integral Group Holdings, LLC are not affiliated in any way with The Integral Group, LLC or IntegralGude, LLC of Atlanta, Georgia

-----Original Appointment-----

From: Sierra Dennis

Sent: October 20, 2021 11:58 AM

To: Sierra Dennis; Greg Mullin; Kelley Park; Briana Keith; Jerry Oglesbee; 'Clemente Quinones'; 'amaddox@greenbergfarrow.com'; Mar Goldstone; heather@animalarts.com; sarah@animalarts.com; bbarnes@epstengroup.com; Jeremy@2020engineer.com; mwothe@aedesign-inc.com; kkeller@aedesign-inc.com; jmullikin@aedesign-inc.com; gpfiler@aedesign-inc.com; dave@2020engineer.com; carrie@2020engineer.com; kelli@2020engineer.com; enielsen@aedesign-inc.com; skaltz@aedesign-inc.com; Steph Powell; Taylor Marshall; Andi Walter; Jean Shi; Kathleen Truong; Akemi Flores; Blake Bredbenner; Katy Townsend; erin@2020engineer.com; Jonathan Pilgrim; 'Sarah McCracken'; 'Patrick Nesbitt'; 'William Mensah'

Cc: Anais Engel; Marilyn Specht; John Nelson; Ruicong Liu

Subject: LEED Online Help Session

When: October 25, 2021 1:00 PM-1:30 PM (UTC-05:00) Eastern Time (US & Canada).

Where: Microsoft Teams Meeting

Hi FCASF team,

I will be hosting a 30-minute session, for all team members, demonstrating how to navigate the LEED Online profile, including setting-up accounts, reviewing credits, uploading documents, etc. The meeting will be recorded and shared. Please forward this invite to team members, as needed.

*PLEASE NOTE: The LEED Online interface is most efficient when using an **Internet Explorer** browser!*

Best,

Sierra Dennis
Sustainability Consultant
Integral Group

Additional Resources:

- [LEED Online](#)
- [USGBC](#)
- [LEED v4 credits](#)
- [LEED v4.1 credits](#)

Microsoft Teams meeting

Join on your computer or mobile app

[Click here to join the meeting](#)

William Mensah

From: Sarah McCracken
Sent: Tuesday, October 26, 2021 3:38 PM
To: Drew Clayton; William Mensah; Patrick Nesbitt
Cc: Carrie Campbell; 21123
Subject: FW: FCASF: Recording - LEED Online Help Session
Attachments: RE: FCASF: Recording - LEED Online Help Session

All,

I was able to speak to Sierra this afternoon. See response below in [blue](#).

We discussed scheduling a WJG huddle to get into more specifics of the LEED construction credits in the next 2-3 weeks, after the design submission is complete. Pat, can you take the lead on reaching out to Sierra the week of November 15th?

Thanks,

Sarah McCracken | LEED AP

Project Executive
404-965-3350 (d)
404-861-7099 (c)

From: Sarah McCracken
Sent: Monday, October 25, 2021 4:10 PM
To: Drew Clayton <dclayton@winter-construction.com>
Cc: Patrick Nesbitt <pnesbitt@winter-construction.com>; William Mensah <WMensah@winter-construction.com>
Subject: FW: FCASF: Recording - LEED Online Help Session

Drew (and team),

FYI.....

I left a voicemail with Sierra to chat about who the WJG contact will be (maybe need a couple options) along with some general questions as noted: [Sierra confirmed we can have multiple people assigned to credits \(and encourages this\) as the new LEED online system operates where you can only see the credits that you are assigned to, so it is good to have multiple people assigned to each credit. I suggest that Drew, Pat, and I all create USGBC accounts and are both assigned to the project.](#)

- She mentioned LEED V4 and V4.1. Was curious as to why some credits seemed to fall under different versions as this hasn't been the case in the past. [Although the project is registered under V4.0, we can select to use the newer v4.1 requirements for certain credits at will. Sierra explained that some of the v4.1 requirements are less stringent than v4.0. See attached e-mail for the credits she is assuming we will use v4.1 versus v4.0.](#)
- Does WJG actually upload everything or do we send it to them to review and then they upload (the latter is how it worked on Central Library)? [The Integral Group will review our submittals \(i.e. IAQ plans, certification letters, etc.\) before we upload to LEED Online. For the tracking spreadsheets, we will simply enter the information into LEED online and then The Integral Group will review. In summary, WJG enters/uploads all required credit back-up, but The Integral Group reviews/confirms everything and actually submits to USGBC.](#)

- During the kick-off meeting, she mentioned that she would send us templates for required documentation plans, etc. I will request those.....[Sierra confirmed she will send in the next week or so.](#)
- If Certified wood is a pre-requisite for MRc3: Building Product Disclosure & Optimization Sourcing of Raw Materials Product [Certified Wood is not a required pre-requisite. The requirement is simply a minimum of 5 product manufacturers meet one or more of the requirements \(recycled content, regional content, renewable materials, and/or certified wood\). It is all based on percentages of cost of construction so in theory we could meet the credit through recycled content \(as an example\) if we had 5 different product manufacturers that met the percentage requirement.](#)

Let me know if anyone has any additional questions. I will let you know once I hear back from her.

Thanks,

Sarah McCracken | LEED AP

Project Executive
404-965-3350 (d)
404-861-7099 (c)

From: Sierra Dennis <Sierra.Dennis@integralgroup.com>

Sent: Monday, October 25, 2021 3:09 PM

To: Greg Mullin <GMullin@pgal.com>; Kelley Park <KPark@pgal.com>; Briana Keith <BKeith@pgal.com>; 'Jerry Oglesbee' <jerry@2020engineer.com>; 'Clemente Quinones' <clemente.quinones@loweengineers.com>; 'amaddox@greenbergfarrow.com' <amaddox@greenbergfarrow.com>; Mar Goldstone <mgoldstone@epstengroup.com>; heather@animalarts.com; sarah@animalarts.com; bbarnes@epstengroup.com; Jeremy@2020engineer.com; mwothe@aedesign-inc.com; kkeller@aedesign-inc.com; jmullikin@aedesign-inc.com; gpfile@aedesign-inc.com; dave@2020engineer.com; carrie@2020engineer.com; kelli@2020engineer.com; enielsen@aedesign-inc.com; skaltz@aedesign-inc.com; Steph Powell <spowell@aedesign-inc.com>; Taylor Marshall <TMarshall@pgal.com>; Andi Walter <awalter@aedesign-inc.com>; Jean Shi <jshi@greenbergfarrow.com>; Kathleen Truong <KTruong@pgal.com>; Akemi Flores <akemi.flores@loweengineers.com>; Blake Bredbenner <blake.bredbenner@loweengineers.com>; Caty Townsend <caty@animalarts.com>; erin@2020engineer.com; Jonathan Pilgrim <jonathan@animalarts.com>; Sarah McCracken <SMcCracken@winter-construction.com>; Patrick Nesbitt <pnesbitt@winter-construction.com>; William Mensah <WMensah@winter-construction.com>

Cc: Anais Engel <aengel@integralgroup.com>; Marilyn Specht <mspecht@integralgroup.com>; John Nelson <john.nelson@integralgroup.com>; Ruicong Liu <rliu@integralgroup.com>

Subject: FCASF: Recording - LEED Online Help Session

Hi All,

Please see below for the *LEED Online Help Session* recording - the Sharepoint link password is **FCASF2021**

https://integralgroup2-my.sharepoint.com/:v/g/person/sierra_dennis_integralgroup_com/EQ0cl2JjbitNm6CuqlrEi_wBX2zvbETnx-ve_aXptLBymA?e=1UBZLz

Best,
Sierra Dennis

11/01/2021

William Mensah

From: Borders, Armond <Armond.Borders@fultoncountyga.gov>
Sent: Monday, November 1, 2021 9:40 AM
To: Greg Mullin
Cc: Sarah McCracken; William Mensah; Kelley Park
Subject: RE: TLMM TMANI60 Fulton County Animal Services Facility 102121
Attachments: RE: Fulton County Animal Services Facility - Roofing Specifications TLMM TMANI60

Yes, I got a response back on Friday and I am sorry for the late response. Sam Bakare (County Building Construction Administrator) stated "The most important thing for us is the warranty period, which in this case is 20 years with Manufacturer guarantee. We will leave the installation and inspection assurance to the A/E of record."

See the attached email for record as well.

Armond Borders | Project Manager
HEERY/McAfee3, A Joint Venture
FCURA – Project Management Team
Department of Real Estate & Asset Management
Fulton County Government Center
141 Pryor Street, SW - Suite 6001
Atlanta, GA 30303
404-612-5916 (office) | 470-201-8508 (CELL)
Email: Armond.Borders@fultoncountyga.gov

From: Greg Mullin [mailto:GMullin@pgal.com]
Sent: Monday, November 1, 2021 9:38 AM
To: Borders, Armond <Armond.Borders@fultoncountyga.gov>
Cc: Sarah McCracken <SMcCracken@winter-construction.com>; William Mensah <WMensah@winter-construction.com>; Kelley Park <KPark@pgal.com>
Subject: RE: TLMM TMANI60 Fulton County Animal Services Facility 102121

Armond –
Have you heard anything back from the County’s Roofing Manager?
Thanks.
Greg



GREG MULLIN AIA LEED AP
Principal

- | | | | | |
|-------------------------------------|-------------------------------------|----------------------------------|--------------------------------------|------------------------------------|
| ALEXANDRIA T 703 836 0588 | BOCA RATON T 561 988 4002 | DENVER T 720 216 9600 | LAS VEGAS T 702 435 4448 | SAN DIEGO T 619 269 5288 |
| ATLANTA T 404 602 3800 | CHICAGO T 312 856 5006 | HOBOKEN T 201 984 6210 | LOS ANGELES T 310 645 3276 | |
| AUSTIN | DALLAS/FT WORTH | HOUSTON | SALT LAKE CITY | |

11/01/2021

T 512 236 1005 T 972 871 2225 T 713 622 1444 T 801 999 9850

PGAL.COM



From: Greg Mullin
Sent: Wednesday, October 27, 2021 10:21 AM
To: 'William Mensah' <WMensah@winter-construction.com>; Sarah McCracken <SMcCracken@winter-construction.com>
Subject: FW: TLMM TMANI60 Fulton County Animal Services Facility 102121

FYI, they, and I, would like the County to sign off on this as an acceptable solution. Technically, it is fine with PGAL and we can get our specs revised to reflect the actual installation. However, I think that we all want to make sure that it meets the County's requirements from a warranty and insurability standpoint.
 Thanks.
 Greg

From: Borders, Armond <Armond.Borders@fultoncountyga.gov>
Sent: Wednesday, October 27, 2021 7:58 AM
To: Greg Mullin <GMullin@pgal.com>; Dunlap, Duane @ ATLANTA <Duane.Dunlap@cbre.com>
Subject: RE: TLMM TMANI60 Fulton County Animal Services Facility 102121

It looks good to me and still achieves a 20 year warranty. I may need to check with the County's Roofing Manager Michelle Cox just to make sure.

Armond Borders | Project Manager
 HEERY/McAfee3, A Joint Venture
 FCURA – Project Management Team
 Department of Real Estate & Asset Management
 Fulton County Government Center
 141 Pryor Street, SW - Suite 6001
 Atlanta, GA 30303
 404-612-5916 (office) | 470-201-8508 (CELL)
 Email: Armond.Borders@fultoncountyga.gov

From: Greg Mullin [<mailto:GMullin@pgal.com>]
Sent: Tuesday, October 26, 2021 3:00 PM
To: Borders, Armond <Armond.Borders@fultoncountyga.gov>; Dunlap, Duane @ ATLANTA <Duane.Dunlap@cbre.com>
Subject: FW: TLMM TMANI60 Fulton County Animal Services Facility 102121

Not sure who at the County would want or need to review...but this does achieve a 20-yr warranty, if that is acceptable to the County.



GREG MULLIN AIA LEED AP
 Principal

Exhibit A - Attachment M

Fulton County Animal Shelter

11/01/2021

| | | | | |
|-------------------------------------|--|----------------------------------|---|------------------------------------|
| ALEXANDRIA T 703 836 0588 | BOCA RATON T 561 988 4002 | DENVER T 720 216 9600 | LAS VEGAS T 702 435 4448 | SAN DIEGO T 619 269 5288 |
| ATLANTA T 404 602 3800 | CHICAGO T 312 856 5006 | HOBOKEN T 201 984 6210 | LOS ANGELES T 310 645 3276 | |
| AUSTIN T 512 236 1005 | DALLAS/FT WORTH T 972 871 2225 | HOUSTON T 713 622 1444 | SALT LAKE CITY T 801 999 9850 | |

PGAL.COM



From: William Mensah <WMensah@winter-construction.com>

Sent: Monday, October 25, 2021 7:25 PM

To: Greg Mullin <GMullin@pgal.com>

Cc: Kelley Park <KPark@pgal.com>; Sarah McCracken <SMcCracken@winter-construction.com>; Drew Clayton <dclayton@winter-construction.com>; Patrick Nesbitt <pnesbitt@winter-construction.com>

Subject: FW: TLMM TMANI60 Fulton County Animal Services Facility 102121

Greg,
Pleased see attached assembly letter from GAF showing that fastening all layers of substrate, insulation and cover boards simultaneously and mechanically attaching a 60 mil TPO is eligible for a 20 year NDL warranty as called for in the specifications.

Thanks,
William Mensah LEED AP
Senior Estimator
Winter Construction
404-965-3347 (d)
404-822-6273 (c)
404-588-3300 (o)

Disclaimer

The information contained in this communication from the sender is confidential. It is intended solely for use by the recipient and others authorized to receive it. If you are not the recipient, you are hereby notified that any disclosure, copying, distribution or taking action in relation of the contents of this information is strictly prohibited and may be unlawful.

MATERIALS & FINISHES

Table with columns: MATERIAL DESCRIPTION, MARK, SUBCATEGORY. Lists various materials like ALP-1, APC-1, HPC-1, etc.

GENERAL NOTES

- 1. REFER TO A9.10 FOR FINISH INFORMATION
2. ALL FLOOR FINISHES TO BE CENTERED WITH ROOM UNLESS OTHERWISE NOTED.
3. ALL DIMENSIONS ARE TAKEN FROM FACE OF DRYWALL UNLESS NOTED OTHERWISE.


CLIENT: FULTON COUNTY
Fulton County Georgia
141 Pryor Street, SW, Atlanta, GA 30303
T 404 612 4000

ARCHITECT

PGAL
1425 Ellsworth Industrial Suite 15
Atlanta, GA 30318
T 404 602 3500
F 404 602 3810
www.pgal.com

CONSULTANT


FILE NAME: BM 360/Fulton County Animal Services Facility/ARCH - FCAS - RV12020.rvt
DATE STAMP: 10/8/2021 4:51:53 PM



CUSTOM LIGHT

ART GRAPHIC

FINISH PLAN - SECTOR A 1/8" = 1'-0" 1



DRAWING HISTORY

Table with columns: No., DATE, DESCRIPTION. Shows drawing revision history.

REGISTRATION

Copyright © 2021
RELEASED FOR CONSTRUCTION
FOR REGULATORY APPROVAL, BIDDING, PERMIT, OR CONSTRUCTION PURPOSES.




PROJECT NAME: Fulton County Animal Services Facility

PROJECT LOCATION: 1251 Fulton Industrial Boulevard, Atlanta, GA 30318

PROJECT NUMBER: 1004636.00

SHEET TITLE: FINISH PLAN - SECTOR A

SHEET NUMBER: A9.11



IEQc1 WALK-OFF MAT PLACEMENT DIAGRAM

FLOOR PLAN - OVERALL 1/16" = 1'-0" 1

11/03/2021

William Mensah

From: Greg Mullin <GMullin@pgal.com>
Sent: Wednesday, November 3, 2021 4:57 PM
To: William Mensah; Kelley Park
Cc: Sarah McCracken
Subject: RE: Demountable Walls / Fulton County Animal Services Facility

I've used KI's demountable product before and this is acceptable.



GREG MULLIN AIA LEED AP
Principal

| | | | | |
|-------------------------------------|--|----------------------------------|---|------------------------------------|
| ALEXANDRIA T 703 836 0588 | BOCA RATON T 561 988 4002 | DENVER T 720 216 9600 | LAS VEGAS T 702 435 4448 | SAN DIEGO T 619 269 5288 |
| ATLANTA T 404 602 3800 | CHICAGO T 312 856 5006 | HOBOKEN T 201 984 6210 | LOS ANGELES T 310 645 3276 | |
| AUSTIN T 512 236 1005 | DALLAS/FT WORTH T 972 871 2225 | HOUSTON T 713 622 1444 | SALT LAKE CITY T 801 999 9850 | |

PGAL.COM



From: William Mensah <WMensah@winter-construction.com>
Sent: Wednesday, November 3, 2021 4:24 PM
To: Greg Mullin <GMullin@pgal.com>; Kelley Park <KPark@pgal.com>
Cc: Sarah McCracken <SMcCracken@winter-construction.com>
Subject: FW: Demountable Walls / Fulton County Animal Services Facility

Greg/Kelley,
Attached is a demountable partition manufacturer's product information for your review. Please let us know if this would be acceptable.

Thanks,
William Mensah LEED AP
Senior Estimator
Winter Construction
404-965-3347 (d)
404-822-6273 (c)
404-588-3300 (o)



www.wintercompanies.com

Exhibit A - Attachment P

11/03/2021

From: Grant Huebner <Grant.Huebner@ki.com>

Sent: Wednesday, November 3, 2021 3:59 PM

To: William Mensah <WMensah@winter-construction.com>

Cc: Hassan Hagood <hassan@contractbusinessinteriors.com>; Cheryl Madison <cheryl@contractbusinessinteriors.com>;

Carl Hagood <carl@contractbusinessinteriors.com>; Stephen Gamble <stephen@contractbusinessinteriors.com>

Subject: RE: Demountable Walls / Fulton County Animal Services Facility

William,

Please see attached Genius Brochure, STC Report, and Environment Data Sheet.

This information should be more than sufficient for the architect. Let me know if there is any additional information that you may need.

Thank you.



GRANT HUEBNER | Wall Specialist-Strategic Accounts

P: 404.869.0885 | **M:** 404.323.5838 | **E:** grant.huebner@ki.com | ki.com



Visually inspiring. Seamlessly functional.

Learn more about KI architectural walls at ki.com/wall

Due to the rising cost of raw materials, transportation and logistical shortages, effective July 12th all orders* received on or after this date will incur a 5% material & transportation surcharge.

*Some exclusions apply

From: Stephen Gamble <stephen@contractbusinessinteriors.com>

Sent: Wednesday, November 3, 2021 3:09 PM

To: wmensah@winter-construction.com

Cc: Hassan Hagood <hassan@contractbusinessinteriors.com>; Cheryl Madison <cheryl@contractbusinessinteriors.com>;

Carl Hagood <carl@contractbusinessinteriors.com>; Grant Huebner <Grant.Huebner@ki.com>

Subject: RE: Demountable Walls / Fulton County Animal Services Facility

CAUTION: This message originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Grant,

I just spoke with William (Winter-Construction / copied). He is requesting the technical data of our product offering so as to forward to the Architect for approval. Please send as an attachment ASAP. Thank you.

Regards,

Stephen

Disclaimer

The information contained in this communication from the sender is confidential. It is intended solely for use by the recipient and others authorized to receive it. If you are not the recipient, you are hereby notified that any disclosure, copying, distribution or taking action in relation of the contents of this information is strictly prohibited and may be unlawful.

William Mensah

From: Kelley Park <KPark@pgal.com>
Sent: Monday, November 1, 2021 4:28 PM
To: Borders, Armond; Crayton, Gregory; Sarah McCracken
Cc: Dunlap, Duane @ ATLANTA; Drew Clayton; William Mensah; Patrick Nesbitt; Carrie Campbell; Greg Mullin; All.IT.Operations; Regis, Abdias; Kallmyer, Matthew; Dimond, Timothy; Mason, Bill; Eric Nielsen; Greg Pfile; Taylor Marshall; Briana Keith; Sarah Boman; Caty Townsend
Subject: RE: Animal Services Facility - IT/Security Scope Review - 11/01/21
Attachments: 2021-11-01_Animal Services Facility - FIB Updates.xls

Good Afternoon,
Please see updated Equipment spreadsheet from today's meeting.

I also followed up with Animal Arts and they mentioned if it is in the budget, then it would be ideal if the barn and the dog kennel run yards could have WAPs. The only areas where wifi is not needed is the west-most dog yard (this is only for the quarantine dogs) and the south-most yards.



I will send out Arch/Elec/IT floor plans for the County to use to coordinate laptop/computer/printer locations with Lifeline. This will be sent via Newforma as the file is to large to send by email.

Thank you,
Kelley



KELLEY PARK RA RID LEED AP BD+C
Associate

| | | | | |
|-------------------------------------|--|----------------------------------|---|------------------------------------|
| ALEXANDRIA T 703 836 0588 | BOCA RATON T 561 988 4002 | DENVER T 720 216 9600 | LAS VEGAS T 702 435 4448 | SAN DIEGO T 619 269 5288 |
| ATLANTA T 404 602 3800 | CHICAGO T 312 856 5006 | HOBOKEN T 201 984 6210 | LOS ANGELES T 310 645 3276 | |
| AUSTIN T 512 236 1005 | DALLAS/FT WORTH T 972 871 2225 | HOUSTON T 713 622 1444 | SALT LAKE CITY T 801 999 9850 | |

PGAL.COM



From: Borders, Armond <Armond.Borders@fultoncountyga.gov>
Sent: Wednesday, October 27, 2021 3:39 PM
To: Crayton, Gregory <Gregory.Crayton@fultoncountyga.gov>; Sarah McCracken <SMcCracken@winter-construction.com>
Cc: Dunlap, Duane @ ATLANTA <Duane.Dunlap@cbre.com>; Drew Clayton <dclayton@winter-construction.com>; William Mensah <WMensah@winter-construction.com>; Patrick Nesbitt <pnesbitt@winter-construction.com>; Carrie Campbell <CCampbell@winter-construction.com>; Greg Mullin <GMullin@pgal.com>; Kelley Park <KPark@pgal.com>; All.IT.Operations <All.IT.Operations@fultoncountyga.gov>; Regis, Abdias <Abdias.Regis@fultoncountyga.gov>; Kallmyer, Matthew <Matthew.Kallmyer@fultoncountyga.gov>; Dimond, Timothy <Timothy.Dimond@fultoncountyga.gov>; Mason, Bill <Bill.Mason2@fultoncountyga.gov>
Subject: RE: Animal Services Facility - IT/Security Scope Review - 10/27/21

Please see the attached document we reviewed today. Kelly Park is setting up a meeting Monday at 1:00pm with the team to go through the drawings and determine how many phones, computers, printers, etc. will be needed. It was determined that Lifeline will not be providing the phones, computers etc. Sorry if I missed anything, please provide any notes to this email string that are needed.

- **IT will be providing the 8 network switches.**
- **WJG will be providing Camera, WAP, Data lines, card readers. WJG needs a narrative or it to be listed in the documents. Kelly to verify with G. Mullin.**
- **IDENTIV Hirsch Panels (Access Control) – Need power supply, dual contacts, locks, electric strikes. WJG needs specifications from FULCO and then integrated into the Contract Documents. Kelly will check with their Electrical group. Programming to be provided by Fulton County.**
- **OptiPlex 7090 Tower – M. Kallmyer needs to get with his team and review the documents to determine the amount that is needed. We will need the PGAL team and DREAM to coordinate in Monday’s meeting.**
- **Phones – will be provided by the County.**

- 11/01/2021
- **Computers** – M. Kallmyer states the computers will be included in the County's setup. Need to coordinate with drawings & drops to determine the number. Will review on Monday 10/1/21.
 - **Camera Switches** – Need to make sure we have space on the racks in the MDF closet.
 - **AT&T-Comcast Circuit** – Need clear demarcation from the AT&T source at the street to the IT closet inside the building.
 - **We are setting up a meeting for Monday@1:00p to go room by room to determine the number of phones, PC's printers, etc. We need to make sure the IT closet has enough room as well.**

Armond Borders | Project Manager
 HEERY/McAfee3, A Joint Venture
 FCURA – Project Management Team
 Department of Real Estate & Asset Management
 Fulton County Government Center
 141 Pryor Street, SW - Suite 6001
 Atlanta, GA 30303
 404-612-5916 (office) | 470-201-8508 (CELL)
 Email: Armond.Borders@fultoncountyga.gov

From: Crayton, Gregory
Sent: Tuesday, October 26, 2021 1:09 PM
To: Borders, Armond <Armond.Borders@fultoncountyga.gov>; Sarah McCracken <SMcCracken@winter-construction.com>
Cc: Dunlap, Duane @ ATLANTA <Duane.Dunlap@cbre.com>; Drew Clayton <dclayton@winter-construction.com>; William Mensah <WMensah@winter-construction.com>; Patrick Nesbitt <pnesbitt@winter-construction.com>; Carrie Campbell <CCampbell@winter-construction.com>; Greg Mullin <GMullin@pgal.com>; Kelley Park <KPark@pgal.com>; All.IT.Operations <All.IT.Operations@fultoncountyga.gov>; Regis, Abdias <Abdias.Regis@fultoncountyga.gov>
Subject: RE: Animal Services Facility - IT/Security Scope Review

Armond see attached, please let me know if you have any questions.

For discussion during our meeting the meeting tomorrow...

Gregory Crayton
Technical Operations Manager
 Data Center Operations | Physical Security | Infrastructure
 Fulton County Information Technology
 Main: 404.612.0058 | Direct: 404.612.0034 | Mobile: 404.861.7850
gregory.crayton@fultoncountyga.gov

From: Borders, Armond
Sent: Tuesday, October 26, 2021 11:40 AM
To: Sarah McCracken
Cc: Crayton, Gregory; Dunlap, Duane @ ATLANTA; Drew Clayton; William Mensah; Patrick Nesbitt; Carrie Campbell; Greg Mullin; Kelley Park
Subject: Re: Animal Services Facility - IT/Security Scope Review

I spoke with Greg this morning and he should be sending it over today.

Exhibit A - Attachment Q

Armond Borders | Project Manager

HEERY/McAfee3, A Joint Venture

FCURA – Project Management Team

Department of Real Estate & Asset Management

Fulton County Government Center

[141 Pryor Street, SW - Suite 6001](#)[Atlanta, GA 30303](#)[404-612-5916](#)[470-201-8508](#)Email: Armond.Borders@fultoncountyga.gov**Fulton County Animal Shelter**

11/01/2021

On Oct 26, 2021, at 11:35 AM, Sarah McCracken <SMcCracken@winter-construction.com> wrote:

Greg C.,

Can we expect to receive the below referenced low voltage scope spreadsheet today? It would be great if we could have time to review prior to tomorrow's meeting.

Thank you,

Sarah McCracken | LEED AP

Project Executive

404-965-3350 (d)

404-861-7099 (c)

From: Borders, Armond <Armond.Borders@fultoncountyga.gov>**Sent:** Thursday, October 21, 2021 11:30 AM**To:** Greg Mullin <GMullin@pgal.com>; Sarah McCracken <SMcCracken@winter-construction.com>; Crayton, Gregory <Gregory.Crayton@fultoncountyga.gov>; Kelley Park <KPark@pgal.com>; Carrie Campbell <CCampbell@winter-construction.com>; Kallmyer, Matthew <Matthew.Kallmyer@fultoncountyga.gov>; Crayton, Gregory <Gregory.Crayton@fultoncountyga.gov>; Regis, Abdias <Abdias.Regis@fultoncountyga.gov>; Mason, Bill <Bill.Mason2@fultoncountyga.gov>; Dimond, Timothy <Timothy.Dimond@fultoncountyga.gov>**Cc:** Dunlap, Duane @ ATLANTA <Duane.Dunlap@cbre.com>; Drew Clayton <dclayton@winter-construction.com>; William Mensah <WMensah@winter-construction.com>; Patrick Nesbitt <pnesebitt@winter-construction.com>**Subject:** RE: Animal Services Facility - IT/Security Scope Review

Sarah please send out the invite for Wednesday 2:30p-4:00p.

G. Crayton please send over the spreadsheet for us to review as well.

Armond Borders | Project Manager

HEERY/McAfee3, A Joint Venture

FCURA – Project Management Team

Department of Real Estate & Asset Management

Fulton County Government Center

141 Pryor Street, SW - Suite 6001

Atlanta, GA 30303

404-612-5916 (office) | 470-201-8508 (CELL)

Email: Armond.Borders@fultoncountyga.gov

11/01/2021

From: Greg Mullin [<mailto:GMullin@pgal.com>]
Sent: Thursday, October 21, 2021 10:47 AM
To: Sarah McCracken <SMcCracken@winter-construction.com>; Borders, Armond <Armond.Borders@fultoncountyga.gov>; Crayton, Gregory <Gregory.Crayton@fultoncountyga.gov>; Kelley Park <KPark@pgal.com>; Carrie Campbell <CCampbell@winter-construction.com>; Kallmyer, Matthew <Matthew.Kallmyer@fultoncountyga.gov>; Crayton, Gregory <Gregory.Crayton@fultoncountyga.gov>; Regis, Abdias <Abdias.Regis@fultoncountyga.gov>; Mason, Bill <Bill.Mason2@fultoncountyga.gov>; Dimond, Timothy <Timothy.Dimond@fultoncountyga.gov>
Cc: Dunlap, Duane @ ATLANTA <Duane.Dunlap@cbre.com>; Drew Clayton <dclayton@winter-construction.com>; William Mensah <WMensah@winter-construction.com>; Patrick Nesbitt <pnesbitt@winter-construction.com>
Subject: RE: Animal Services Facility - IT/Security Scope Review

That works for me as well.



GREG MULLIN AIA LEED AP
Principal

| | | | | |
|-------------------------------------|--|----------------------------------|---|------------------------------------|
| ALEXANDRIA T 703 836 0588 | BOCA RATON T 561 988 4002 | DENVER T 720 216 9600 | LAS VEGAS T 702 435 4448 | SAN DIEGO T 619 269 5288 |
| ATLANTA T 404 602 3800 | CHICAGO T 312 856 5006 | HOBOKEN T 201 984 6210 | LOS ANGELES T 310 645 3276 | |
| AUSTIN T 512 236 1005 | DALLAS/FT WORTH T 972 871 2225 | HOUSTON T 713 622 1444 | SALT LAKE CITY T 801 999 9850 | |

PGAL.COM



From: Sarah McCracken <SMcCracken@winter-construction.com>
Sent: Thursday, October 21, 2021 10:12 AM
To: Borders, Armond <Armond.Borders@fultoncountyga.gov>; Crayton, Gregory <Gregory.Crayton@fultoncountyga.gov>; Kelley Park <KPark@pgal.com>; Carrie Campbell <CCampbell@winter-construction.com>; Kallmyer, Matthew <Matthew.Kallmyer@fultoncountyga.gov>; Crayton, Gregory <Gregory.Crayton@fultoncountyga.gov>; Regis, Abdias <Abdias.Regis@fultoncountyga.gov>; Mason, Bill <Bill.Mason2@fultoncountyga.gov>; Dimond, Timothy <Timothy.Dimond@fultoncountyga.gov>; Greg Mullin <GMullin@pgal.com>
Cc: Dunlap, Duane @ ATLANTA <Duane.Dunlap@cbre.com>; Drew Clayton <dclayton@winter-construction.com>; William Mensah <WMensah@winter-construction.com>; Patrick Nesbitt <pnesbitt@winter-construction.com>
Subject: RE: Animal Services Facility - IT/Security Scope Review

The Winter Johnson Group team can meet on Wednesday from 2:30 – 4 pm. Let us know if we should issue a meeting invitation.

Thank you,

Sarah McCracken | LEED AP
Project Executive

11/01/2021 404-965-3350 (d)
404-861-7099 (c)

From: Borders, Armond <Armond.Borders@fultoncountyga.gov>
Sent: Wednesday, October 20, 2021 2:46 PM
To: Crayton, Gregory <Gregory.Crayton@fultoncountyga.gov>; Kelley Park <KPark@pgal.com>; Sarah McCracken <SMcCracken@winter-construction.com>; Carrie Campbell <CCampbell@winter-construction.com>; Kallmyer, Matthew <Matthew.Kallmyer@fultoncountyga.gov>; Crayton, Gregory <Gregory.Crayton@fultoncountyga.gov>; Regis, Abdias <Abdias.Regis@fultoncountyga.gov>; Mason, Bill <Bill.Mason2@fultoncountyga.gov>; Dimond, Timothy <Timothy.Dimond@fultoncountyga.gov>; Greg Mullin <GMullin@pgal.com>
Cc: Dunlap, Duane @ ATLANTA <Duane.Dunlap@cbre.com>
Subject: Animal Services Facility - IT/Security Scope Review
Importance: High

These are the time slots that Fulco IT gave me as their availability. Let me know which date works for everyone. Also participation by all is required as we need to get scope nailed down determine who will be responsible for what and prevent scope gap. I will send out the spreadsheet from Greg Crayton and his team once I receive and we can review before the meeting next week.

Monday October 25, 2021 – 11:30a – 3:00pm est
Wednesday October 27, 2021 – 2:30pm – 4:00pm est

- Phones
- Computers
- Printers
- Servers
- Server Racks
- Laptops
- Laptop Docking Stations
- Card Readers
- Credit Card Readers
- Cabling
- Cameras
- Security Monitors (2)
- Computer Monitors for Desktops

Armond Borders | Project Manager
HEERY/McAfee3, A Joint Venture
FCURA – Project Management Team
Department of Real Estate & Asset Management
Fulton County Government Center
141 Pryor Street, SW - Suite 6001
Atlanta, GA 30303
404-612-5916 (office) | 470-201-8508 (CELL)
Email: Armond.Borders@fultoncountyga.gov

From: Crayton, Gregory
Sent: Wednesday, October 20, 2021 1:13 PM
To: Borders, Armond <Armond.Borders@fultoncountyga.gov>

11/01/2021 Cc: Regis, Abdias <Abdias.Regis@fultoncountyga.gov>

Subject: RE: Time Slots for Enrique & I

Thanks Abdias,

Armond, see the below time slots we are available to meet and discuss Animal Services Technology details and responsibilities.

Monday October 25, 2021 – 1130 – 3pm est

Wednesday October 27, 2021 – 230 – 4pm est

Please let me know if either of the slots works for everyone involved...

Thanks,

Gregory Crayton

Technical Operations Manager

Data Center Operations | Physical Security | Infrastructure

Fulton County Information Technology

Main: 404.612.0058 | Direct: 404.612.0034 | Mobile: 404.861.7850

gregory.crayton@fultoncountyga.gov

Disclaimer

The information contained in this communication from the sender is confidential. It is intended solely for use by the recipient and others authorized to receive it. If you are not the recipient, you are hereby notified that any disclosure, copying, distribution or taking action in relation of the contents of this information is strictly prohibited and may be unlawful.

Disclaimer

The information contained in this communication from the sender is confidential. It is intended solely for use by the recipient and others authorized to receive it. If you are not the recipient, you are hereby notified that any disclosure, copying, distribution or taking action in relation of the contents of this information is strictly prohibited and may be unlawful.



Fulton County Georgia
141 Pryor Street, SW,
Atlanta, GA 30303
T 404 612 4000




PGAL
1425 Ellsworth Industrial
Suite 15
Atlanta, GA 30318
T 404 602 3500
F 404 602 3810
www.pgal.com



AE DESIGN
Integrated Lighting and Electrical Solutions

| KEYNOTE LEGEND | |
|----------------|---|
| KEY VALUE | KEYNOTE TEXT |
| 1 | APPROXIMATE LOCATION OF INCOMING SERVICE CONDUITS. PROVIDE (2) 4" CONDUITS AND (1) 2" CONDUIT TO IT ROOM 126. CONTRACTOR SHALL COORDINATE FINAL LOCATION AND CONNECTION REQUIREMENTS WITH APPROVED SHOP DRAWINGS PRIOR TO ROUGH-IN. |
| 2 | EC SHALL COORDINATE EXACT MOUNTING HEIGHT AND LOCATION OF RECEPTACLE WITH ARCHITECTURAL ELEVATIONS & SECTIONS PRIOR TO ROUGH-IN. |



1 | PARTIAL ELECTRICAL TECHNOLOGY PLAN - SECTOR B
T2.11 | 1/8" = 1'-0"

DRAWING HISTORY

| No. | DATE | DESCRIPTION |
|-----|------------|-------------|
| 1 | 10/06/2021 | 100% CD |

REGISTRATION
Copyright © 2020

RELEASED FOR
CONSTRUCTION
FOR REGULATORY APPROVAL,
BIDDING, PERMIT, OR
CONSTRUCTION PURPOSES.




PROJECT NAME
Fulton County
Animal Services
Facility

PROJECT LOCATION
1251 Fulton Industrial
Boulevard
Atlanta, GA 30318

PROJECT NUMBER
1004636.00

SHEET TITLE
SECTOR B -
TECHNOLOGY
PLAN

SHEET NUMBER



KEYPLAN


T2.11

Exhibit A - Attachment S


11/18/2021

GENERAL SITE PLAN NOTES

- FFE OF 6'-0" IN THESE PLANS REFERS TO CIVIL ELEVATION XX.XX' NAVD OR XX.XX' NGVD.
- EXISTING SITE TO REMAIN AS-IS WITHIN LIMITS OF DISTURBANCE UNLESS OTHERWISE SPECIFIED.
- CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO COMMENCING WORK.
- CONTRACTOR SHALL NOTIFY ARCHITECT OF ANY DISCREPANCY, INACCURACY OR CONFLICTING INFORMATION BEFORE EXECUTION OF WORK.
- DO NOT SCALE DIMENSIONS FROM DRAWINGS, ANY UNKNOWN DIMENSION SHALL BE OBTAINED FROM DESIGN PROFESSIONALS VIA REQUEST FOR INFORMATION (RFI).
- REFER TO CIVIL AND LANDSCAPE DWGS FOR ALL INFORMATION REGARDING SITE ELEMENTS INCLUDING BUT NOT LIMITED TO PAVING, GRADING, SITE DRAINAGE, PLANTINGS ECT.
- REFER TO ELECTRICAL & SECURITY FOR SITE LIGHTING POLE FIXTURE & VIDEO SURVEILLANCE.
- GATES TO MATCH ADJACENT FENCING, RE FENCE TYPES.
- FENCING TO REMAIN 3'-0" OFF EXTERIOR FACE OF CURB.



- Fencing required by GP per conditions agreed to in order to allow site access within the easement.**
- To remain in the project scope**
Type: Black Vinyl Coated Chain Link
- Pasture / Barn Fencing**
To remain in the project scope
FUTURE REVISION - VE NOT INCLUDED IN BASE SCOPE OF WORK
- Secure Parking / Dog Play Area Fencing**
To remain in the project scope
Type: Black Vinyl Coated Chain Link
- Public Facing Fencing**
To remain in the project scope
Type: Black Vinyl Coated Chain Link
FUTURE REVISION - VE NOT INCLUDED IN BASE SCOPE OF WORK
- Dog Yard / Kennel Fencing**
To remain in the project scope
Type: Black Vinyl Coated Chain Link
- Fencing NOT REQUIRED**



- PUBLIC PARKING COUNT**
64 STANDARD SPACES (7 EV READY)
24 PARALLEL SPACES
4 ACCESSIBLE SPACES
92 PARKING SPACES
- INTAKE/VETERINARY PARKING COUNT**
6 STANDARD SPACES
2 ACCESSIBLE SPACES
8 PARKING SPACES
- SECURE PARKING AREA**
20 OVERSIZE TRUCK SPACES (20 EV READY)
8 STANDARD SPACES
7 EV READY SPACES
3 ACCESSIBLE SPACES
38 PARKING SPACES
- TOTAL PARKING COUNT = 138 SPACES**

CLIENT

Fulton County Georgia
141 Pryor Street, SW,
Atlanta, GA 30303
T 404 612 4000

ARCHITECT

PGAL
1425 Ellsworth Industrial
Suite 15
Atlanta, GA 30318
T 404 602 3500
F 404 602 3810
www.pgal.com

CONSULTANT

DRAWING HISTORY

| NO. | DATE | DESCRIPTION |
|-----|------------|-------------|
| 1 | 10/08/2021 | 100% CD |

REGISTRATION
Copyright © 2021
RELEASED FOR
CONSTRUCTION
FOR REGULATORY APPROVAL,
BIDDING, PERMIT, OR
CONSTRUCTION PURPOSES.



PROJECT NAME
Fulton County
Animal Services
Facility

PROJECT LOCATION
1251 Industrial
Boulevard
Atlanta, GA 30318

PROJECT NUMBER
1004636.00

SHEET TITLE
ARCHITECTURAL
SITE PLAN
(ENLARGED)

SHEET NUMBER
A1.10

FILE NAME: BIM 360/Fulton County Animal Services Facility/ARCH - FCAS - RV12020.rvt
DATE STAMP: 10/8/2021 4:23:55 PM

ENLARGED SITE PLAN 1" = 50'-0" 1




EXHIBIT B

GMP COST

Exhibit B

11/18/2021



Project Name: *Fulton Co. Animal Shelter GMP*

Estimate Number: *21-21027*

Date: *11/18/2021*

| BID PACKAGE | TOTAL COST | | TOTAL COST | | VARIANCE | NOTES |
|---|--|--|----------------------|---------------------|----------|--|
| | 50% CD Budget w/ Approved VE 9/14/2021 | | GMP 11/18/2021 | | | |
| 01A GENERAL CONDITIONS | \$ 1,976,369 | | \$ 1,976,369 | \$ - | | |
| 01 GENERAL REQUIREMENTS | | | \$ - | \$ - | | |
| 01D.1400 FINAL CLEAN-UP | \$ 34,614 | | \$ - | \$ (34,614) | | Included in General Conditions |
| 02B.2100 SITEWORK | \$ 1,984,413 | | \$ 1,988,855 | \$ 4,442 | | |
| 02D.2400 PILE SUBCONTRACTOR | \$ 153,000 | | \$ 128,724 | \$ (24,276) | | |
| 02E.2500 PAVING & SURFACING | \$ 367,556 | | \$ 491,140 | \$ 123,584 | | Fuel price escalation |
| 02E.2510 SITE CONCRETE | \$ 343,516 | | \$ 589,369 | \$ 245,853 | | Shoring required plus material escalation |
| 02E.2520 CURBS AND GUTTERS | w/Paving & SURFACING | | \$ 96,640 | \$ 96,640 | | |
| 02E.2530 STRIPING AND SIGNS | w/Paving & SURFACING | | \$ 11,093 | \$ 11,093 | | |
| 02F.2620 UNIT PAVERS | | | \$ 87,956 | \$ 87,956 | | New scope |
| 02F.2640 FENCES AND GATES | \$ 583,748 | | \$ 849,189 | \$ 265,441 | | Added welded picket fence and paddock fencing at barn and pasture. Added call tower. |
| Approved changes to vinyl coated chain link | | | | | | Incorporated VE at GA Power Easement and Dog Courtyards |
| 02G.2700 LANDSCAPING | \$ 251,361 | | \$ 317,135 | \$ 65,774 | | Market price |
| 03A.3000 CONCRETE TURNKEY | \$ 1,085,022 | | \$ 1,480,641 | \$ 395,619 | | Foundations lowered to accommodate drains; new piers; material escalation |
| 04A.4000 MASONRY | \$ 3,090,444 | | \$ 2,394,823 | \$ (695,621) | | VE Incorporated |
| 05A.5000 STRUCTURAL STEEL - TURNKEY | \$ 2,336,310 | | \$ 2,368,102 | \$ 31,792 | | |
| 06A.6010 ROUGH CARPENTRY | \$ 150,762 | | \$ 150,762 | \$ - | | |
| 06B.6100 ARCHITECTURAL MILLWORK | \$ 510,066 | | \$ 566,366 | \$ 56,300 | | Market price. Steel cabinetry material escalation |
| 07A.7000 WATERPROOFING | \$ 139,451 | | \$ 190,630 | \$ 51,179 | | Air-moisture barrier at exterior wall cavity (previous in masonry system) |
| 07C.7220 ROOFING | \$ 834,234 | | \$ 1,269,594 | \$ 435,360 | | Escalation in insulation prices & procurement times (requiring temp roof). |
| 07C.7230 METAL ROOF AND WALL PANELS | \$ 343,740 | | \$ 316,131 | \$ (27,609) | | |
| 07C.7320 EXTERIOR SIDING | \$ 201,960 | | \$ 192,260 | \$ (9,700) | | |
| 08A.8000 DOORS, FRAMES, AND HARDWARE | \$ 860,747 | | \$ 1,067,411 | \$ 206,664 | | Changes to Doors, Frames and Hardware and Glass and Glazing scopes |
| 08A.8040 OVERHEAD DOORS/COILING GRILLS | \$ 89,472 | | \$ 66,728 | \$ (22,744) | | |
| 08A.8090 DOOR & HARDWARE INSTALLATION | \$ 61,200 | | \$ 50,949 | \$ (10,251) | | |
| 08B.8210 GLASS AND GLAZING | \$ 792,383 | | \$ 552,126 | \$ (240,257) | | Changes to Doors, Frames and Hardware and Glass and Glazing scopes |
| 09B.9100 DRYWALL | \$ 1,559,376 | | \$ 1,095,113 | \$ (464,263) | | Market price |
| 09B.9200 TILE & STONE | w/Resilient Flooring | | w/Resilient Flooring | \$ - | | |
| 09D.9350 RESILIENT FLOORING | \$ 150,704 | | \$ 170,436 | \$ 19,732 | | |
| 09E.9410 SPECIAL FLOORING | \$ 560,728 | | \$ 527,299 | \$ (33,429) | | |
| 09E.9500 PAINTING | \$ 626,865 | | \$ 368,891 | \$ (257,974) | | |
| 09E.9520 ACOUS. TREATMENTS | | | \$ 87,832 | \$ 87,832 | | Previously with drywall. Increased scope of work |
| 10A.1002 MARKERBOARDS/TKBOARDS | | | \$ 5,702 | \$ 5,702 | | New scope |
| 10A.1004 TOILET COMPARTMENTS & ACCESS. | \$ 18,315 | | \$ 50,579 | \$ 32,264 | | |
| 10A.1008 WALL/CORNER GUARDS | \$ 22,129 | | \$ 31,932 | \$ 9,803 | | |
| 10A.1012 CANOPIES | \$ 133,155 | | \$ 649,034 | \$ 515,879 | | Canopy designed in accordance with structural design |
| Target Additional Canopy VE | | | in above | | | VE incorporated to change to standard finish and revised details |
| 10A.1014 SIGNAGE | \$ 197,160 | | \$ 197,160 | \$ - | | Design-Build Allowance |
| 10A.1022 LOCKERS | \$ 2,861 | | \$ 9,996 | \$ 7,135 | | |
| 10A.1024 FIRE EXT.& CABINETS | \$ 5,826 | | \$ 8,421 | \$ 2,595 | | |
| 10A.1030 OPERABLE PARTITIONS | \$ 36,268 | | \$ 43,248 | \$ 6,980 | | |
| 10A.1037 DEMOUNTABLE PARTITIONS | | | \$ 47,736 | \$ 47,736 | | New Scope |
| 11A.1120 LAUNDRY EQUIP. | w/Miscellaneous Equipment | | \$ 100,343 | \$ 100,343 | | |
| 11A.1126 PROJECTORS & SCREENS | w/Miscellaneous Equipment | | \$ 28,050 | \$ 28,050 | | |
| 11A.1130 LOADING DOCK EQUIP. | w/Miscellaneous Equipment | | \$ 19,355 | \$ 19,355 | | |
| 11A.1136 FOOD SERVICE EQUIP. | w/Miscellaneous Equipment | | \$ 62,911 | \$ 62,911 | | |
| 11A.1138 RESIDENTIAL EQUIP. | w/Miscellaneous Equipment | | \$ 25,000 | \$ 25,000 | | |
| 11A.1144 MEDICAL & MISC. EQUIPMENT | \$ 1,740,878 | | \$ 2,409,023 | \$ 668,145 | | Changes to Miscellaneous Equipment scope. Added medical equipment |
| 12A.1230 WINDOW TREATMENTS | \$ 92,658 | | \$ 10,926 | \$ (81,732) | | Scope clarified |
| 13A.1330 PRE-ENGINEERED BUILDINGS | \$ 128,387 | | \$ 141,735 | \$ 13,348 | | |
| 15A.1500 PLUMBING | \$ 3,175,346 | | \$ 2,844,002 | \$ (331,344) | | Market price |
| 15B.1525 HVAC SYSTEMS | \$ 3,102,840 | | \$ 3,191,325 | \$ 88,485 | | Market price |
| 15C.1560 FIRE PROTECTION | \$ 212,160 | | \$ 215,089 | \$ 2,929 | | Market price |
| 16A.1600 ELECTRICAL SYSTEMS | \$ 3,420,025 | | \$ 2,995,781 | \$ (424,244) | | |
| Light fixt Pkg | in above | | in above | \$ - | | Target VE \$\$ incorporated |
| Large fans at dog run courtyard deleted | | | in above | \$ - | | Incorporated VE |
| Tier 3 Generator | | | in above | \$ - | | Incorporated VE |
| SUBTOTAL CONSTRUCTION COST | 31,376,052 | | 32,539,912 | 1,163,860 | | |
| PERMITS | w/original RFP | | \$ 14,124 | \$ 14,124 | | Add'l Permit amount needed for constr. cost beyond original \$32.5 mil |
| BONDS & INSURANCE | w/original RFP | | \$ 47,138 | \$ 47,138 | | Add'l Bond & Ins. amount needed for constr. cost beyond original \$32.5 mil |
| G.C. FEE | \$ 850,718 | | \$ 840,497 | \$ (10,221) | | Variance due to reconciled VE |
| TOTAL BEFORE CONTINGENCY | \$ 32,226,770 | | \$ 33,441,671 | \$ 1,214,901 | | |
| OWNER-CONTROLLED CONTINGENCY | \$ 875,019 | | \$ 941,519 | \$ 66,500 | | |
| DESIGN CONTINGENCY | \$ 875,019 | | \$ - | \$ (875,019) | | Used to cover difference between 50% & 100% docs and market conditions |
| TOTAL CONSTRUCTION COST + CONTINGENCY | 33,976,807 | | 34,383,190 | 406,383 | | |
| | *50% CD - ROW 64 ON PROJECT BUDGET ESTIMATE => \$33,646,807 + \$330,000 equipment reallocation | | | | | |
| ADDITIONAL UNINCORPORATED VALUE ENGINEERING | | | | | | |
| Fencing change at the pasture & barn | | | \$ (80,000) | | | |
| Previously rejected fence VE at Entrance | | | \$ (55,000) | | | Deferred decision toward end of the project |
| Target Pile Reduction | | | \$ (15,000) | | | |
| Landscaping | | | \$ (50,000) | | | Deferred decision toward end of the project |
| Change unit pavers to scored concrete | | | \$ (35,000) | | | Deferred decision toward end of the project |
| ADJUSTED TOTAL CONSTRUCTION COST + CONTINGENCY | 33,976,807 | | 34,148,190 | 171,383 | | *ADJUSTED - 100% CD - ROW 64 ON PROJECT BUDGET ESTIMATE |

EXHIBIT **C**

CLARIFICATIONS AND
ASSUMPTIONS

Clarifications and Assumptions

The following clarifications, in conjunction with the attached detailed Guaranteed Maximum Price (GMP) estimate, represent the complete scope of work, as understood, for the Fulton County Animal Services Facility. The following documents were used in preparation of this GMP estimate:

| <u>Exhibit</u> | <u>Attachment</u> | <u>Date</u> |
|----------------|---|-------------|
| Exhibit A | | |
| | Attachment A – Drawing Log | 11/18/21 |
| | Attachment B – Specification Log | 11/18/21 |
| | Attachment C – Geotechnical Exploration Report* | 07/02/21 |
| | Attachment D – Equipment (FF&E) Schedule | 11/04/21 |
| | Attachment E – FIB Update | 11/01/21 |
| | Attachment F – RFI Response Log #1 | 10/25/21 |
| | Attachment G – RFI Response Log #2 | 10/28/21 |
| | Attachment H – RFI Response Log #3 | 10/29/21 |
| | Attachment I – RFI Response Log #4 | 11/04/21 |
| | Attachment J – GMP Impact Items | 10/21/21 |
| | Attachment K – Mitchell Metals Canopy/Trellis Information | 11/18/21 |
| | Attachment L – LEED Online Session Email | 10/26/21 |
| | Attachment M – Roof Warranty Acceptance Email | 11/01/21 |
| | Attachment N – Custom Art Light | 11/04/21 |
| | Attachment O – Walk Off Mat Diagram | 11/09/21 |
| | Attachment P – Demountable Walls Email | 11/03/21 |
| | Attachment Q – Extended Wireless Access Points Email | 11/01/21 |
| | Attachment R – Additional Card Readers | 11/03/21 |
| | Attachment S – GMP Fencing Scope | 11/18/21 |

* - Geotechnical Exploration Report (see Exhibit A Attachment C) is included for informational purposes only. WJG expects any recommendations coming out of the report to be incorporated into the plans and specifications.

01. GENERAL REQUIREMENTS

- 01.01. Escalation and Procurement Delays: Due to the volatile market conditions, owner-controlled construction contingency can be used for costs associated with material escalation and procurement delays. This is especially true for steel, plastic, insulation, and roofing materials. The GMP is based upon the premise that WJG and Subcontractors can bill for and receive payment for materials procured and stored off site.

02. SITEWORK

- 02.01. Grading and Site Utilities
- a. Fees for water meter and vault to be installed by City of Atlanta are included at \$33,900
 - b. Sewer tap fees are included at \$3,995.
 1. Sanitary sewer tie-in to be done by open trench, not jack and bore.
 - c. Relocation of overhead power and associated costs are not included.
 - d. Relocation of “all utilities, storm drainage, signs, traffic signals and poles, etc.” required for GDOT work per General Site Note #17 on drawing C3.02 is not included.



- e. Key Note #4 on drawing C2.02 calls for “Storm Water Structure to be [Relocated]. See GDOT plans by Lowe Engineers dated XX/XX/2021.” The work associated with Key Note #4 is not included.
- 02.02. Asphalt Paving
 - a. DOT Right of Way striping included as thermoplastic. All other striping is two coats of traditional marking paint.
 - b. Work associated with Key Note #29 (GDOT work) on drawing C3.02 is not included.
- 02.03. Site Concrete
 - a. The site retaining wall is per detail 11/S3.03. No facing material is included.
- 02.04. Fencing
 - a. Priefert Estate Fencing included as fence type F3. Specified product not available.
 - b. Animal housing has been included per the Equipment Schedule (see Exhibit A Attachment D).
 - c. Fencing has been included per the GMP Fencing Scope (see Exhibit A Attachment S).
- 02.05. Hardscape
 - a. Unit pavers subgrade is included as 4” GAB and 1” of setting sand.
- 02.06. Landscaping
 - a. An irrigation system is not included.
- 03. CONCRETE**
 - 03.01. Cast-in-Place Concrete
 - a. Wall at the reception to receive a rubbed concrete finish.
- 04. MASONRY**
 - 04.01. Grout is only included at cells with rebar per RFI 1.12.
- 05. METALS**
 - 05.01. Metal Fabrications
 - a. Prices of raw steel continue to be volatile; manufacturers are unable to guarantee pricing until shop drawings are approved and sent to the fabricator. As noted above, any escalation from GMP pricing is expected to be an allowable owner-controlled contingency expense.
 - b. All canopies and trellises on the project are included as pre-manufactured aluminum systems (see Exhibit A Attachment K) in lieu of the structural steel fabrications indicated on the 10/8/2021 100% CD drawings.
- 06. WOOD**
 - 06.01. Millwork
 - a. Per email dated 10/26/2021, certified wood not included for LEED (see Exhibit A Attachment L).
- 07. THERMAL & MOISTURE PROTECTION**
 - 07.01. Waterproofing
 - a. Intumescent coating is not included.
 - b. Spray-applied fireproofing is not included.
 - 07.02. Roofing
 - a. Prices and lead times of roofing insulation continue to be volatile; manufacturers are unable to guarantee pricing until submittals are approved and the material is fabricated and loaded onto the delivery truck. As noted above, any escalation from GMP pricing is



expected to be an allowable owner-controlled contingency expense. Additionally, due to extraordinary long lead times, GMP includes installation of a temporary roof system to not impede interior finish schedules.

- b. Per the 11/1/2021 email response (Exhibit A Attachment M) from the Owner and the Architect, the roofing system is included with all layers of substrate, insulation and cover boards fasten simultaneously and mechanically attaching a 60 mil TPO.

08. DOORS & WINDOWS

08.01. Doors, Frames, and Hardware

- a. Slabs are included as being poured monolithically (with no masonry) at the door thresholds in lieu of detail 8/A7.55.

08.02. Special Glass Systems

- a. A skylight system is not included. A Specification Section 086250 – Tubular Daylighting Devices, is listed in the Project Manual Table of Contents, but no specification section is actually included, and no skylights are indicated on the drawings.

09. FINISHES

09.01. Paint & Wallcoverings

- a. Exposed ceilings / structure in housekeeping, mechanical room, and electrical rooms to be unfinished.
- b. The High-Performance Coating at CMU walls is included two block fill coats due to specifications calling for “pin-hole free” plus a finish coat.
- c. STC stenciling is not included.
- d. Film graphics, artwork, and custom light fixture per 11/4/2021 email (see Exhibit A Attachment N) and detail A9.111 are not included.

10. SPECIALTIES

10.01. Signage is included as a design-build allowance.

10.02. Canopies

- a. Kynar coated exterior canopies as provided by Mitchell Metals is included as approved by PGAL (see Exhibit A Attachment K).

10.03. Visual Display

- a. Glass markerboards are included.

10.04. Mats

- a. Entrance mats are included as Construction Specialties *Design Step* entrance mat, 20-50 square feet, 3/8” thick with rubber backing, 1 ½” perimeter frame, Duration texture in one of 8 manufacturer’s standard colors. Locations are in accordance with architects 11/9/2021 emailed sketch (see Exhibit A Attachment O).

11. EQUIPMENT

11.01. Furniture, Fixtures, Equipment, and FF&E

- a. Medical equipment designated Contractor-Furnished-Contractor-Installed is included (see Exhibit A Attachment D).
- b. Acoustical panels are included per the counts indicated on Equipment Schedule previously noted in the documents list.

11.02. Shelving

- a. The following counts and types of metal shelving are included as a shelving type is not specified on the FF&E schedule:



1. Nineteen (19) each of Metro Super Erecta Shelving Preconfigured model 3048-46NC.
2. Six (6) each of Metro Super Erecta Shelving Preconfigured model 2436-46BR.
3. Seven (7) each of Metro Super Erecta Shelving Preconfigured model 2448-46BR.
4. Four (4) each of Metro Super Erecta Shelving Preconfigured model 2460-46BR.
5. Five (5) each of Metro Super Erecta shelves model 1448NS.
6. Fourteen (14) each of Metro Super Erecta shelves model 1460NS.

13. SPECIAL CONSTRUCTION

- 13.01. An 8'x 30' x 6'(high) chicken coop as manufactured by American Coop is included.
- 13.02. Demountable partitions are included as manufactured by KI (see Exhibit A Attachment P) for architect's 11/3/2021 emailed approval.

15. MECHANICAL

- 15.01. Plumbing
 - a. No trap primers are included. 45 Trap guards are included for the areas assumed to have irregular wash downs per RFI response 4.05.
 - b. No plumbing under the barn slab is included. Civil drawings show piping to it and refer to plumbing plans, but no plumbing scope is shown.
- 15.02. Fire Protection
 - a. A fire pump is not included.

16. ELECTRICAL

- 16.01. Electrical
 - a. WAPs are not included in the plan west-most dog yard in Sector C and the plan south dog yards below Sector C and Sector D, as shown on drawing A2.10 (see Exhibit A Attachment Q).
 - b. Tier 4 generator exhaust per specification section 263212.14 -2.3 E is not included. Tier 4 exhaust is only available on tier 4 generators and a tier 4 generator will not work with the electrical system as designed. A tier 3 generator meeting the specification is included.
 - c. Additional card readers are included per architect's 11/3/2021 email (see Exhibit A Attachment R)
 - d. Wi-Fi and security systems at the barn are not included as scope and extent are yet to be determined.
 - e. Large fans and associated infrastructure at dog run courtyard not included.
 - f. Includes alternate lighting package to achieve target value engineering of \$400,000.00 (value inclusive of overhead and profit).

ALLOWANCES included in GMP

- | | |
|--|-----------|
| 1. Barn concrete foundation (yet to be designed). | \$34,000 |
| 2. Design build signage package. | \$197,160 |
| 3. Emergency Radio Responder System (ERRC) if required by City of Atlanta. | \$60,000 |

EXHIBIT |
CONTRACT SCHEDULE

Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float | 2021 2022 2023 | | | | | | | | | | | | | | | | | | | | | | | |
|---|--|------------------|-------------|-------------|-------------|---|-----|------|-----|-----|-----|-----|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | | | | | 2021 | | 2022 | | | | | | 2023 | | | | | | | | | | | | | | | |
| | | | | | | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct |
| Fulton County Animal Services Facility | | | | | | Fulton County Animal Services | | | | | | | | | | | | | | | | | | | | | | | |
| PRE AWARD | | | | | | PRE AWARD | | | | | | | | | | | | | | | | | | | | | | | |
| PA1000 | Submit RFP Proposal | 0d | 28-Apr-21 A | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PA1040 | Owner RFP Review | 10d | 29-Apr-21 A | 14-Jul-21 A | | | | | | | | | | | | | | | | | | | | | | | | | |
| PA1030 | Interview | 5d | 09-Jun-21 A | 09-Jun-21 A | | | | | | | | | | | | | | | | | | | | | | | | | |
| PA1020 | Fulton County Board of Commissioners Meeti... | 0d | 14-Jul-21 A | 14-Jul-21 A | | Board of Commissioners Meeting - July | | | | | | | | | | | | | | | | | | | | | | | |
| PA1110 | Executed Contract | 0d | | 03-Aug-21 A | | Contract | | | | | | | | | | | | | | | | | | | | | | | |
| PA1010 | Notice to Proceed | 0d | | 02-Dec-21 | 8d | ◆ Notice to Proceed | | | | | | | | | | | | | | | | | | | | | | | |
| PA1060 | GMP Approved (BOC Meeting) | 0d | | 02-Dec-21 | 0d | ◆ GMP Approved (BOC Meeting) | | | | | | | | | | | | | | | | | | | | | | | |
| PA1120 | Start Construction | 0d | 28-Mar-22 | | -1d | ◆ Start Construction | | | | | | | | | | | | | | | | | | | | | | | |
| DESIGN/PRICING | | | | | | DESIGN/PRICING | | | | | | | | | | | | | | | | | | | | | | | |
| DESIGN DEVELOPMENT | | | | | | DESIGN DEVELOPMENT | | | | | | | | | | | | | | | | | | | | | | | |
| DD-6490 | Design Development Production | 38d | 01-Feb-21 A | 21-May-21 A | 2d | Design Development Production | | | | | | | | | | | | | | | | | | | | | | | |
| CONSTRUCTION DOCUMENTS | | | | | | CONSTRUCTION DOCUMENTS | | | | | | | | | | | | | | | | | | | | | | | |
| 50% CONSTRUCTION DOCUMENTS (GMP) | | | | | | CONSTRUCTION DOCUMENTS (GMP) | | | | | | | | | | | | | | | | | | | | | | | |
| CD-6520 | 50% Construction Documents Released | 9d | 01-Jun-21 A | 06-Aug-21 A | | 50% Construction Documents Released | | | | | | | | | | | | | | | | | | | | | | | |
| CD-6600 | 50% CD Cost Estimating | 20d | 09-Aug-21 A | 03-Sep-21 A | | 50% CD Cost Estimating | | | | | | | | | | | | | | | | | | | | | | | |
| CD-6870 | Owner Review of 50% CD Pricing | 10d | 07-Sep-21 A | 20-Sep-21 A | | Owner Review of 50% CD Pricing | | | | | | | | | | | | | | | | | | | | | | | |
| FINAL CONSTRUCTION DOCUMENTS | | | | | | FINAL CONSTRUCTION DOCUMENTS | | | | | | | | | | | | | | | | | | | | | | | |
| CD-6510 | Construction Permit Documents Released | 42d | 09-Aug-21 A | 08-Oct-21 A | | Construction Permit Documents Released | | | | | | | | | | | | | | | | | | | | | | | |
| CD-6610 | GMP Pricing | 25d | 11-Oct-21 A | 12-Nov-21 A | | GMP Pricing | | | | | | | | | | | | | | | | | | | | | | | |
| CD-6660 | Owner Review & Approval of GMP | 10d | 12-Nov-21 | 29-Nov-21 | 2d | Owner Review & Approval of GMP | | | | | | | | | | | | | | | | | | | | | | | |
| PERMITTING | | | | | | PERMITTING | | | | | | | | | | | | | | | | | | | | | | | |
| CD-6650 | Land Disturbance Permit | 60d | 17-Sep-21 A | 16-Nov-21 | 87d | Land Disturbance Permit | | | | | | | | | | | | | | | | | | | | | | | |
| CD-6640 | Building Permit | 40d | 12-Nov-21 | 12-Jan-22 | 117d | Building Permit | | | | | | | | | | | | | | | | | | | | | | | |
| A2000 | Health Department Permit | 45d | 12-Nov-21 | 20-Jan-22 | 116d | Health Department Permit | | | | | | | | | | | | | | | | | | | | | | | |
| CD-6680 | EPD Approval | 25d | 12-Nov-21 | 20-Dec-21 | 65d | EPD Approval | | | | | | | | | | | | | | | | | | | | | | | |
| A2160 | Fulton Industrial Lane Closure Permit (Utility ... | 50d | 03-Jan-22 | 14-Mar-22 | 160d | Fulton Industrial Lane Closure Permit (Utility Tie-In) - COA & GDOT | | | | | | | | | | | | | | | | | | | | | | | |
| MILESTONES | | | | | | MILESTONES | | | | | | | | | | | | | | | | | | | | | | | |
| CONSTRUCTION MILESTONES | | | | | | CONSTRUCTION MILESTONES | | | | | | | | | | | | | | | | | | | | | | | |
| MI1150 | Mobilization | 0d | 28-Mar-22 | | -3d | ◆ Mobilization | | | | | | | | | | | | | | | | | | | | | | | |
| MI1130 | Building Pad Ready | 0d | | 30-Jun-22 | 0d | ◆ Building Pad Ready | | | | | | | | | | | | | | | | | | | | | | | |
| MI1080 | Permanent Power | 0d | | 24-Jan-23 | 41d | ◆ Permanent Power | | | | | | | | | | | | | | | | | | | | | | | |
| MI1040 | Final Building Inspection | 0d | | 26-May-23 | 0d | ◆ Final Building Inspection | | | | | | | | | | | | | | | | | | | | | | | |
| MI1030 | Contract Substantial Completion | 0d | | 30-May-23 | 0d | ◆ Contract Substantial Completion | | | | | | | | | | | | | | | | | | | | | | | |
| MI1050 | Certificate of Occupancy | 0d | | 30-May-23 | 0d | ◆ Certificate of Occupancy | | | | | | | | | | | | | | | | | | | | | | | |
| MI1200 | Calculated Substantial Completion | 0d | | 30-May-23 | 0d | ◆ Calculated Substantial Completion | | | | | | | | | | | | | | | | | | | | | | | |
| MI1140 | Final Completion | 0d | | 10-Jul-23 | 0d | ◆ Final Completion | | | | | | | | | | | | | | | | | | | | | | | |
| MI1070 | Punchlist Complete | 0d | | 10-Jul-23 | 0d | ◆ Punchlist Complete | | | | | | | | | | | | | | | | | | | | | | | |
| Top Out | | | | | | Top Out | | | | | | | | | | | | | | | | | | | | | | | |
| MI1170 | Top Out - Sector A & B | 0d | | 10-Jan-23 | 51d | ◆ Top Out - Sector A & B | | | | | | | | | | | | | | | | | | | | | | | |
| MI1120 | Top Out - Sector C & D | 0d | | 22-Mar-23 | 13d | ◆ Top Out - Sector C & D | | | | | | | | | | | | | | | | | | | | | | | |

- Current
- Progress
- Critical
- ◆ Milestones
- ▮ Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 1 of 14


INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|--|--|------------------|-------------|-----------|-------------|
| | | | | | |
| Roof Dry-In | | | | | |
| MI1180 | Roof Dry-In - Sector A & B | 0d | | 07-Apr-23 | 1d |
| MI1110 | Roof Dry In - Sector C & D | 0d | | 09-Feb-23 | 30d |
| Building Dry-In | | | | | |
| MI1190 | Building Dry In - Sector A & B | 0d | | 07-Apr-23 | 1d |
| MI1100 | Building Dry In - Sector C & D | 0d | | 17-Feb-23 | 24d |
| Conditioned Air | | | | | |
| MI1090 | Conditioned Air - Sector A & B | 0d | | 07-Apr-23 | 1d |
| MI1160 | Conditioned Air - Sector C & D | 0d | | 11-Apr-23 | 9d |
| OWNER MILESTONES | | | | | |
| CD-6670 | FAA Approval | 90d | 15-Nov-21 A | 30-May-23 | 29d |
| OM1180 | Water Meter Install | 5d | 01-Aug-22 | 24-Mar-22 | 140d |
| OM1160 | Transformer Set | 0d | | 05-Aug-22 | 96d |
| OM1170 | Gas Meter Installed | 0d | | 22-Aug-22 | 127d |
| OM1140 | Phone Line | 0d | | 30-Dec-22 | 57d |
| OM1150 | FFE Delivery | 0d | | 09-Jan-23 | 89d |
| PROCUREMENT | | | | | |
| DIVISION 02 - SITE CONSTRUCTION | | | | | |
| SITE EARTHWORK | | | | | |
| PROC1900 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 11-Apr-22 | 36d |
| PROC1840 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 08-Dec-21 | 18d |
| PROC2360 | Subcontractor Submittal Prep - Retaining Wall... | 10d | 09-Dec-21 | 22-Dec-21 | 18d |
| PROC1850 | TWCC Submittal Review | 5d | 09-Dec-21 | 22-Dec-21 | 86d |
| PROC2370 | TWCC Submittal Review - Retaining Wall Shops | 5d | 23-Dec-21 | 30-Dec-21 | 18d |
| PROC1860 | Architect Submittal Review | 10d | 23-Dec-21 | 30-Dec-21 | 86d |
| PROC2380 | Architect Submittal Review - Retaining Wall S... | 10d | 03-Jan-22 | 14-Jan-22 | 18d |
| PROC1870 | Fabrication - Underground Detention Pond | 60d | 03-Jan-22 | 14-Jan-22 | 86d |
| PROC2350 | Fabrication - Precast Manholes | 30d | 18-Jan-22 | 11-Apr-22 | 18d |
| PROC2390 | Fabrication - Retaining Wall Rebar | 10d | 18-Jan-22 | 28-Feb-22 | 71d |
| AGGREGATE PILES | | | | | |
| PROC2700 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 28-Feb-22 | 71d |
| PROC2710 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 08-Dec-21 | 18d |
| PROC2730 | TWCC Submittal Review | 5d | 09-Dec-21 | 22-Dec-21 | 18d |
| PROC2750 | Architect / Engineer Submittal Review | 10d | 23-Dec-21 | 30-Dec-21 | 18d |
| PROC2770 | Procurment - Aggregate piers | 30d | 03-Jan-22 | 14-Jan-22 | 18d |
| PAVING AND STRIPING | | | | | |
| PROC2780 | Subcontractor Contract Executed | 5d | 18-Jan-22 | 28-Feb-22 | 71d |
| PROC2790 | Subcontractor Submittal Prep | 10d | 02-Dec-21 | 08-Dec-21 | 18d |
| PROC2800 | TWCC Submittal Review | 5d | 09-Dec-21 | 22-Dec-21 | 18d |
| PROC2810 | Architect / Engineer Submittal Review | 10d | 23-Dec-21 | 30-Dec-21 | 18d |
| PROC2820 | Procurement - Paving | 20d | 03-Jan-22 | 14-Jan-22 | 18d |
| SITE CONCRETE | | | | | |
| 52d 02-Dec-21 14-Feb-22 81d | | | | | |



Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 2 of 14

INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float | 2021 | | | | | | | | | | | | 2022 | | | | | | | | | | | | 2023 | | | | | | | | | | | | | |
|-------------------------------|--|------------------|-----------|-----------|-------------|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | | | | | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2830 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 18d | ■ Subcontractor Contract Executed | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2840 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 18d | ■ Subcontractor Submittal Prep | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2850 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 18d | ■ TWCC Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2860 | Architect / Engineer Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 18d | ■ Architect / Engineer Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2870 | Procurement - Site Concrete | 20d | 18-Jan-22 | 14-Feb-22 | 81d | ■ Procurement - Site Concrete | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| CURB AND GUTTER | | 52d | 02-Dec-21 | 14-Feb-22 | 242d | ■ CURB AND GUTTER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2880 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 18d | ■ Subcontractor Contract Executed | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2890 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 18d | ■ Subcontractor Submittal Prep | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2900 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 18d | ■ TWCC Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2910 | Architect / Engineer Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 18d | ■ Architect / Engineer Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2920 | Procurement - Curb and Gutter | 20d | 18-Jan-22 | 14-Feb-22 | 236d | ■ Procurement - Curb and Gutter | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| UNIT PAVERS | | 52d | 02-Dec-21 | 14-Feb-22 | 242d | ■ UNIT PAVERS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2930 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 18d | ■ Subcontractor Contract Executed | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2940 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 18d | ■ Subcontractor Submittal Prep | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2950 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 18d | ■ TWCC Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2960 | Architect / Engineer Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 18d | ■ Architect / Engineer Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2970 | Procurement - Unit Pavers | 20d | 18-Jan-22 | 14-Feb-22 | 236d | ■ Procurement - Unit Pavers | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| FENCES AND GATES | | 72d | 02-Dec-21 | 14-Mar-22 | 284d | ■ FENCES AND GATES | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2980 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 18d | ■ Subcontractor Contract Executed | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC2990 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 18d | ■ Subcontractor Submittal Prep | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC3000 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 18d | ■ TWCC Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC3010 | Architect / Engineer Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 18d | ■ Architect / Engineer Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC3020 | Fabrication - Fencing and Gates | 40d | 18-Jan-22 | 14-Mar-22 | 278d | ■ Fabrication - Fencing and Gates | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| LANDSCAPING | | 52d | 02-Dec-21 | 14-Feb-22 | 296d | ■ LANDSCAPING | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC3030 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 18d | ■ Subcontractor Contract Executed | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC3040 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 18d | ■ Subcontractor Submittal Prep | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC3050 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 18d | ■ TWCC Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC3060 | Architect / Engineer Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 18d | ■ Architect / Engineer Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC3070 | Procurement - Landscaping | 20d | 18-Jan-22 | 14-Feb-22 | 290d | ■ Procurement - Landscaping | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DIVISION 03 - CONCRETE | | 72d | 02-Dec-21 | 14-Mar-22 | 76d | ■ DIVISION 03 - CONCRETE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1910 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 75d | ■ Subcontractor Contract Executed | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1120 | Subcontractor Submittal Prep | 20d | 09-Dec-21 | 07-Jan-22 | 75d | ■ Subcontractor Submittal Prep | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1130 | TWCC Submittal Review | 5d | 10-Jan-22 | 14-Jan-22 | 75d | ■ TWCC Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1140 | Architect Submittal Review | 10d | 18-Jan-22 | 31-Jan-22 | 75d | ■ Architect Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1150 | Rebar Fabrication | 30d | 01-Feb-22 | 14-Mar-22 | 75d | ■ Rebar Fabrication | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DIVISION 04 - MASONRY | | 112d | 02-Dec-21 | 09-May-22 | 40d | ■ DIVISION 04 - MASONRY | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1920 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 39d | ■ Subcontractor Contract Executed | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1160 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 39d | ■ Subcontractor Submittal Prep | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1170 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 39d | ■ TWCC Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1180 | Architect Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 39d | ■ Architect Submittal Review | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROC1190 | Fabrication - 16 Weeks for Ground Face 8 for ... | 80d | 18-Jan-22 | 09-May-22 | 39d | ■ Fabrication - 16 Weeks for Ground Face 8 for Reg | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DIVISION 05 - STEEL | | 228d | 02-Dec-21 | 21-Oct-22 | 8d | ■ DIVISION 05 - STEEL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 3 of 14


INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|--|--|------------------|------------------|------------------|-------------|
| | | | | | |
| PROC1930 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 8d |
| PROC1200 | Subcontractor Submittal Prep | 25d | 09-Dec-21 | 14-Jan-22 | 8d |
| PROC1210 | TWCC Submittal Review | 5d | 18-Jan-22 | 24-Jan-22 | 8d |
| PROC1220 | Architect Submittal Review | 10d | 25-Jan-22 | 07-Feb-22 | 8d |
| PROC1570 | Anchor Bolt Fabrication | 20d | 08-Feb-22 | 07-Mar-22 | 80d |
| PROC1880 | Redetailing | 10d | 08-Feb-22 | 21-Feb-22 | 8d |
| PROC1230 | Steel Joist Fabrication | 170d | 22-Feb-22 | 21-Oct-22 | 8d |
| PROC1560 | Steel Fabrication | 60d | 22-Feb-22 | 16-May-22 | 103d |
| DIVISION 06 - WOOD, PLASTICS & COMPOSITES | | 92d | 02-Dec-21 | 11-Apr-22 | 266d |
| PROC1940 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 260d |
| PROC1240 | Subcontractor Submittal Prep | 20d | 09-Dec-21 | 07-Jan-22 | 260d |
| PROC1250 | TWCC Submittal Review | 5d | 10-Jan-22 | 14-Jan-22 | 260d |
| PROC1260 | Architect Submittal Review | 10d | 18-Jan-22 | 31-Jan-22 | 260d |
| PROC1270 | Fabrication - Millwork - 10 wks | 50d | 01-Feb-22 | 11-Apr-22 | 260d |
| PROC2270 | Fabrication - Quartz 6 wks | 30d | 01-Feb-22 | 14-Mar-22 | 280d |
| DIVISION 07 - THERMAL & MOISTURE PROTECTION | | 298d | 02-Dec-21 | 27-Jan-23 | 45d |
| ROOFING - PVC | | 298d | 02-Dec-21 | 27-Jan-23 | 45d |
| PROC1950 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 45d |
| PROC1280 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 45d |
| PROC1290 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 45d |
| PROC1300 | Architect Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 45d |
| PROC1310 | Fabrication - Poly Insulation 52 Weeks | 260d | 18-Jan-22 | 27-Jan-23 | 45d |
| PROC2240 | Fabrication - TPO & Fasteners - 26 Weeks | 130d | 18-Jan-22 | 21-Jul-22 | 103d |
| PROC2250 | Fabrication - Coping 8 Weeks | 40d | 18-Jan-22 | 14-Mar-22 | 193d |
| WATERPROOFING | | 74d | 02-Dec-21 | 16-Mar-22 | 137d |
| PROC2400 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 103d |
| PROC2410 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 103d |
| PROC2420 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 103d |
| PROC2430 | Architect Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 103d |
| PROC2280 | Fabrication - Expansion Joints | 42d | 18-Jan-22 | 16-Mar-22 | 136d |
| PROC2440 | Procurment - Waterproofing | 20d | 18-Jan-22 | 14-Feb-22 | 158d |
| METAL ROOF AND WALL PANELS | | 74d | 02-Dec-21 | 16-Mar-22 | 224d |
| PROC2530 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 103d |
| PROC2540 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 103d |
| PROC2550 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 103d |
| PROC2560 | Architect Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 103d |
| PROC2570 | Fabrication - Metal Panels | 42d | 18-Jan-22 | 16-Mar-22 | 218d |
| DIVISION 08 - OPENINGS | | 193d | 02-Dec-21 | 01-Sep-22 | 220d |
| GLASS AND GLAZING | | 155d | 02-Dec-21 | 11-Jul-22 | 143d |
| PROC2450 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 138d |
| PROC2460 | Subcontractor Submittal Prep | 20d | 09-Dec-21 | 07-Jan-22 | 138d |
| PROC2470 | TWCC Submittal Review | 5d | 10-Jan-22 | 14-Jan-22 | 138d |



Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 4 of 14


INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|--|--|------------------|------------------|------------------|-------------|
| | | | | | |
| PROC2480 | Architect Submittal Review | 10d | 18-Jan-22 | 31-Jan-22 | 138d |
| PROC1350 | Fabrication - Storefront and Curtainwall | 112d | 01-Feb-22 | 11-Jul-22 | 138d |
| PROC3080 | Fabrication - Glass | 112d | 01-Feb-22 | 11-Jul-22 | 138d |
| DOORS, FRAMES AND HARDWARE | | 122d | 02-Dec-21 | 23-May-22 | 60d |
| PROC1960 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 59d |
| PROC1320 | Subcontractor Submittal Prep | 20d | 09-Dec-21 | 07-Jan-22 | 59d |
| PROC1330 | TWCC Submittal Review | 5d | 10-Jan-22 | 14-Jan-22 | 59d |
| PROC1340 | Architect Submittal Review - Doors and Hard... | 10d | 18-Jan-22 | 31-Jan-22 | 59d |
| PROC2330 | Architect Submittal Review - Frames | 10d | 18-Jan-22 | 31-Jan-22 | 59d |
| PROC2300 | Fabrication - Doors and Hardware - Need! | 80d | 01-Feb-22 | 23-May-22 | 59d |
| PROC2340 | Fabrication - Frames - Need! | 80d | 01-Feb-22 | 23-May-22 | 59d |
| OVERHEAD COILING DOORS | | 193d | 02-Dec-21 | 01-Sep-22 | 220d |
| PROC2490 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 362d |
| PROC2500 | Subcontractor Submittal Prep | 20d | 09-Dec-21 | 07-Jan-22 | 362d |
| PROC2510 | TWCC Submittal Review | 5d | 10-Jan-22 | 14-Jan-22 | 362d |
| PROC2520 | Architect Submittal Review | 10d | 18-Jan-22 | 31-Jan-22 | 362d |
| PROC2260 | Fabrication - OH Doors - 30 Weeks | 150d | 01-Feb-22 | 01-Sep-22 | 212d |
| DIVISION 09 - FINISHES | | 116d | 07-Dec-21 | 18-May-22 | 232d |
| PROC1970 | Subcontractor Contract Executed | 5d | 07-Dec-21 | 13-Dec-21 | 212d |
| PROC1360 | Subcontractor Submittal Prep | 10d | 14-Dec-21 | 28-Dec-21 | 212d |
| PROC1370 | TWCC Submittal Review | 5d | 29-Dec-21 | 05-Jan-22 | 212d |
| PROC1380 | Architect Submittal Review | 10d | 06-Jan-22 | 20-Jan-22 | 212d |
| DRYWALL AND ACT | | 52d | 21-Jan-22 | 04-Apr-22 | 218d |
| PROC2310 | Fabrication - Studs 4 wks, ACT 8 wks | 52d | 21-Jan-22 | 04-Apr-22 | 212d |
| TILE, FLOORING AND BASE | | 84d | 21-Jan-22 | 18-May-22 | 232d |
| PROC2320 | Fabrication - Tile and Flooring | 84d | 21-Jan-22 | 18-May-22 | 226d |
| PAINT AND SPECIAL COATINGS | | 52d | 21-Jan-22 | 04-Apr-22 | 241d |
| PROC1390 | Fabrication - Paint 8 wks, Acoustic Panels 8 wks | 52d | 21-Jan-22 | 04-Apr-22 | 235d |
| ACOUSTICAL TREATMENTS | | | | | |
| DIVISION 10 - SPECIALTIES | | 183d | 14-Dec-21 | 30-Aug-22 | 177d |
| PROC1980 | Subcontractor Contract Executed | 5d | 14-Dec-21 | 20-Dec-21 | 147d |
| PROC1400 | Subcontractor Submittal Prep | 10d | 21-Dec-21 | 05-Jan-22 | 147d |
| PROC1410 | TWCC Submittal Review | 5d | 06-Jan-22 | 12-Jan-22 | 147d |
| PROC1420 | Architect Submittal Review | 10d | 13-Jan-22 | 27-Jan-22 | 147d |
| PROC1430 | Fabrication - Vet Specialties - Nycom - 30 wks | 150d | 28-Jan-22 | 30-Aug-22 | 147d |
| TOILET PARTITIONS, ACCESSORIES AND FECS | | 92d | 14-Dec-21 | 21-Apr-22 | 268d |
| PROC2580 | Subcontractor Contract Executed | 5d | 14-Dec-21 | 20-Dec-21 | 262d |
| PROC2590 | Subcontractor Submittal Prep | 10d | 21-Dec-21 | 05-Jan-22 | 262d |
| PROC2600 | TWCC Submittal Review | 5d | 06-Jan-22 | 12-Jan-22 | 262d |
| PROC2610 | Architect Submittal Review | 10d | 13-Jan-22 | 27-Jan-22 | 262d |
| PROC2630 | Fabrication - Toilet Accessories | 60d | 28-Jan-22 | 21-Apr-22 | 262d |
| PROC2620 | Fabrication - Toilet Partitions | 60d | 28-Jan-22 | 21-Apr-22 | 262d |



Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 5 of 14

INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|--|---|------------------|-----------|-----------|-------------|
| | | | | | |
| PROC2640 | Fabrication - Fire Extinguishers and Cabinets | 30d | 28-Jan-22 | 10-Mar-22 | 292d |
| WALL PROTECTION AND CORNER GUARDS | | 92d | 14-Dec-21 | 21-Apr-22 | 268d |
| PROC2650 | Subcontractor Contract Executed | 5d | 14-Dec-21 | 20-Dec-21 | 262d |
| PROC2660 | Subcontractor Submittal Prep | 10d | 21-Dec-21 | 05-Jan-22 | 262d |
| PROC2670 | TWCC Submittal Review | 5d | 06-Jan-22 | 12-Jan-22 | 262d |
| PROC2680 | Architect Submittal Review | 10d | 13-Jan-22 | 27-Jan-22 | 262d |
| PROC2690 | Procurement - Wall protection and corner gua... | 60d | 28-Jan-22 | 21-Apr-22 | 262d |
| CANOPIES | | | | | |
| SIGNAGE | | | | | |
| LOCKERS | | | | | |
| OPERABLE PARTITIONS | | | | | |
| DEMOUNTABLE PARTITIONS | | | | | |
| DIVISION 11 - EQUIPMENT | | 102d | 02-Dec-21 | 25-Apr-22 | 241d |
| PROC1990 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 225d |
| PROC1440 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 225d |
| PROC1450 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 225d |
| PROC1460 | Architect Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 225d |
| PROC1520 | Fabrication - Freezer | 70d | 18-Jan-22 | 25-Apr-22 | 225d |
| PROC1470 | Fabrication | 30d | 18-Jan-22 | 28-Feb-22 | 275d |
| LAUNDRY EQUIPMENT | | | | | |
| PARKING CONTROL | | | | | |
| LOADING DOCK EQUIPMENT | | | | | |
| FOOD SERVICE EQUIPMENT | | | | | |
| RESIDENTIAL EQUIPMENT | | | | | |
| MEDICAL EQUIPMENT AND SPECIALTY CASEWORK | | | | | |
| DIVISION 12 - FURNISHING | | 62d | 14-Dec-21 | 10-Mar-22 | 273d |
| PROC2000 | Subcontractor Contract Executed | 5d | 14-Dec-21 | 20-Dec-21 | 267d |
| PROC1480 | Subcontractor Submittal Prep | 10d | 21-Dec-21 | 05-Jan-22 | 267d |
| PROC1490 | TWCC Submittal Review | 5d | 06-Jan-22 | 12-Jan-22 | 267d |
| PROC1500 | Architect Submittal Review | 10d | 13-Jan-22 | 27-Jan-22 | 267d |
| PROC1510 | Fabrication | 30d | 28-Jan-22 | 10-Mar-22 | 267d |
| CHICKEN COOP | | | | | |
| WINDOW TREATMENTS | | | | | |
| DIVISION 13 - PRE-FAB BARN | | 62d | 02-Dec-21 | 28-Feb-22 | 280d |
| PROC2150 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 274d |
| PROC2160 | Subcontractor Submittal Prep | 10d | 09-Dec-21 | 22-Dec-21 | 274d |
| PROC2170 | TWCC Submittal Review | 5d | 23-Dec-21 | 30-Dec-21 | 274d |
| PROC2180 | Architect Submittal Review | 10d | 03-Jan-22 | 14-Jan-22 | 274d |
| PROC2190 | Fabrication | 30d | 18-Jan-22 | 28-Feb-22 | 274d |
| DIVISION 21- FIRE PROTECTION | | 77d | 02-Dec-21 | 21-Mar-22 | 195d |
| PROC2030 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 192d |
| PROC1600 | Subcontractor Submittal Prep | 15d | 09-Dec-21 | 30-Dec-21 | 192d |



Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 6 of 14


INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|---------------------------------------|--|------------------|------------------|------------------|-------------|
| | | | | | |
| PROC1610 | TWCC Submittal Review | 5d | 03-Jan-22 | 07-Jan-22 | 192d |
| PROC2090 | Fire Marshall Review | 20d | 10-Jan-22 | 07-Feb-22 | 192d |
| PROC1620 | Architect Submittal Review | 10d | 10-Jan-22 | 24-Jan-22 | 202d |
| PROC1630 | Fabrication | 30d | 08-Feb-22 | 21-Mar-22 | 192d |
| DIVISION 22 - PLUMBING | | 93d | 02-Dec-21 | 12-Apr-22 | 59d |
| PROC2040 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 58d |
| PROC1640 | Subcontractor Submittal Prep | 15d | 09-Dec-21 | 30-Dec-21 | 58d |
| PROC1650 | TWCC Submittal Review | 5d | 03-Jan-22 | 07-Jan-22 | 58d |
| PROC1660 | Architect Submittal Review | 10d | 10-Jan-22 | 24-Jan-22 | 58d |
| PROC1670 | Fabrication and Fixtures | 56d | 25-Jan-22 | 12-Apr-22 | 58d |
| DIVISION 23 - MECHANICAL | | 158d | 02-Dec-21 | 14-Jul-22 | 168d |
| PROC2050 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 157d |
| PROC1680 | Subcontractor Submittal Prep | 15d | 09-Dec-21 | 30-Dec-21 | 157d |
| PROC1690 | TWCC Submittal Review | 5d | 03-Jan-22 | 07-Jan-22 | 157d |
| PROC1700 | Architect Submittal Review | 10d | 18-Jan-22 | 31-Jan-22 | 157d |
| PROC1710 | Fabrication - Ductwork | 70d | 01-Feb-22 | 09-May-22 | 157d |
| PROC2230 | Equipment - AHUs, DOAS and ERVs | 115d | 01-Feb-22 | 14-Jul-22 | 158d |
| PROC3100 | Equipment - VFDs, VAVs, Fans, Louvers, Heat... | 30d | 01-Feb-22 | 14-Mar-22 | 197d |
| PROC3090 | Equipment - Multi-stack Chiller | 100d | 01-Feb-22 | 22-Jun-22 | 178d |
| DIVISION 26 - ELECTRICAL | | 268d | 02-Dec-21 | 16-Dec-22 | 93d |
| PROC2060 | Subcontractor Contract Executed | 5d | 02-Dec-21 | 08-Dec-21 | 41d |
| PROC1720 | Subcontractor Submittal Prep | 15d | 09-Dec-21 | 30-Dec-21 | 41d |
| PROC1730 | TWCC Submittal Review | 5d | 03-Jan-22 | 07-Jan-22 | 41d |
| PROC1740 | Architect Submittal Review | 10d | 10-Jan-22 | 24-Jan-22 | 41d |
| PROC1750 | Fabrication | 80d | 25-Jan-22 | 16-May-22 | 155d |
| PROC2200 | Generator Fab and Deliver | 228d | 25-Jan-22 | 16-Dec-22 | 41d |
| PROC2210 | Gear - Switchboards, Panels and Transformers | 175d | 25-Jan-22 | 30-Sep-22 | 98d |
| PROC2220 | Lighting | 70d | 25-Jan-22 | 02-May-22 | 248d |
| IT, ACCESS CONTROL AND TELECOM | | | | | |
| CONSTRUCTION | | 332d | 28-Mar-22 | 10-Jul-23 | 0d |
| SITWORK | | 296d | 28-Mar-22 | 19-May-23 | 6d |
| EARTHWORK | | 214d | 28-Mar-22 | 24-Jan-23 | 45d |
| A1100 | Mobilization & Initial Erosion Control (Include... | 10d | 28-Mar-22 | 12-Apr-22 | -1d |
| A2140 | Water Main Tie-In (Boring) | 10d | 28-Mar-22 | 12-Apr-22 | 153d |
| A1110 | Clearing and Grubbing | 20d | 13-Apr-22 | 10-May-22 | -1d |
| A2150 | Sewer Main Tie-In (Trench) | 5d | 13-Apr-22 | 19-Apr-22 | 153d |
| A2850 | Mass Grading - North Half | 15d | 27-Apr-22 | 17-May-22 | -1d |
| A2630 | Site Retaining Wall - Foundation | 10d | 11-May-22 | 24-May-22 | 16d |
| A1120 | Mass Grading - South Half | 15d | 18-May-22 | 07-Jun-22 | -1d |
| A2620 | Site Retaining Wall - Wall | 15d | 25-May-22 | 14-Jun-22 | 16d |
| A1320 | Soil Settlement Monitoring | 3d | 07-Jun-22 | 11-Jun-22 | -1d |
| A2120 | Aggregate Piers - Test Piers | 5d | 09-Jun-22 | 16-Jun-22 | 0d |



Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 7 of 14


INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|-----------------------|--|------------------|------------------|------------------|-------------|
| | | | | | |
| A2130 | Aggregate Piers | 10d | 16-Jun-22 | 30-Jun-22 | 0d |
| A2180 | Storm Line Installation | 20d | 27-Jun-22 | 22-Jul-22 | 95d |
| A2220 | Sewer Line Installation | 10d | 11-Jul-22 | 22-Jul-22 | 95d |
| A2170 | Water Line Installation | 10d | 18-Jul-22 | 29-Jul-22 | 95d |
| A1130 | Gas Line installation | 7d | 01-Aug-22 | 09-Aug-22 | 145d |
| A3560 | Generator Install | 20d | 16-Dec-22 | 24-Jan-23 | 32d |
| FINAL SITEWORK | | 208d | 01-Aug-22 | 19-May-23 | 6d |
| A1140 | Curb & Gutter | 15d | 01-Aug-22 | 19-Aug-22 | 115d |
| A1150 | Paving | 10d | 22-Aug-22 | 02-Sep-22 | 138d |
| A1160 | Hardscapes | 15d | 14-Mar-23 | 07-Apr-23 | 6d |
| A2010 | Site Fencing | 20d | 14-Mar-23 | 14-Apr-23 | 24d |
| A1170 | Landscape / Pasture - Section B | 7d | 30-Mar-23 | 11-Apr-23 | 6d |
| A2580 | Landscape / Pasture - Section A | 7d | 11-Apr-23 | 20-Apr-23 | 6d |
| A2590 | Landscape / Pasture - Section D | 7d | 20-Apr-23 | 01-May-23 | 6d |
| A2570 | Landscape / Pasture - Section C | 7d | 01-May-23 | 10-May-23 | 6d |
| A1340 | Final Site Inspection | 7d | 10-May-23 | 19-May-23 | 6d |
| STRUCTURE | | 184d | 30-Jun-22 | 14-Apr-23 | 16d |
| SECTOR B | | 105d | 30-Jun-22 | 25-Nov-22 | 5d |
| B-100 | Foundations | 15d | 30-Jun-22 | 21-Jul-22 | 0d |
| B-110 | U/G Rough-In - Pour 1 | 10d | 07-Jul-22 | 21-Jul-22 | 0d |
| B-120 | Below Grade CMU | 15d | 07-Jul-22 | 28-Jul-22 | 0d |
| B-130 | Slab on Grade/CIP Concrete Wall - Pour 1 - A.... | 10d | 21-Jul-22 | 04-Aug-22 | 0d |
| B-140 | U/G Rough-In - Pour 2 | 10d | 21-Jul-22 | 04-Aug-22 | 4d |
| B-150 | U/G Rough-In - Pour 3 | 10d | 04-Aug-22 | 18-Aug-22 | 4d |
| B-160 | Slab on Grade/CIP Concrete Wall - Pour 2 - C-... | 10d | 04-Aug-22 | 18-Aug-22 | 0d |
| B-170 | Load Bearing CMU Walls - Pour 1 (Includes Ex... | 15d | 18-Aug-22 | 08-Sep-22 | 0d |
| B-180 | Slab on Grade/CIP Concrete Wall - Pour 3 - C-... | 10d | 18-Aug-22 | 01-Sep-22 | 30d |
| B-190 | Load Bearing CMU Walls - Pour 2 (Includes Ex... | 15d | 08-Sep-22 | 29-Sep-22 | 0d |
| B-200 | Steel Columns & Beams | 15d | 29-Sep-22 | 20-Oct-22 | 10d |
| B-210 | Load Bearing CMU Walls - Pour 3 (Includes Ex... | 20d | 29-Sep-22 | 27-Oct-22 | 0d |
| B-220 | Steel Joists & Roof Deck | 20d | 27-Oct-22 | 25-Nov-22 | 5d |
| SECTOR A | | 115d | 21-Jul-22 | 10-Jan-23 | 0d |
| A-100 | Foundations | 15d | 21-Jul-22 | 11-Aug-22 | 4d |
| A-110 | Below Grade CMU | 15d | 04-Aug-22 | 25-Aug-22 | 9d |
| A-120 | U/G Rough-In - Pour 1 | 10d | 04-Aug-22 | 18-Aug-22 | 4d |
| A-130 | Slab on Grade/CIP Concrete Wall - Pour 1 - A-... | 10d | 18-Aug-22 | 01-Sep-22 | 9d |
| A-140 | U/G Rough-In - Pour 2 | 10d | 18-Aug-22 | 01-Sep-22 | 4d |
| A-150 | Slab on Grade/CIP Concrete Wall - Pour 2 - C-... | 10d | 01-Sep-22 | 15-Sep-22 | 25d |
| A-160 | U/G Rough-In - Pour 3 | 10d | 01-Sep-22 | 15-Sep-22 | 4d |
| A-170 | Slab on Grade/CIP Concrete Wall - Pour 3 - C-... | 10d | 15-Sep-22 | 29-Sep-22 | 25d |
| A-180 | Load Bearing CMU Walls - Pour 1 | 15d | 29-Sep-22 | 20-Oct-22 | 0d |



Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 8 of 14


INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|-----------------|--|------------------|------------------|------------------|-------------|
| | | | | | |
| A-200 | Load Bearing CMU Walls - Pour 2 | 15d | 20-Oct-22 | 10-Nov-22 | 0d |
| A-210 | Load Bearing CMU Walls - Pour 3 | 15d | 10-Nov-22 | 05-Dec-22 | 0d |
| A-220 | Steel Joists & Roof Deck | 20d | 05-Dec-22 | 10-Jan-23 | 0d |
| SECTOR D | | 130d | 11-Aug-22 | 08-Mar-23 | 33d |
| D-100 | Foundations | 15d | 11-Aug-22 | 01-Sep-22 | 9d |
| D-110 | Below Grade CMU | 15d | 01-Sep-22 | 22-Sep-22 | 4d |
| D-120 | U/G Rough-In | 20d | 01-Sep-22 | 29-Sep-22 | 4d |
| D-130 | Slab on Grade - Pour 1 - E-F, 10.6-12 | 10d | 22-Sep-22 | 06-Oct-22 | 4d |
| D-140 | Slab on Grade - Pour2 - E-F, 8.7-10.3 | 10d | 06-Oct-22 | 20-Oct-22 | 4d |
| D-150 | Slab on Grade - Pour 3 - E-F, 6.9-8 | 10d | 20-Oct-22 | 03-Nov-22 | 4d |
| D-160 | Load Bearing CMU Walls - Pour 1 | 15d | 27-Oct-22 | 18-Nov-22 | 0d |
| D-170 | Load Bearing CMU Walls - Pour 2 | 15d | 18-Nov-22 | 13-Dec-22 | 0d |
| D-180 | Load Bearing CMU Walls - Pour 3 | 15d | 13-Dec-22 | 10-Jan-23 | 0d |
| D-190 | Steel Joists & Roof Deck | 15d | 10-Jan-23 | 09-Feb-23 | 3d |
| D-200 | Canopy Structure | 15d | 09-Feb-23 | 08-Mar-23 | 30d |
| SECTOR C | | 139d | 01-Sep-22 | 14-Apr-23 | 16d |
| C-100 | Foundations | 15d | 01-Sep-22 | 22-Sep-22 | 29d |
| C-110 | U/G Rough-In - Pour 1 | 15d | 22-Sep-22 | 13-Oct-22 | 19d |
| C-120 | Below Grade CMU | 15d | 22-Sep-22 | 13-Oct-22 | 19d |
| C-130 | U/G Rough-In - Pour 2 | 10d | 13-Oct-22 | 27-Oct-22 | 75d |
| C-140 | Slab on Grade - Pour 1 - E-F, 4.7-6 | 10d | 03-Nov-22 | 18-Nov-22 | 4d |
| C-150 | Slab on Grade - Pour 2 - E-F, 3-4.3 | 10d | 18-Nov-22 | 05-Dec-22 | 60d |
| C-160 | Load Bearing CMU Walls - Pour 1 Zone 1 | 20d | 24-Nov-22 | 29-Dec-22 | 0d |
| C-170 | Load Bearing CMU Walls - Pour 1 - Zone 2 | 15d | 29-Dec-22 | 27-Jan-23 | 0d |
| C-180 | Load Bearing CMU Walls - Pour 2 | 15d | 27-Jan-23 | 27-Feb-23 | 0d |
| C-190 | Steel Joists & Roof Deck | 15d | 27-Feb-23 | 22-Mar-23 | 0d |
| C-200 | Canopy Structure | 15d | 22-Mar-23 | 14-Apr-23 | 16d |
| SKIN | | 157d | 22-Sep-22 | 01-May-23 | 10d |
| SECTOR B | | 152d | 22-Sep-22 | 24-Apr-23 | 15d |
| B-SKN-100 | Exterior Waterproofing - Pour 1 | 10d | 22-Sep-22 | 06-Oct-22 | 5d |
| B-SKN-110 | CMU Veneer - Pour 1 | 10d | 29-Sep-22 | 13-Oct-22 | 25d |
| B-SKN-120 | Exterior Waterproofing - Pour 2 | 10d | 06-Oct-22 | 20-Oct-22 | 5d |
| B-SKN-130 | CMU Veneer - Pour 2 | 10d | 13-Oct-22 | 27-Oct-22 | 25d |
| B-SKN-140 | Exterior Waterproofing - Pour 3 | 10d | 20-Oct-22 | 03-Nov-22 | 5d |
| B-SKN-150 | Storefront/Windows/Doors | 10d | 27-Oct-22 | 10-Nov-22 | 55d |
| B-SKN-160 | CMU Veneer - Pour 3 | 10d | 27-Oct-22 | 10-Nov-22 | 25d |
| B-SKN-170 | Metal Panels | 10d | 25-Nov-22 | 13-Dec-22 | 35d |
| B-SKN-200 | Temporary Roofing | 15d | 25-Nov-22 | 22-Dec-22 | 13d |
| B-SKN-180 | Overhead Doors | 5d | 28-Nov-22 | 02-Dec-22 | 87d |
| B-SKN-190 | Canopies | 5d | 13-Dec-22 | 22-Dec-22 | 45d |
| B-SKN-220 | Roofing/Coping | 15d | 30-Jan-23 | 17-Feb-23 | 45d |



Current
 Progress
 Critical

Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 9 of 14


INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|------------------|---|------------------|-----------|-----------|-------------|
| | | | | | |
| SECTOR A | | | | | |
| A-SKN-100 | Exterior Waterproofing - Pour 1 | 10d | 03-Nov-22 | 18-Nov-22 | 5d |
| A-SKN-110 | CMU Veneer - Pour 1 | 10d | 10-Nov-22 | 25-Nov-22 | 25d |
| A-SKN-120 | Exterior Waterproofing - Pour 2 | 10d | 18-Nov-22 | 05-Dec-22 | 5d |
| A-SKN-130 | CMU Veneer - Pour 2 | 10d | 25-Nov-22 | 13-Dec-22 | 25d |
| A-SKN-140 | Exterior Waterproofing - Pour 3 | 10d | 05-Dec-22 | 22-Dec-22 | 5d |
| A-SKN-160 | Metal Panels | 15d | 13-Dec-22 | 10-Jan-23 | 35d |
| A-SKN-150 | CMU Veneer - Pour 3 | 10d | 13-Dec-22 | 30-Dec-22 | 25d |
| A-SKN-170 | Canopies | 5d | 22-Dec-22 | 30-Dec-22 | 45d |
| A-SKN-190 | Composite Wood Trellis | 5d | 10-Jan-23 | 20-Jan-23 | 35d |
| A-SKN-220 | Temporary Roofing | 15d | 10-Jan-23 | 09-Feb-23 | 3d |
| A-SKN-180 | Cold Formed Metal Framing/Sheathing/Wate... | 10d | 10-Jan-23 | 30-Jan-23 | 10d |
| A-SKN-200 | Curtainwall/Storefront/Doors | 10d | 30-Jan-23 | 17-Feb-23 | 10d |
| A-SKN-230 | Metal Panel Soffit | 5d | 09-Feb-23 | 17-Feb-23 | 20d |
| A-SKN-210 | HP Laminate | 10d | 17-Feb-23 | 08-Mar-23 | 10d |
| A-SKN-240 | Roofing/Coping | 15d | 17-Feb-23 | 16-Mar-23 | 39d |
| SECTOR D | | | | | |
| D-SKN-100 | Exterior Waterproofing - Pour 1 | 10d | 22-Dec-22 | 10-Jan-23 | 5d |
| D-SKN-110 | CMU Veneer - Pour 1 | 10d | 30-Dec-22 | 20-Jan-23 | 25d |
| D-SKN-120 | Exterior Waterproofing - Pour 2 | 10d | 10-Jan-23 | 30-Jan-23 | 5d |
| D-SKN-130 | CMU Veneer - Pour 2 | 10d | 20-Jan-23 | 09-Feb-23 | 25d |
| D-SKN-140 | Exterior Waterproofing - Pour 3 | 10d | 30-Jan-23 | 17-Feb-23 | 5d |
| D-SKN-150 | Roofing | 10d | 09-Feb-23 | 28-Feb-23 | 3d |
| D-SKN-160 | CMU Veneer - Pour 3 | 10d | 09-Feb-23 | 28-Feb-23 | 25d |
| D-SKN-170 | Storefront/Windows/Doors | 10d | 17-Feb-23 | 08-Mar-23 | 10d |
| D-SKN-180 | Exterior Kennel CMU | 5d | 07-Apr-23 | 14-Apr-23 | 1d |
| D-SKN-190 | Metal Canopy | 5d | 14-Apr-23 | 21-Apr-23 | 1d |
| SECTOR C | | | | | |
| C-SKN-100 | Exterior Waterproofing - Pour 1 | 10d | 17-Feb-23 | 08-Mar-23 | 5d |
| C-SKN-110 | CMU Veneer - Pour 1 | 10d | 28-Feb-23 | 16-Mar-23 | 5d |
| C-SKN-120 | Storefront/Windows/Doors | 10d | 08-Mar-23 | 23-Mar-23 | 10d |
| C-SKN-130 | Exterior Waterproofing - Pour 2 | 10d | 08-Mar-23 | 23-Mar-23 | 5d |
| C-SKN-140 | CMU Veneer - Pour 2 | 10d | 16-Mar-23 | 31-Mar-23 | 5d |
| C-SKN-150 | Roofing | 10d | 22-Mar-23 | 07-Apr-23 | 1d |
| C-SKN-160 | Exterior Waterproofing - Pour 3 | 10d | 23-Mar-23 | 10-Apr-23 | 5d |
| C-SKN-170 | CMU Veneer - Pour 3 | 10d | 31-Mar-23 | 17-Apr-23 | 5d |
| C-SKN-180 | Exterior Kennel CMU | 5d | 17-Apr-23 | 24-Apr-23 | 5d |
| C-SKN-190 | Metal Canopy | 5d | 24-Apr-23 | 01-May-23 | 5d |
| INTERIORS | | | | | |
| SECTOR B | | | | | |
| B-INT-100 | Mech Rough-In - Overhead | 7d | 28-Nov-22 | 06-Dec-22 | 19d |



Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 10 of 14

INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float | Gantt Chart | | | | | | | | | | | | | | | | | | | | | | | |
|---------------------------|--|------------------|------------------|------------------|-------------|---|-----|------|-----|-----|-----|-----|-----|-----|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | | | | | 2021 | | 2022 | | | | | | | | 2023 | | | | | | | | | | | | | |
| | | | | | | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct |
| B-INT-110 | Elec Rough-In - Overhead | 7d | 01-Dec-22 | 09-Dec-22 | 19d | ■ Elec Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-120 | Plumb Rough-In - Overhead | 7d | 01-Dec-22 | 09-Dec-22 | 19d | ■ Plumb Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-130 | Fire S. Rough-In - Overhead | 7d | 01-Dec-22 | 09-Dec-22 | 19d | ■ Fire S. Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-210 | Electrical Room Build Out | 20d | 22-Dec-22 | 24-Jan-23 | 42d | ■ Electrical Room Build Out | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-220 | Mechanical Room Build-Out - OH Rough | 10d | 22-Dec-22 | 09-Jan-23 | 37d | ■ Mechanical Room Build-Out - OH Rough | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-140 | Interior Framing | 10d | 22-Dec-22 | 09-Jan-23 | 11d | ■ Interior Framing | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-150 | Plumbing Wall Rough | 6d | 29-Dec-22 | 09-Jan-23 | 16d | ■ Plumbing Wall Rough | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-160 | Elec Wall Rough | 6d | 29-Dec-22 | 09-Jan-23 | 16d | ■ Elec Wall Rough | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-270 | Mechanical Room Build-Out - Set Equipment | 5d | 09-Jan-23 | 17-Jan-23 | 37d | ■ Mechanical Room Build-Out - Set Equipment | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-170 | MEP Wall Cover Inspection | 5d | 09-Jan-23 | 17-Jan-23 | 16d | ■ MEP Wall Cover Inspection | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-180 | Hard Ceiling Framing | 5d | 09-Jan-23 | 17-Jan-23 | 14d | ■ Hard Ceiling Framing | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-230 | Drywall Hang/Tape/Finish | 8d | 17-Jan-23 | 27-Jan-23 | 16d | ■ Drywall Hang/Tape/Finish | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-290 | Mechanical Room Build-Out - Connect Equip... | 15d | 17-Jan-23 | 07-Feb-23 | 37d | ■ Mechanical Room Build-Out - Connect Equipment | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-190 | Hard Ceiling Rough Ins | 5d | 17-Jan-23 | 24-Jan-23 | 14d | ■ Hard Ceiling Rough Ins | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-200 | Hard Ceiling Inspections | 5d | 24-Jan-23 | 31-Jan-23 | 14d | ■ Hard Ceiling Inspections | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-310 | Mechanical Unit Start-Up | 5d | 25-Jan-23 | 31-Jan-23 | 41d | ■ Mechanical Unit Start-Up | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-240 | Freezer | 10d | 27-Jan-23 | 10-Feb-23 | 36d | ■ Freezer | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-250 | Wall Tile | 10d | 27-Jan-23 | 10-Feb-23 | 51d | ■ Wall Tile | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-260 | Hard Ceiling H/T/F | 5d | 31-Jan-23 | 07-Feb-23 | 14d | ■ Hard Ceiling H/T/F | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-280 | Prime and First Coat | 10d | 07-Feb-23 | 21-Feb-23 | 14d | ■ Prime and First Coat | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-300 | Flooring - Resinous | 15d | 10-Feb-23 | 03-Mar-23 | 36d | ■ Flooring - Resinous | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-320 | Paint - Final Coat | 5d | 21-Feb-23 | 28-Feb-23 | 14d | ■ Paint - Final Coat | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-330 | ACT Grid | 5d | 28-Feb-23 | 07-Mar-23 | 14d | ■ ACT Grid | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-340 | MEPF to Grid (breakout) | 5d | 07-Mar-23 | 14-Mar-23 | 14d | ■ MEPF to Grid (breakout) | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-350 | Cover Up ACT Inspections | 3d | 14-Mar-23 | 17-Mar-23 | 14d | ■ Cover Up ACT Inspections | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-360 | Acoustical Ceiling Tile | 5d | 17-Mar-23 | 24-Mar-23 | 14d | ■ Acoustical Ceiling Tile | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-370 | Millwork | 5d | 24-Mar-23 | 31-Mar-23 | 21d | ■ Millwork | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-380 | Fiberglass Reinforced Panels | 5d | 24-Mar-23 | 31-Mar-23 | 21d | ■ Fiberglass Reinforced Panels | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-390 | Mech Trim | 12d | 24-Mar-23 | 11-Apr-23 | 21d | ■ Mech Trim | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-400 | Flooring - Carpet Tile | 5d | 24-Mar-23 | 31-Mar-23 | 14d | ■ Flooring - Carpet Tile | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-410 | Caging | 7d | 24-Mar-23 | 04-Apr-23 | 29d | ■ Caging | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-420 | Plumb Trim | 12d | 29-Mar-23 | 14-Apr-23 | 21d | ■ Plumb Trim | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-430 | Elec Trim | 12d | 31-Mar-23 | 18-Apr-23 | 19d | ■ Elec Trim | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-440 | Fire S. Trim | 10d | 31-Mar-23 | 14-Apr-23 | 21d | ■ Fire S. Trim | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-450 | Doors and Hardware | 5d | 31-Mar-23 | 07-Apr-23 | 26d | ■ Doors and Hardware | | | | | | | | | | | | | | | | | | | | | | | |
| B-INT-460 | Test and Balance | 10d | 11-Apr-23 | 25-Apr-23 | 21d | ■ Test and Balance | | | | | | | | | | | | | | | | | | | | | | | |
| Restrooms Sector B | | 53d | 22-Dec-22 | 07-Mar-23 | 49d | Restrooms Sector B | | | | | | | | | | | | | | | | | | | | | | | |
| B-RR-100 | Wall Furring/Framing | 5d | 22-Dec-22 | 30-Dec-22 | 49d | ■ Wall Furring/Framing | | | | | | | | | | | | | | | | | | | | | | | |
| B-RR-110 | Wall Rough Ins | 5d | 30-Dec-22 | 09-Jan-23 | 49d | ■ Wall Rough Ins | | | | | | | | | | | | | | | | | | | | | | | |
| B-RR-120 | Wall Cover Inspection | 5d | 09-Jan-23 | 17-Jan-23 | 49d | ■ Wall Cover Inspection | | | | | | | | | | | | | | | | | | | | | | | |
| B-RR-130 | Ceiling Framing | 5d | 17-Jan-23 | 24-Jan-23 | 49d | ■ Ceiling Framing | | | | | | | | | | | | | | | | | | | | | | | |
| B-RR-140 | Ceiling Rough | 5d | 24-Jan-23 | 31-Jan-23 | 49d | ■ Ceiling Rough | | | | | | | | | | | | | | | | | | | | | | | |

Current
 Progress
 Critical

Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 11 of 14


INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|---------------------------|---------------------------------|------------------|------------------|------------------|-------------|
| | | | | | |
| B-RR-160 | Drywall Hang/Tape/Finish | 5d | 07-Feb-23 | 14-Feb-23 | 49d |
| B-RR-170 | Paint | 5d | 14-Feb-23 | 21-Feb-23 | 49d |
| B-RR-180 | Tile | 5d | 21-Feb-23 | 28-Feb-23 | 49d |
| B-RR-190 | Toilet Fixtures and Accessories | 5d | 28-Feb-23 | 07-Mar-23 | 49d |
| SECTOR A | | 96d | 10-Jan-23 | 24-May-23 | 0d |
| A-INT-100 | Mech Rough-In - Overhead | 8d | 10-Jan-23 | 23-Jan-23 | 0d |
| A-INT-110 | Elec Rough-In - Overhead | 8d | 12-Jan-23 | 25-Jan-23 | 0d |
| A-INT-120 | Plumb Rough-In - Overhead | 8d | 12-Jan-23 | 25-Jan-23 | 0d |
| A-INT-130 | Fire S. Rough-In - Overhead | 8d | 12-Jan-23 | 25-Jan-23 | 0d |
| A-INT-200 | Mechanical Unit Start-Up | 5d | 25-Jan-23 | 01-Feb-23 | 41d |
| A-INT-140 | Interior Framing | 10d | 25-Jan-23 | 08-Feb-23 | 0d |
| A-INT-370 | Elect Wall Rough Ins | 6d | 31-Jan-23 | 08-Feb-23 | 0d |
| A-INT-380 | Plumbing Wall Rough Ins | 6d | 31-Jan-23 | 08-Feb-23 | 0d |
| A-INT-150 | Hard Ceiling Framing | 5d | 08-Feb-23 | 15-Feb-23 | 0d |
| A-INT-390 | MEP Wall Cover Up Inspections | 5d | 08-Feb-23 | 15-Feb-23 | 0d |
| A-INT-190 | Drywall - Hang/Tape/Finish | 10d | 15-Feb-23 | 01-Mar-23 | 0d |
| A-INT-160 | Hard Ceiling Rough Ins | 5d | 15-Feb-23 | 22-Feb-23 | 0d |
| A-INT-170 | Hard Ceiling Inspections | 5d | 22-Feb-23 | 01-Mar-23 | 0d |
| A-INT-220 | Wall Tile | 10d | 01-Mar-23 | 15-Mar-23 | 28d |
| A-INT-230 | Hard Ceiling H/T/F | 5d | 01-Mar-23 | 08-Mar-23 | 0d |
| A-INT-180 | Plank Ceiling | 5d | 01-Mar-23 | 08-Mar-23 | 13d |
| A-INT-210 | Prime/1st Coat | 5d | 08-Mar-23 | 15-Mar-23 | 0d |
| A-INT-240 | Paint | 5d | 15-Mar-23 | 22-Mar-23 | 0d |
| A-INT-250 | Flooring - Resinous | 15d | 15-Mar-23 | 05-Apr-23 | 8d |
| A-INT-260 | ACT Grid | 5d | 22-Mar-23 | 29-Mar-23 | 0d |
| A-INT-400 | MEFP to Grid | 5d | 29-Mar-23 | 05-Apr-23 | 0d |
| A-INT-310 | Doors and Hardware | 5d | 31-Mar-23 | 07-Apr-23 | 26d |
| A-INT-410 | Cover Up ACT Inspection | 3d | 05-Apr-23 | 10-Apr-23 | 0d |
| A-INT-270 | Acoustical Ceiling Tile | 5d | 10-Apr-23 | 17-Apr-23 | 0d |
| A-INT-280 | Millwork | 5d | 17-Apr-23 | 24-Apr-23 | 5d |
| A-INT-290 | Fiberglass Reinforced Panels | 5d | 17-Apr-23 | 24-Apr-23 | 0d |
| A-INT-300 | Flooring - Carpet Tile | 5d | 17-Apr-23 | 24-Apr-23 | 3d |
| A-INT-420 | Caging | 7d | 17-Apr-23 | 26-Apr-23 | 13d |
| A-INT-320 | Mech Trim | 12d | 24-Apr-23 | 10-May-23 | 0d |
| A-INT-340 | Elec Trim | 12d | 27-Apr-23 | 15-May-23 | 0d |
| A-INT-330 | Plumb Trim | 12d | 27-Apr-23 | 15-May-23 | 0d |
| A-INT-350 | Fire S. Trim | 10d | 01-May-23 | 15-May-23 | 0d |
| A-INT-360 | Test & Balance | 10d | 10-May-23 | 24-May-23 | 0d |
| Restrooms Sector A | | 50d | 25-Jan-23 | 05-Apr-23 | 28d |
| A-RR-100 | Wall Furring/Framing | 5d | 25-Jan-23 | 01-Feb-23 | 28d |
| A-RR-110 | Wall Rough Ins | 5d | 01-Feb-23 | 08-Feb-23 | 28d |



Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 12 of 14

INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

| 11/12/2021 | | Planned Durat... | Start | Finish | Total Float | 2021 | | | | | | | | | | | | 2022 | | | | | | | | | | | | 2023 | | | | | | | | | | | |
|------------|---------------------------------|------------------|-----------|-----------|-------------|-----------------------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| ID | Name | | | | | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct |
| A-RR-120 | Wall Cover Inspection | 5d | 08-Feb-23 | 15-Feb-23 | 28d | ■ Wall Cover Inspection | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A-RR-130 | Ceiling Framing | 5d | 15-Feb-23 | 22-Feb-23 | 28d | ■ Ceiling Framing | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A-RR-140 | Ceiling Rough | 5d | 22-Feb-23 | 01-Mar-23 | 28d | ■ Ceiling Rough | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A-RR-150 | Ceiling Inspections | 5d | 01-Mar-23 | 08-Mar-23 | 28d | ■ Ceiling Inspections | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A-RR-160 | Drywall Hang/Tape/Finish | 5d | 08-Mar-23 | 15-Mar-23 | 28d | ■ Drywall Hang/Tape/Finish | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A-RR-170 | Paint | 5d | 15-Mar-23 | 22-Mar-23 | 28d | ■ Paint | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A-RR-180 | Tile | 5d | 22-Mar-23 | 29-Mar-23 | 28d | ■ Tile | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A-RR-190 | Toilet Fixtures and Accessories | 5d | 29-Mar-23 | 05-Apr-23 | 28d | ■ Toilet Fixtures and Accessories | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SECTOR D | | 57d | 09-Feb-23 | 01-May-23 | 17d | SECTOR D | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-100 | Mech Rough-In - Overhead | 7d | 09-Feb-23 | 20-Feb-23 | 14d | ■ Mech Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-120 | Plumb Rough-In - Overhead | 7d | 14-Feb-23 | 23-Feb-23 | 14d | ■ Plumb Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-130 | Fire S. Rough-In - Overhead | 7d | 14-Feb-23 | 23-Feb-23 | 14d | ■ Fire S. Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-110 | Elec Rough-In - Overhead | 7d | 14-Feb-23 | 23-Feb-23 | 32d | ■ Elec Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-140 | Mechanical Unit Start-Up | 10d | 23-Feb-23 | 09-Mar-23 | 32d | ■ Mechanical Unit Start-Up | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-150 | Prime Coat/1st Coat | 5d | 28-Feb-23 | 07-Mar-23 | 4d | ■ Prime Coat/1st Coat | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-160 | Paint | 5d | 07-Mar-23 | 14-Mar-23 | 4d | ■ Paint | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-170 | ACT Grid | 5d | 09-Mar-23 | 16-Mar-23 | 4d | ■ ACT Grid | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-210 | Flooring - Resinous | 15d | 14-Mar-23 | 04-Apr-23 | 4d | ■ Flooring - Resinous | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-180 | MEP Rough @ ACT Grid | 5d | 16-Mar-23 | 23-Mar-23 | 4d | ■ MEP Rough @ ACT Grid | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-230 | Mech Trim | 12d | 21-Mar-23 | 06-Apr-23 | 22d | ■ Mech Trim | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-190 | ACT Grid Cover Up Inspection | 3d | 23-Mar-23 | 28-Mar-23 | 4d | ■ ACT Grid Cover Up Inspection | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-270 | Plumb Trim | 12d | 24-Mar-23 | 11-Apr-23 | 24d | ■ Plumb Trim | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-260 | Elec Trim | 12d | 24-Mar-23 | 11-Apr-23 | 22d | ■ Elec Trim | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-250 | Fire S. Trim | 12d | 24-Mar-23 | 11-Apr-23 | 24d | ■ Fire S. Trim | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-200 | Acoustical Ceiling Tile | 5d | 28-Mar-23 | 04-Apr-23 | 4d | ■ Acoustical Ceiling Tile | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-280 | Interior Kennel Installation | 10d | 04-Apr-23 | 18-Apr-23 | 9d | ■ Interior Kennel Installation | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-290 | Test & Balance | 5d | 06-Apr-23 | 13-Apr-23 | 29d | ■ Test & Balance | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-220 | Exterior Kennel Installation | 5d | 14-Apr-23 | 21-Apr-23 | 1d | ■ Exterior Kennel Installation | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D-INT-240 | Flooring - Turf | 5d | 24-Apr-23 | 01-May-23 | 0d | ■ Flooring - Turf | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SECTOR C | | 44d | 14-Mar-23 | 15-May-23 | 7d | SECTOR C | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-100 | Mech Rough-In - Overhead | 7d | 14-Mar-23 | 23-Mar-23 | 9d | ■ Mech Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-110 | Elec Rough-In - Overhead | 7d | 17-Mar-23 | 28-Mar-23 | 9d | ■ Elec Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-120 | Plumb Rough-In - Overhead | 7d | 17-Mar-23 | 28-Mar-23 | 34d | ■ Plumb Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-130 | Fire S. Rough-In - Overhead | 7d | 17-Mar-23 | 28-Mar-23 | 34d | ■ Fire S. Rough-In - Overhead | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-140 | Prime Coat | 5d | 22-Mar-23 | 29-Mar-23 | 0d | ■ Prime Coat | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-160 | Mechanical Unit Start-Up | 10d | 28-Mar-23 | 11-Apr-23 | 9d | ■ Mechanical Unit Start-Up | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-150 | Paint | 5d | 29-Mar-23 | 05-Apr-23 | 0d | ■ Paint | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-230 | Flooring - Resinous | 15d | 04-Apr-23 | 25-Apr-23 | 4d | ■ Flooring - Resinous | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-170 | ACT Grid | 5d | 05-Apr-23 | 12-Apr-23 | 0d | ■ ACT Grid | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-180 | MEP Rough @ ACT Grid | 5d | 12-Apr-23 | 19-Apr-23 | 0d | ■ MEP Rough @ ACT Grid | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-240 | Mech Trim | 12d | 14-Apr-23 | 02-May-23 | 4d | ■ Mech Trim | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C-INT-190 | ACT Grid Cover Up Inspection | 3d | 19-Apr-23 | 24-Apr-23 | 0d | ■ ACT Grid Cover Up Inspection | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 13 of 14


INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY



Exhibit I

11/12/2021

| ID | Name | Planned Durat... | Start | Finish | Total Float |
|---------------------------|------------------------------|------------------|------------------|------------------|-------------|
| | | | | | |
| C-INT-260 | Plumb Trim | 12d | 21-Apr-23 | 09-May-23 | 4d |
| C-INT-270 | Fire S. Trim | 12d | 21-Apr-23 | 09-May-23 | 4d |
| C-INT-210 | Acoustical Ceiling Tile | 5d | 24-Apr-23 | 01-May-23 | 0d |
| C-INT-200 | Exterior Kennel Installation | 5d | 24-Apr-23 | 01-May-23 | 5d |
| C-INT-220 | Flooring - Turf | 5d | 01-May-23 | 08-May-23 | 5d |
| C-INT-280 | Interior Kennel Installation | 10d | 01-May-23 | 15-May-23 | 0d |
| C-INT-290 | Test & Balance | 5d | 02-May-23 | 09-May-23 | 11d |
| BARN CONSTRUCTION | | 133d | 01-Aug-22 | 03-Feb-23 | 71d |
| SITework/UTILITIES | | 5d | 01-Aug-22 | 05-Aug-22 | 162d |
| BARN-100 | Underground Utilities | 5d | 01-Aug-22 | 05-Aug-22 | 143d |
| STRUCTURE | | 44d | 05-Dec-22 | 03-Feb-23 | 71d |
| BARN-110 | Barn SOG | 5d | 05-Dec-22 | 13-Dec-22 | 60d |
| BARN-120 | Pre-Fabricated Structure | 20d | 13-Dec-22 | 20-Jan-23 | 60d |
| BARN-130 | MEP Install | 5d | 20-Jan-23 | 27-Jan-23 | 71d |
| BARN-140 | MEP Inspections | 5d | 27-Jan-23 | 03-Feb-23 | 71d |
| CLOSEOUT | | 40d | 15-May-23 | 10-Jul-23 | 0d |
| A1080 | Final Inspections | 7d | 15-May-23 | 24-May-23 | 0d |
| A1090 | Owner/Arch Punchlist Walk | 10d | 24-May-23 | 08-Jun-23 | 0d |
| A1940 | Punchlist Work | 20d | 08-Jun-23 | 10-Jul-23 | 0d |



Current
 Progress
 Critical
 Milestones
 Summary

DATA DATE: 12-Nov-21
 CURRENT DATE: 12-Nov-21
 PAGE: 14 of 14

INITIAL PREP VIEW
 Fulton County Animal Services Facility
 THE WINTER CONSTRUCTION COMPANY

