

**EXHIBIT "B"**

**Morris Road Concept-1200828 City of Milton**

**MILTON BID**

**WATER MAIN INSTALLATION QUANTITIES & COST ESTIMATE**

PAY ITEM #		ITEM	SIZE	QUANTITY	UNIT		
171	-	0030	TEMPORARY SILT FENCE, TYPE C	200	LF	\$1,000.00	
500	-	3101	CLASS A CONCRETE	5	CY	\$3,750.00	
611	-	8120	ADJUST WATER METER BOX TO GRADE	3	EA	\$2,250.00	
611	-	8140	ADJUST WATER VALVE BOX TO GRADE	8	EA	\$8,160.00	
670	-	1060	WATER MAIN, 6 IN, DIP	6"	100	LF	\$16,500.00
670	-	1080	WATER MAIN, 8 IN, DIP	8"	100	LF	\$18,000.00
670	-	1500	CUT & PLUG OR REMOVE EXISTING WATER MAIN	2	EA	\$4,000.00	
670	-	1900	INLINE PLUG	If Necesarry	1	EA	\$1,500.00
670	-	2500	INSERT VALVE (8" TO 12" DIA)	If Necesarry	1	EA	\$23,309.00
670	-	2080	GATE VALVE, 8 IN	8"	1	EA	\$2,220.00
670	-	2002	VALVE MARKER REMOVE	4	EA	\$1,084.00	
670	-	3087	TAPPING SLEEVE & VALVE ASSEMBLY	6 IN x 6 IN For FH	2	EA	\$21,142.00
670	-	4000	FIRE HYDRANT	W/6" GV	4	EA	\$33,940.00
669	-	5620	WATER SERVICE LINE, 3/4 IN	3/4-inch	50	LF	\$5,050.00
670	-	5010	WATER SERVICE LINE, 1 IN	1-inch	50	LF	\$5,650.00
670	-	5020	WATER SERVICE LINE, 2 IN	2-inch	20	LF	\$3,320.00
670	-	9710	RELOCATE EXITING FIRE HYDRANT	If Necesarry	1	EA	\$2,938.00
670	-	9720	RELOCATE EXITING WATER VALVE, INC BOX	If Necesarry	1	EA	\$1,085.00
670	-	9730	RELOCATE EXITING WATER METER, INC BOX		1	EA	\$1,830.00
670	-	9920	REMOVE EXIST FIRE HYDRANT		3	EA	\$1,950.00
668		3300	SAN SEWER MANHOLE, TYPE 1		2	EA	\$30,000.00
611	-	8050	ADJUST MH TO GRADE		5	EA	\$6,725.00
670	-	9737	REMOVE AND REPLACE EXT. WATER VAULT INCL MEETER AND BYPASS.		2	EA	\$84,640.00
			Note: All pipe fittings & accessories shall be included with pipe (LF) price.			<b>\$280,043.00</b>	
			Task Allowance: (As designated by Fulton County Project Manager)	20%		\$56,008.60	
			<b>TOTAL COST</b>			<b>\$336,051.60</b>	
			Note: No extra payment for traffic control & grading, it will be covered by pipe installation cost				