CHANGE ORDER

No. FOUR (4)

PROJECT: FTY AIRPORT ADMINISTRATION

ARFF BUILDING RENOVATION: PHASE 2

DATE OF ISSUANCE:

1/26/2023

OWNER: Fulton County, Georgia

PROJECT NO.

20ITB126798-JAJ

CONTRACTOR: Trident Construction Group

8125 Roswell Road, Building 100

Atlanta, Georgia 30350

Engineer Project No.

185863

CONTRACTOR FOR: ARFF BUILDING RENOVATION: PHASE 2

PURPOSE OF CHANGE ORDER: To add the following items and quantities to the Contract. You are directed to make the following changes in the Contract Documents: DESCRIPTION:

BASE BID ADDED ITEMS:

SPECIFICATION	BID	UNIT	ESTIMATE	ITEM	ESTIMATE
NO.	ПЕМ	PRICE	QUANTITY	UNIT	COST
02-3010	SITE WORK - ADDITIONAL ROCK EXCAVATION	LS	1	LS	\$126,524.00
02-3010	SITE WORK - FIRE LINE CHANGE PER CITY OF ATLANTA	LS	1	LS	\$20,735.40
15-9900	FIRE PROTECTION - ADDED SCOPE: FIRE SPRINKLER	LS	1	LS	\$19,488.00
06-2300	MILLWORK CHANGES	LS	1	LS	\$2,822.96
06-2300	STAIRWAY LIGHTING	LS	t	LS	\$5,000.00

TOTAL:

\$174,570.36

TOTAL INCREASE BASE BID:

\$174,570.36

CHANGE IN CONTRACT PRICE:	CHANGE IN CONTRACT TIME
Original Contract Price \$2,486,000.00	Original Contract Time <u>Two Hundred and Ten (210) Calendar Davs</u>
Net "Change" from previous Change Orders \$101,717.58	Net "Change" from previous Change Orders One Hundred and Five (105) Calendar Days
Previous Contract Price \$2,587,717.58	Previous Contract Time (Three Hundred and Fifteen (315) Calendar Days)
Net "Change" in this Change Order \$174,570.36	Net "Change", This Change Order (33) Calendar Days
New Contract Price w/approved C.O.'s \$2,762,287.94	New Contract Time w/approved C.O.'s (Three Hundred and Forty Eight (348) Calendar Days)
OWNER: FULTON COUNTY, GEORGIA	CONTRACTOR:
ROBERTS L. PITTS, CHAIRMAN FULTON COUNTY BOARD OF COMISSIONERS ATTEST:	PRESIDENT TRIDENT CONSTRUCTION GROUP ATTEST:
TONYA R. GRIER CLERK TO THE COMMISSION	SECRETARY/ ASSISTANT SECRETARY
(AFFIX COUNTY SEAL) APPROVED AS TO FORM:	(AFFIX CORPORATE SEAL) ATTEST:
AFFROVED AS TO FORM:	ameralostos
OFFICE OF THE COUNTY ATTORNEY	NOTARY PUBLIC
APPROVED AS TO CONTENT:	COUNTY: Detalb Milliam A. CO47
DAVID CLARK, DIRECTOR DEPARTMENT OF PUBLIC WORKS	COMMISSION EXPIRES: (AFFIX NOTARY SEAL)





Trident Construction Group 8125 Roswell Road Building 100 Atlanta, Georgia 30350 Phone: (770) 680-5110 Project: 21-054 - 21-054 ARFF Building Renovation 3965 Aero Drive, NW Atlanta, Georgia 30336

Prime Contract Potential Change Order #009: CE #023 - Rock Removal & Haul

то:	Fulton County Dept of Public Works Attn: James Jones 141 Pryor Street SW Suite 6001 Atlanta, Georgia 30303	FROM:	Trident Construction Group 8215 Roswell Road Building 100 Atlanta, Georgia 30350
PCO NUMBER/REVISION:	009 / 3	CONTRACT:	1 - PO #: 540 20ITB126798K-JAJ
REQUEST RECEIVED FROM:		CREATED BY:	Paul Nielsen (Trident Construction Group)
STATUS:	Pending - In Review	CREATED DATE:	1/10/2023
REFERENCE:		PRIME CONTRACT CHANGE ORDER:	None
FIELD CHANGE:	Yes		
LOCATION:		ACCOUNTING METHOD:	Amount Based
SCHEDULE IMPACT:	28 days	PAID IN FULL:	No
EXECUTED:	No	SIGNED CHANGE ORDER RECEIVED DATE:	
		TOTAL AMOUNT:	\$126,524.00

POTENTIAL CHANGE ORDER TITLE: CE #023 - Rock Removal & Haul

CHANGE REASON: Existing Condition

POTENTIAL CHANGE ORDER DESCRIPTION: (The Contract is Changed As Follows)

CE #023 - Rock Removal & Haul Off

This change order is broken into 2 parts based on the rock excavation/haul-off and the rock hammering required to meet the requirements for site elevations and utility installation. Upon the start of the excavation, it was immediately identified the existing substrate contained rock. Trident immediately notified the airport and received 3rd party documentation to support the findings from Nova. Per Sheet SQ-1/Item 11/GDOT 205/Rock Excavation, Trident's base contract was to include 500 cu/yds. Due to the extent of the "rock excavation" during construction, the total quantity would exceed 500 cu/yds. Trident discussed the process, and it was agreed by all parties Nova would be used to verify the total quantities. In an effort to help mitigate some of the costs, Trident offered three possible solutions, but all were rejected.

- 1. Utilize alternate locations on the airport site to waste material.
- 2. Relocate utility runs to an alternate location to avoid discovered rock areas.
- Utilize the adjacent vacant lot.

Attached is the Rock/Equipment Breakdown, initial Nova report, Nova reports during export to verify quantities and truck tickets.

ATTACHMENTS:

ARFF - Truck Tickets - Rock Export - Combined pdf , 21-054-21-054 ARFF Building Renovation-2022-11-29-2022-12-29.pdf , Daily Field Report 2022-07-05 10289801.pdf , NOVA Daily Field Report 2022-12-19 - 2022-12-22 11408193.pdf , Daily Field Report 2022-10-03 10922914.pdf , Daily Field Report 2022-10-19 11021678.pdf , Daily Field Report 2022-11-18 11215712.pdf , Daily Field Report 2022-07-26 10486081.pdf , Daily Field Report 2022-12-28 11426689.pdf , Rock Removal Breakdown 2023.01.09.pdf

#	Budget Code	Description	Amount
1	02-3010 S.O Site Work.Other	Rock Removal & Haul off	\$103,965.00
2	01-2102 L.O Supervision Other	3 Weeks of GC	\$14,753.00
3	01-1070 O.O Performance Bond.Other		\$1,781.00
4	01-0001 O.O Fee.Other	5%	\$6,025,00





Grand Total:

\$126,524.00

Fulton County Dept of Public Works
Attn: James Jones 141 Pryor Street SW

Suite 6001

Atlanta, Georgia 30303

Trident Construction Group 8215 Roswell Road Building 100

Atlanta, Georgia 30350

SIGNATURE

DATE

SIGNATURE

DATE

SIGNATURE

DATE

Printed On: 1/12/2023 10:44 AM





Trident Construction Group 8125 Roswell Road Building 100 Atlanta, Georgia 30350 Phone: (770) 680-5110 Project: 21-054 - 21-054 ARFF Building Renovation 3965 Aero Drive, NW Atlanta, Georgia 30336

Prime Contract Potential Change Order #010: CE #024 - Fire Line-changes per City of Atlanta

то:	Fulton County Dept of Public Works Attn: James Jones 141 Pryor Street SW Suite 6001	FROM:	Trident Construction Group 8215 Roswell Road Building 100 Atlanta, Georgia 30350
PCO NUMBER/REVISION:	Atlanta, Georgia 30303	CONTRACT:	1 - PO #: 540 20ITB126798K-JAJ
REQUEST RECEIVED FROM:		CREATED BY:	Pete Mancinelli (Trident Construction Group)
STATUS:	Pending - In Review	CREATED DATE:	12/8/2022
REFERENCE:		PRIME CONTRACT CHANGE ORDER:	None
FIELD CHANGE:	No		
LOCATION:		ACCOUNTING METHOD:	Amount Based
SCHEDULE IMPACT:	5 days	PAID IN FULL:	No
EXECUTED:	No	SIGNED CHANGE ORDER RECEIVED DATE:	
		TOTAL AMOUNT:	\$20,735.40

POTENTIAL CHANGE ORDER TITLE: CE #024 - Fire Line-changes per City of Atlanta

CHANGE REASON: Design Development

POTENTIAL CHANGE ORDER DESCRIPTION: (The Contract is Changed As Follows)

Changes per the City of Atlanta CE #024 - Fire Line-changes per City

Description of Change:

Proposal to account for the plan changes noted in the approved utility plan regarding the fire mains.

The Contract will be (Increased) by (5) days as a result of this change order proposal.

- 1) Original plan showed an 8"x4" tapping sleeve and valve. The plans also originally showed one meter vault.
- 2) New plans show upsizing the tapping sleeve to 8"x6" and then a 6" detector check in 5x7 vault was added. The FDC was also moved however this would be no cost to do so.
- 3) Plans point to a 6" detector check however the material list on the side of the stamped drawing approved by Tim Cotton of City of Atlanta shows 4" detector check. Contractor to confirm what is required. Wofford reserves the right to revisit pricing should the city plan reviewer and/or engineer provide further comments.
- 4) Vaults to take 2-3 weeks from time of ordering once materials to be provided by City of Atlanta are received; COA to release materials upon receipt of payment for new service fees from Contractor.
- 5) Material was previously shipped to account for the original plan so we will need to return the 8"x4" tapping sleeve and valve and replace with the new size. 6" DIP will also be needed to make the connection.
- 6) Fire line to reduce down to 4" after the 6" backflow vault.
- 7) Due to not having the vaults ready by the time we would be ready to install the vault in our current mobilization, we will need to demobilize/remobilize once work is approved and new vaults are ready for shipment.

ATTACHMENTS:

COP #05 - Changes to Fire Line Per Approved Plans - 12-2-22.pdf

#	Budget Code	Description	Amount
1	02-3010 S.O Site Work.Other	Fire Line Change-per City	\$18,400.00
2	01-1070 O.O Performance Bond Other		\$276.00
3	01-2102 L.O Supervision.Other		\$1,072.00
4	01-0001 O.O Fee.Other	5%	\$987.40
		Grand Total:	\$20,735.40





Fulton County Dept of Public Works

Attn: James Jones 141 Pryor Street SW Suite 6001

Atlanta, Georgia 30303

Trident Construction Group 8215 Roswell Road Building 100

Atlanta, Georgia 30350

SIGNATURE DATE SIGNATURE DATE SIGNATURE DATE



Change Order Proposal

Date:

12/2/2022

Owner / General Contractor:

Trident Construction Group

Address:

8125 Roswell Road, Bldg 100

Atlanta, GA 30350

Contact Name:
Contact Phone Number:

Pete Mancinelli 470-442-8664

Contact Faone (sumber)

470-442-8004

Project:

ARFF Building

Wofford Project #:

22-005

Change Order Proposal No.

5

Description of Change:

Proposal to account for the plan changes noted in the approved utility plan regarding the fire mains.

Contract Amount:

The Contract will be (Increased) by as a result of this change order proposal.

18,400.00

Contract Time:

The Contract will be (Increased) by (3) days as a result of this change order proposal

Clarifications / Notes:

1) Original plan showed an 8"x4" tapping sleeve and valve. The plans also originally showed one meter vault. 2) New plans show upsizing the tapping sleeve to 8"x6" and then a 6" detector check in 5x7 vault was added. The FDC was also moved however this would be no cost to do so. 3) Plans point to a 6" detector check however the material list on the side of the stamped drawing approved by Tim Cotton of City of Atlanta shows 4" detector check. Contractor to confirm what is required. Wofford reserves the right to revisit pricing should the city plan reviewer and/or engineer provide further comments. 4) Vaults to take 2-3 weeks from time of ordering once materials to be provided by City of Atlanta are received; COA to release materials upon receipt of payment for new service fees from Contractor. 5) Material was previously shipped to account for the original plan so we will need to return the 8"x4" tapping sleeve and valve and replace with the new size. 6" DIP will also be needed to make the connection. 6) Fire line to reduce down to 4" after the 6" backflow vault. 7) Due to not having the vaults ready by the time we would be ready to install the vault in our current mobilization, we will need to demobilize/remobilize once work is approved and new vaults are ready for shipment.

Submitted By:	Date	Approved By	Date:
Tadd Swartz	12/2/2022		

Itemized Change Order Proposal

Breakdown	Qty	Unit	Unit Price	Subtotal	
Labor/Equipment					
L/E - Install Detector Check Vault / Additional Pipe Labor	1	LS	\$ 5,179.50	\$ 5,179.50	
Mobilization Charge	1	EA	\$ 1,500.00	\$ 1,500.00	
Haul Small Aggregate, Wofford Truck	18.5	TN	\$ 12.43	\$ 230.00	
Material / Rental Items					
8"x4" Tapping Sleeve and Valve	-1	EA	\$ 2,281.00	\$ (2,281:00	
4" Vault - Previous Plans (Has not been ordered)	-1	L.S	\$ 13,311,00	\$ (13,311.00	
Restock Fee, 8"x4" Tapping Sleeve and Valve (25% Restock Fee)	1	EA	\$ 570.25	\$ 570.25	
8"x6" Tappling Sleeve and Valve	1	EA	\$ 2,809.00	\$ 2,809 00	
6"x4" Reducer	1	EA	\$ 77.00	\$ 77.00	
6" Mega Lug	2	EA	\$ 62.00	\$ 124 00	
4" Mega Lug	2	EA	\$ 48.00	\$ 9600	
6" DIP	20	LF	\$ 24.99	\$ 499 80	
6" Detector Check in 5x7 Vault	1	EA	\$ 7,686 00	\$ 7,686 00	
6* BFP in Vault	1	EA	\$ 11,621.36	\$ 11,621.36	
#57 Stone - Material Only	18.5	TON	\$ 26.50	\$ 490.25	
				s -	

Sales Tax	8 50%	\$	712 44
 Change O	rder Subtotal	S	16,003.60
Overhead	5%	\$	800.18
Profit	10%	\$	1,600 36
Change Order Total		\$	18,404.14
A	djusted Total	s	18,400,00

1								
\$/HR	43.88	86.13	22.50	10.00	36.40	32.50	45.00	
	15 \$	15 \$	15 \$	15 \$	30 \$	30 \$	15 \$	0
Qty.	1	1	1	1	2	2	1	
Water Labor	Skid Steer	Excavator	Trench Roller	Crew Pick Up	Operator	Laborer	Supervisor	

									Total	Unit Cost	
LS	658.13	1,291.88	337.50	150.00	1,092.00	975.00	675.00	,	5,179.50	5,179.50	
	s	s	s	❖	\$	\$	\$	s	Ş	\$	
1											
5/HR	43.88	86.13	22.50	10.00	36.40	32.50	45.00				
	45	₩.	٠.	₹\$	ŝ	٠	₹.				



a MORSCO brand

Due to the continued cost and supply challenges in the DUCTILE IRON PIPE, PVC and HDPE markets, the pricing of these products will be based solely on the availability at the time of shipment. Also, given the volatility in these markets we will not be responsible for product availability and shipment delays, as they are out of our control. Bid prices should be considered an estimate, materials will only be priced at time of shipment until the current supply chain challenges are resolved. These terms are in leu of our standard terms. We appreciate your partnership.

CUSTOMER NO	QUOTING BRANCH	QUOTE NO	QUOTE DATE	PAGE
223867	FORTILINE LAWRENCEVILLE	6269476	11/11/22	1

CUSTOMER

WOFFORD EARTHWORKS LLC 5995 PARKWAY NORTH BLVD 2ND FL SUITE C - BOX 8 CUMMING, GA 30040

DDO	ILCT.	INFORMATION	
PRU.	リヒレコ	INFORMATION	

ARFF CHANGES

LINE	QTY	UOM	DESCRIPTION	UNIT PRICE	TOTAL PRICE
10	1	EA	**************************************	1,432.0000	1,432.00
20 30 40	1 1 1	EA EA EA	6" MJXF TV O/R T2361-19 L/ACC 562S SCREW VB COMP 24"-36" VLV BOX PROTECTOR RING ROUND CONCRETE	1,146.0000 125.0000 22.0000	1,146.00 125.00 22.00
50 60	1	EA EA	4' CONCRETE MARKER WATER 6" ONE-LOK DIP W/ACC SLDEP6	22.0000 62.0000	22.00 62.00
			6" SINGLE CHECK VAULT		
			SINGLE CHECK PROVIDED BY COA		
130	1	EA	6X4X5(ID) CONCRETE VAULT	5,854.00	5,854.00
150 160 170 180	2 2 2 4	EA EA EA EA	W/ 36"X36" ACCESS HATCH 6" FLGXPE DIP 6'00" 6" FLG ACC KIT FF 1/8" RR 6" MJ LONG SLEEVE C153 6" ONE-LOK DIP W/ACC SLDEP6	653.0000 19.0000 120.0000 62.0000	1,306.00 38.00 240.00 248.00
			BACKFLOW VAULT		
220	1	EA	6X5X5 (ID) CONCRETE VAULT	5,854.0000	5,854.00
240 250	2	EA EA	NO BOTTOM W/ 36"X36" HATCH 6" FLGXPE DIP 6'00" 6" DCDA BFP W/SS BODY OSY 350ASTDA	653.0000 3,745.0000	1,306.00 3,745.00
260 270 280 290 300	2 40 4 4 4	EA FT EA EA EA	VLV PIPE STAND 3/4" ALL THREAD ROD BLACK 3/4"X4-1/2" EYE BOLT 3/4" HEAVY HEX NUT 3/4" FLAT WASHER PLAIN	48.0000 2.8600 3.5800 .5600 .3500	96.00 114.40 14.32 2.24 1.40
320 330	2 4	EA EA	6" MJ LONG SLEEVE C153 6" ONE-LOK DIP W/ACC SLDEP6	120.0000 62.0000	240.00 248.00
	1	AT	L STOCK DELIVERIES ARE SUBJECT TO SI	HIPPING CHARGES	l

ALL STOCK DELIVERIES ARE SUBJECT TO SHIPPING CHARGES

All PVC and HDPE material is quoted for shipment within 7 days of quote/bid date. All other material is quoted for shipment within 30 days of quote/bid date.

After 7 days for PVC and HDPE or 30 days for all other material, ALL quoted prices are subject to review based on current market conditions.

223867	ARFF CHANGES	6269476	11/11/22	2
CUSTOMER NO	JOB NAME	QUOTE NO	QUOTE DATE	PAGE

LINE	QTY	UOM	DESCRIPTION	UNIT PRICE	TOTAL PRICE
			6" METER VAULT		
			COA METERS DOMESTIC LINE,		
400	1	EA	12X6%5(ID) CONCRETE VAULT NO	7,200.0000	7,200.00
100	,	-,	FLOOR W/ 36**X36" ACCESS HATCH		
420	1 40	EA FT	6" DBL CHK BFP W/SS BODY OSY 3/4" ALL THREAD ROD BLACK	3,558.0000	3,558.00
440 450	4 8	EA EA	3/4"X4-1/2" EYE BOLT 3/4" HEAVY HEX NUT	3.5800 .5600	14.32 4.48
460 470 480	2 2 2	EA EA EA	6" OSY GATE VLV FLGXFLG 6" FLG TEE C110 6" FLG 96 C110	674.0000 323.0000 221.0000	1,348.00 646.00 442.00
490 500	3 1	EA EA	6" FLGXPE DIP 6'00" FLGXFLG DIP 2'00"	653.0009 482.0000	1,959.00
510 520 530	1 16 7	EA EA EA	6" STAR ADPT FLG DIP SF406G 6" FLG ACC KIT FF 1/8" RR VLV PIPE STAND	77.0000 19.0000 48.0000	77.00 304.00 336.00
540 \$50	2 4	EA EA	6" MJ LONG SLEEVE C153 6" ONE-LOK DIP W/ACC SLDEP6	120.0000 62.0000	240.00 248.00
			Day Dord Dayle with Hantilian and	10/0	
:			Per Brad Barto with Fortiline on following:	12/2 Via text,	we also need the
				1.99/FT	
			6''x4'' Reducer 1 EA \$7	7.00	
		:			
				Subtotal: Tax: Bid Total:	33,235.56 1,994.15 35,229.71
			ALL STOCK DELIVEDIES ARE SUBJECT T		

ALL STOCK DELIVERIES ARE SUBJECT TO SHIPPING CHARGES

All PVC and HDPE material is quoted for shipment within 7 days of quote/bid date. All other material is quoted for shipment within 30 days of quote/bid date.

After 7 days for PVC and HDPE or 30 days for all other material, ALL quoted prices are subject to review based on current market conditions.

Ent By BBB 11/11/22 15:59:02



INVOICE

a MORSCO company

7025 Northwinds Dr. NW Concord, NC 28027 Payment Inquiries 704-788-9800 22-005 - ARFF 09 - Fire Mains - M T.S. Approved 8-15-22 INVOICE NUMBER: 5748073

BILL OF LADING:

INVOICE DATE: 7/29/22 DUE DATE: 8/27/22

Please Remit Payment To: Fortiline, Inc. PO Box 744053 Atlanta, GA 30384-4053 Federal Tax ID# 57-0819190

Warehouse:

FORTILINE LAWRENCEVILLE 1075 CRIPPLE CREEK DR LAWRENCEVILLE, GA 30043 Telephone: 678-714-9211

Page 1 of 3

SOLD TO

For verification of credits for returned material due to plan changes SHIP TO

WOFFORD EARTHWORKS LLC BOX 8 5995 PARKWAY NORTH BLVD STE C 2ND FL CUMMING GA 30040-1477

L EROM CONTRACT

WOFFORD EARTHWORKS LLC 3965 AERO DRIVE NW ATLANTA, GA 30336-2217

		ITRACT	ÓRDER NÓ	Shirri	NG MET	100	<u> </u>	CUSTOMER	NO	TERMS	
007	57276	328	5748073		ur Truck			223867		NET 30 DAYS	
PO NO			JOB NAME		ЮВ МО		SLS		DUE DATE	SHIP DATE	
ARFF WATE	2	AF	RFF BUILDING		ARFF		BB		8/27/22	7/27/22	
PRODUCT NO			DESCRIPTION		иом	ORDERED	SHIPPED	BACK ORDERED	UNIT PRICE	EXTENDED PRICE	
58HHN	1	VY HEX E # 00930	- · · -		EA	16	16	0	.330	5.28	
472GN		SALV NIF E # 00880			EA	1	1	0	328.000	328.00	
34B9SNL		ASS STR E # 01300	EET 90 NO LEAD)		EA	1	1	0	6.000	6,00	
WIL1950XLT2	LEAD-FI		950XLT2		EA	1	1	0	234.000	234.00	
4CF		P FLG C1 E # 00860	• =		EA	1	1	0	68.000	68.00	
490WBD	90WBD	ER CHEC	K VLV W/BALL DRIP		EA	1	1	0	208.000	208.00	
4212212SIAA		K2-1/2 AN E # 00890	NGLE SIAMESE		EA	1	1	0	117,000	117.00	
212PBC	2 PER P	C BREA ACKAGE E # 00900			EA	2	2	0	3.000	6.00	
588SB		BLACK T E # 0092	HREAD STUD		EA	8	8	0	2.500	20.00	
ROM434CC202NU	54 4X3/4 C	C 202NU	SDL 4.50-5.40		EA	1	1	0	50,000	50.00	
34802		D HYD 2 E # 0129	BURY 802		EA	1	1	0	100.000	100,00	
AYM3474701BQ	NO LEA		CCXQJC 74701BQ		EA	1	1	0	85.000	85.00	

INVOICE



a MORSCO company

7025 Northwinds Dr. NW Concord, NC 28027 Payment Inquiries 704-788-9800

SOLD TO

WOFFORD EARTHWORKS LLC BOX 8 5995 PARKWAY NORTH BLVD STE C 2ND FL CUMMING GA 30040-1477 INVOICE NUMBER: 5748073

BILL OF LADING:

INVOICE DATE: DUE DATE: 7/29/22 8/27/22

Please Remit Payment To: Fortiline, Inc. PO Box 744053 Atlanta, GA 30384-4053 Federal Tax ID# 57-0819190

Warehouse:

FORTILINE LAWRENCEVILLE 1075 CRIPPLE CREEK DR LAWRENCEVILLE, GA 30043 Telephone: 678-714-9211

SHIP TO

WOFFORD EARTHWORKS LLC 3965 AERO DRIVE NW ATLANTA, GA 30336-2217

BRANCH NO	FROM CONTRACT	ORDER NO	SHIPPII	NG METI	нов	1 .	CUSTOMER NO		TERMS
007	5727628	5748073	Ot	ur Truck			223867		NET 30 DAYS
PO NO		JOB NAME	J.	ОВ ИО		SLS	SLS DUE DATE		SHIP DATE
ARFF WATER	R AF	RFF BUILDING	- /	ARFF		BBI	3	8/27/22	7/27/22
PRODUCT NO		DESCRIPTION		иом	ORDERED	SHIPPED	BACK ORDERED	UNIT PRICE	EXTENDED PRICE
AYM3474753Q	3/4" ADPT MIPX NO LEAD BID LINE # 0131			EA	1	1	0	27.0000	27.00
34K60	3/4X60' TYPE K BID LINE # 0132	COPPER TUBING (To be returned)		FT	60	60	0	7.8200	469.20
84H615	8X4 MJ TAP SLV	' F/DI H-615 MUE		EA	1	1	0	1469.0000	1,469.00
1812LF	1" YARD HYD 2	BURY LEAD FREE		EA	1	1	0	185.0000	185.00
DFW1600121	16X22X12 JUMB W/BLACK SOLIE	O BLACK METER BOX		EA	1	1	0	66.0000	66.00
4T236119R	4" MJXF TV O/R BID LINE # 0077	T2361-19 L/ACC 0		EA	1	1	0	812.0000	812.00
562S	562S SCREW VI BID LINE # 0078		!	EA	1	1	0	104.0000	104.00
4CVM	4' CONCRETE M BID LINE # 0080			EA	1	1	0	20.0000	20.00
SLDEP4	4" ONE-LOK DIP BID LINE # 0072	W/ACC SLDEP4 0		EA	9	9	0	48.0000	432.00
SLDEP4	4" ONE-LOK DIP BID LINE # 0072	W/ACC SLDEP4 0		EA	1	1	0	48.0000	48.00
SLDEP4	4" ONE-LOK DIP BID LINE # 0072	W/ACC SLDEP4 0		EA	4	4	0	48.0000	192.00
140	1" SCH40 PVC F BID LINE # 0152			FT	20	20	0	1.2200	24.40
4T51	4" TJ DIP CL51 BID LINE # 0068	0		FT	400	400	0	24.1600	9,664.00
4M9	4" MJ 90 C153			EA	2	2	0	78.0000	156.00

INVOICE



a MORSCO company

7025 Northwinds Dr. NW Concord, NC 28027 Payment Inquiries 704-788-9800

SOLD TO

WOFFORD EARTHWORKS LLC BOX 8 5995 PARKWAY NORTH BLVD STE C 2ND FL CUMMING GA 30040-1477 INVOICE NUMBER: 5748073

BILL OF LADING:

INVOICE DATE: DUE DATE: 7/29/22 8/27/22

Please Remit Payment To:

Fortiline, Inc. PO Box 744053

Atlanta, GA 30384-4053 Federal Tax ID# 57-0819190

Warehouse:

FORTILINE LAWRENCEVILLE 1075 CRIPPLE CREEK DR LAWRENCEVILLE, GA 30043 Telephone: 678-714-9211

SHIP TO

WOFFORD EARTHWORKS LLC 3965 AERO DRIVE NW ATLANTA, GA 30336-2217

BRANCH NO	FROM CONTRAC	T ORDER NO	SHIPPI	ING MET	HOD		CUSTOMER	NO	TERMS
007	5727628	5748073		ur Truck			223867		NET 30 DAYS
PO NO		JOB NAME	1	IOB NO		SLS		DUE DATE	SHIP DATE
ARFF WATE	R	ARFF BUILDING		ARFF		BBI	BACK	8/27/22	7/27/22
PRODUCT NO		DESCRIPTION		UOM	ORDERED	SHIPPED	ORDERED	UNIT PRICE	EXTENDED PRICE
	BID LINE # 0	0690							
4M4	4" MJ 45 C15	3		EA	1	1	0	65.000	65.0
	BID LINE # 0								
4MT	4" MJ TEE C	153		EA	1	1	0	102.000	102.00
	BID LINE # 0							1	
4MT	4" MJ TEE C	153		EA	1	1	0	102.000	102.0
	BID LINE # 0					3			
4MF9	4" MJXFLG 9	n C153		EA	1	1	0	89.000	89.0
	BID LINE # 0								
					1				
					II.				
	/ 20				11 77 1			1	



FORTILINE offers online payments and access to invoice copies for your convenience at http://Fortiline.Billtrust.com.

REGISTER TO ACCESS YOUR ONLINE ACCOUNT AT http://FORTILINE.BILLTRUST.COM

Online Payments, View, and Download Invoices and Statements,

NO RETURNS ACCEPTED WITHOUT PRIOR AUTHORIZATION. AUTHORIZED RETURNS ARE SUBJECT TO RESTOCKING FEES, SPECIAL ORDER ITEMS ARE NOT RETURNABLE. ALL CLAIMS MUST BE FILED WITH THE CARRIER.

For TERMS and CONDITIONS of sale, please visit http://www.fortiline.com

AMOUNT DUE	\$15,253.88
ΓAX	\$1,182.23
REIGHT	\$0.00
OTHER	\$0.00
TOTAL DUE	\$16,436.11

Page 3 of 3





a MORSCO brand

Due to the continued cost and supply challenges in the DUCTILE IRON PIPE, PVC and HDPE markets, the pricing of these products will be based solely on the availability at the time of shipment. Also, given the volatility in these markets we will not be responsible for product availability and shipment delays, as they are out of our control. Bid prices should be considered an estimate, materials will only be priced at time of shipment until the current supply chain challenges are resolved. These terms are in leu of our standard terms. We appreciate your partnership

CUSTOMER NO	QUOTING BRANCH	QUOTE NO	QUOTE DATE	PAGE
223867	FORTILINE LAWRENCEVILLE	6059306	3/30/21	1

CUSTOMER

WOFFORD EARTHWORKS LLC 5995 PARKWAY NORTH BLVD 2ND FL SUITE C - BOX 8 CUMMING, GA 30040

PROJECT INFORMATION

FULTON COUNTY AIRPORT ARFF

LINE	QTY	UOM	DESCRIPTION	UNIT PRICE	TOTAL PRICE

			STORM SEWER		
60 70	40 180	FT FT	8" N12 AASHTO M252 PIPE IB/ST 12" N12 AASHTO M294 PIPE IB/ST	6.7800 8.6700	271.20 1,560.60
			OCS PIPING		
180 190 200	1 1 1	EA EA EA	55"X54"X27" TRASH RACK PLASTIC SOLUTIONS ACCESS DOOR PLASTIC SOL ANTI-VORTEX PLATE	3,886.0000 800.0000 719.0000	3,886.00 800.00 719.00
220 230 240 250 260 270	20 20 1 1 2 2	FT FT EA EA EA	8" SCH40 PVC PIPE BE 8" SCH40 PVC PIPE BE PERF 8" SCH40 DWV 45 HXH 8" SCH40 DWV CAP 8" SCH40 DWV ADPT HXF 8" SCH40 DWV CO PLUG RH	8.3500 12.4000 93.0000 65.0000 68.0000 63.0000	167.00 248.00 93.00 65.00 136.00 126.00
		,	YARD INLETS		
310 320 330	4 4 7	EA EA EA	24" SQ CI GRATE 24" SQ 4-HOLE BASIN 2404 10"&12" UNIV ADPT 2410 W/1800 UNIV ADPT OUTLET RED RING	525.0000 325.0000 32.0000	2,100.00 1,300.00 224.00
340	1	EA	8" UNIV OUTLET ADPT 1888	12.0000	12.00
			PAVING UNDERDRAINS		
380 390 400 410	300 4 2 3	FT EA EA EA	6"X100' SGW PIPE PERF W/SOCK 6" N12 45 0694ST 6" N12 WYE 0681ST 6" N12 SNAP END CAP 0667AA	2.8500 31.0000 40.0000 10.0000	855.00 124.00 80.00 30.00

ALL STOCK DELIVERIES ARE SUBJECT TO SHIPPING CHARGES

All PVC and HDPE material is quoted for shipment within 7 days of quote/bid date. All other material is quoted for shipment within 30 days of quote/bid date. After 7 days for PVC and HDPE or 30 days for all other material, ALL quoted prices are subject to review based on current market conditions.

CUSTOMER NO		JOB NAME	QUOTE NO	QUOTE DATE	PAGE
223867	FULTON COUNTY	AIRPORT ARFF	6059306	3/30/21	2

LINE	QTY	UOM	DESCRIPTION	UNIT PRICE	TOTAL PRICE
			SANITARY SEWER		
470 480 1560	238 1 500	FT EA FT	6" SDR35 PVC SEWER PIPE 2"X1000' SEWER DETECTOR TAPE 12GA COPPER-CLAD STEEL TRACER WIRE BLUE	4.7000 28.0000 .1900	1,118.60 28.00 95.00
		:	CLEANOUT ASSEMBLY		
520 530 540	1 1 1	EA EA EA	6" CI CO W/5-1/2" CS BRS PLUG 6" CPLG CI/PVCXCI/PVC 56-66 6" SDR35 PVC T-WYE GXG	29.0000 15.0000 53.0000	29.00 15.00 53.00
570	1	EA	IF IN TRAFFIC: VB2753 HEX C/O BOX MIAMI	160.0000	160.00
			DUMPSTER PAD DRAIN ASSEMBLY		
610 620 630	1 1 1	EA EA EA	DUMPSTERPAD ACO-620 6" CISP P-TRAP NH 6" CPLG CI/PVCXCI/PVC 56-66	655.0000 95.0000 15.0000	655.00 95.00 15.00
	!		FIRE LINE		
680 690 700 710 720	400 2 1 1 9	FT EA EA EA	4" TJ DIP CL51 4" MJ 90 C153 4" MJ 45 C153 4" MJ TEE C153 4" ONE-LOK DIP W/ACC SLDEP4	22.3900 62.0000 52.0000 82.0000 35.0000	8,956.00 124.00 52.00 82.00 315.00
			TAP ASSEMBLY		
760 770 780 790	1 1 1 1	EA EA EA EA	8X4 MJ TAP SLV F/DI TYLER 4" MJXF TV O/R T2361-19 L/ACC 562S SCREW VB COMP 24"-36" 18X18X4 CONCRETE VLV PAD SQ W/10" HOLE	950.0000 510.0000 48.0000 15.0000	950.00 510.00 48.00 15.00
800 810	1 1	EA EA	4' CONCRETE MARKER WATER 4" ONE-LOK DIP W/ACC SLDEP4	15.0000 35.0000	15.00 35.00
840 850 860 870	1 1 1	EA EA EA EA	FDC ASSEMBLY 4" MJ TEE C153 4" MJXFLG 90 C153 4" COMP FLG C110 4" WAFER CHECK VLV W/BALL DRIP 90WBD	82.0000 71.0000 57.0000 177.0000	82.00 71.00 57.00 177.00
880 890 900	1 1 2	EA EA EA	4"X72" GALV NIPPLE 4X2-1/2X2-1/2 ANGLE SIAMESE 2-1/2 FDC BREAKABLE PLAS CAPS 2 PER PACKAGE	215.0000 117.0000 3.0000	215.00 117.00 6.00
910 920 930	4 8 16	EA EA EA	2 PER FACKAGE 4" ONE-LOK DIP W/ACC SLDEP4 5/8"X8" BLACK THREAD STUD 5/8" HEAVY HEX NUT	35.0000 2.5000 .2500	140.00 20.00 4.00
			Package Sub-total:		889.00

CUSTOMER NO	JOB NAME	QUOTE NO	QUOTE DATE	PAGE
223867	FULTON COUNTY AIRPORT ARFF	6059306	3/30/21	3

LINE	QTY	UOM	DESCRIPTION	UNIT PRICE	TOTAL PRICE
			METER VAULT ASSEMBLY		
			NOTE: CONTRACTOR TO PURCHASE & PICK UP METER FROM CITY OF ATLANTA & DELIVER TO FORTILINE. FORTILINE WILL INSTALL IN VAULT & DELIVER TO SITE W/ ALL OTHER COMPONENTS.		J. J
1090	1	EA	12'X6'X5' (ID) CONCRETE VAULT W/ 36" HATCH NO BOTTOM	8,600.0000	8,600.00
1110	1	EA	4" DBL CHK BFP W/SS BODY OSY 350ASTOSY	1,500.0000	1,500.00
1120 1130 1140 1150 1160 1170 1180 1200 1210 1220 1230 1240	40 4 8 2 2 2 3 1 1 16 7 2 4	FT EA EA EA EA EA EA EA	3/4" ALL THREAD ROD BLACK 3/4"X4-1/2" EYE BOLT 3/4" HEAVY HEX NUT 4" OSY GATE VLV FLGXFLG 4" FLG TEE C110 4" FLG 90 C110 4" FLGXFLG DIP 6'00" 4" FLGXFLG DIP 2'00" 4" STAR ADPT FLG DIP SF404G 4" FLG ACC KIT FF 1/8" RR VLV PIPE STAND 4" MJ LONG SLEEVE C153 4" ONE-LOK DIP W/ACC SLDEP4	2.0000 2.5000 .5000 353.0000 189.0000 104.0000 245.0000 46.0000 10.0000 34.0000 53.0000	80.00 10.00 4.00 706.00 378.00 208.00 735.00 200.00 46.00 160.00 238.00 106.00 140.00
	44	L .	Package Sub-total:		13,111.00
			uning,		To be credited bac
1270 1280	1	EA EA	HOSE BIBB ASSEMBLY 4X3/4 CC 202U SDL 4.50-4.80 3/4" BALL CORP CCXQJC 74701BQ NO LEAD	27.0000 62.0000	27.00 62.00
1290 1300 1310	1 1 1	EA EA EA	3/4 YARD HYD 2' BURY 802 3/4" BRASS STREET 90 NO LEAD 3/4" ADPT MIPXQJC 74753Q	100.0000 6.0000 20.0000	100.00 6.00 20.00
1320	60	FT	NO LEAD 3/4X60' TYPE K COPPER TUBING	6.4000	384.00
			Package Sub-total:		599.00
1350 1360 1370 1380 1390	1 1 1 1	EA EA EA EA	FIRE RISER ASSEMBLY 4" FLGXPE DIP 6'00" 4"X2" TAP BLIND FLG C110 2"X3/4" BRASS HEX BUSH NO LEAD 3/4" HOSE BIBB NO LEAD 4" FLG ACC KIT FF 1/8" RR	245.0000 74.0000 16.0000 7.0000 10.0000	245.00 74.00 16.00 7.00 10.00
1440 1460 1470 1480 1490	1 2 2 2 4	EA EA EA EA	4" FIRE DETECTOR CHECK C/O ATL TO PROVIDE FIRE DETECTOR CHECK. 6'X4'X5' PRECAST CONC VAULT W/ 3'X3' HATCH 4" FLGXPE DIP 6'00" 4" FLG ACC KIT FF 1/8" RR 4" MJ LONG SLEEVE C153 4" ONE-LOK DIP W/ACC SLDEP4	4,600.0000 245.0000 10.0000 53.0000 35.0000	4,600.00 490.00 20.00 106.00 140.00
			Package Sub-total:		5,356.00
	<u> </u>	<u> </u>		<u> </u>	

ALL STOCK DELIVERIES ARE SUBJECT TO SHIPPING CHARGES

All PVC and HDPE material is quoted for shipment within 7 days of quote/bid date. All other material is quoted for shipment within 30 days of quote/bid date.

After 7 days for PVC and HDPE or 30 days for all other material, ALL quoted prices are subject to review based on current market conditions.

CUSTOMER NO	JOB NAME	QUOTE NO	QUOTE DATE	PAGE
223867	FULTON COUNTY AIRPORT ARFF	6059306	3/30/21	4

LINE	QTY	UOM	DESCRIPTION	UNIT PRICE	TOTAL PRICE
		-5011	W = O GREET LON		
1520	20	FT	1" WATER LINE 1" SCH40 PVC PIPE BE	.6500	13.00
1530	1	EA	1" DBL CHK BFP 950XLT2 LEAD-FREE	158.0000	158.00
1540	1	EA	13"X20"X12" JUMBO BOX/CIR LID DFW1600.12.1C	54.0000	54.00
1550	1	EA	1" YARD HYD 2' BURY Y1 WOODFORD	175.0000	175.00
			WOODFORD		
!					
					12
					00
	}				
				Subtotal: Tax:	46,869.40 46.89
				Bid Total:	46,916.29
	<u> </u>		ALL STOCK DELIVERIES ARE SUBJECT T		

ALL STOCK DELIVERIES ARE SUBJECT TO SHIPPING CHARGES

All PVC and HDPE material is quoted for shipment within 7 days of quote/bid date. All other material is quoted for shipment within 30 days of quote/bid date.

After 7 days for PVC and HDPE or 30 days for all other material, ALL quoted prices are subject to review based on current market conditions.

Ent By BBB 2/03/22 20:48:31





Trident Construction Group 8125 Roswell Road Building 100 Atlanta, Georgia 30350 Phone: (770) 680-5110 Project: 21-054 - 21-054 ARFF Building Renovation 3965 Aero Drive, NW Atlanta, Georgia 30336

Prime Contract Potential Change Order #014: CE #028 - Fire Marshall Site Review Comments

то:	Fulton County Dept of Public Works Attn: James Jones 141 Pryor Street SW Suite 6001 Atlanta, Georgia 30303	FROM:	Trident Construction Group 8215 Roswell Road Building 100 Atlanta, Georgia 30350
PCO NUMBER/REVISION:	014 / 0	CONTRACT:	1 - PO #: 540 20ITB126798K-JAJ
REQUEST RECEIVED FROM:		CREATED BY:	Pete Mancinelli (Trident Construction Group)
STATUS:	Pending - In Review	CREATED DATE:	1/5/2023
REFERENCE:		PRIME CONTRACT CHANGE ORDER:	None
FIELD CHANGE:	No		
LOCATION:		ACCOUNTING METHOD:	Amount Based
SCHEDULE IMPACT:		PAID IN FULL:	No
EXECUTED:	No	SIGNED CHANGE ORDER RECEIVED DATE:	
		TOTAL AMOUNT:	\$19,488.00

POTENTIAL CHANGE ORDER TITLE: CE #028 - Fire Marshall Site Review Comments

CHANGE REASON: Client Request

POTENTIAL CHANGE ORDER DESCRIPTION: (The Contract is Changed As Follows)

CE #028 - Fire Marshall Site Review Comments

Add additional sprinkler and fire alarm to adjacent spaces per site review from the Fire Marshal on 11/29/2022

ATTACHMENTS:

A110A Fire Sprinkler & Fire Alarm.pdf , AARF Ph II Renov CO Fire Sprinkler.pdf , Fire Marshal Report 2022-12-02 11-58.pdf

#	Budget Code	Description	Amount
1	15-9900 S.O Fire Protection.Other	Added Scope-Fire Sprinkler	\$15,770.00
2	01-2102 L.O Supervision.Other		\$2,680.00
3	01-1070 O.O Performance Bond.Other		\$237.00
4	01-0001 O.O Fee.Other	5%	\$801.00
		Grand Total:	\$19,488.00

Fulton County Dept of Public Works
Attn: James Jones 141 Pryor Street SW
Suite 6001
Atlanta, Georgia 30303

Trident Construction Group 8215 Roswell Road Building 100

Atlanta, Georgia 30350

SIGNATURE DATE SIGNATURE DATE DATE