

	County Facility	Project Description	Project Cost
1	Quality Living Services	Trench and install up to 180' of 1-1/2" yellow poly gas piping on the right side of the building to supply gas to the heaters. Install up to 100' of 2" threaded gas piping on the roof to provide gas to the kitchen and water heater.	\$39,343.00
2	Lewis Slaton Courthouse and Justice Tower	4" Control valve in the Mechanical Room on the 2 nd floor of Lewis Slaton building is defective and needs replacement. Section between two 4" control valves on the 2 nd floor mezzanine floor of Justice Tower is leaking. This section along with the two valves need replacement. Install a 3" ball valve on the main line from the City water supply to low levels of Lewis Slaton Courthouse, to cut off water without involvement from City (avoids delays in the event of a pipeline break or other repairs in our system)	\$23,169.45
3	Justice Tower	Replace existing 70' of 5" copper pipe, compromised due to electrolytic corrosion, with 4" copper pipe	\$18,000.00
4	Lewis Slaton Courthouse	The back flow preventor that protects domestic water from contaminated and dosed cooling tower water and chilled water is not working and is leaking. This is installed at a height of over 20 feet with no safe way of maintaining or testing. Replacing this device and re-locating it to floor level for easy access and maintenance.	\$36,000.00
5	Justice Tower	Replacing and bringing to ADA compliance the water fountain in the Jury Room of Court Room 7E	\$7,375.00

6	Lewis Slaton Courthouse	Probing and blowing down 6 storm drains in Lewis Slaton Courthouse to check and prevent flooding due to drain back up	\$7,860.00
	Total Costs		\$131,747.45